

CALCULATION ROW	LOCATION	AREAS	661	661	661	661	661	661	661	661	661	661	661	661	661	661	661	
			00501	14000	14000	14000	14000	14000	20020	20000	20020	30020	30120	40080	40080	40080	99000	99000
			MULCH, AS PER PLAN	PERENNIALS, Hemerocallis 'Gentle Shepherd', Clump, #2 CONT.	PERENNIALS, Liatris Spicata 'Blazing Star', Clump, #2 CONT.	PERENNIALS, Sporobolus heterolepis 'Prairie Dropseed', Clump, #2 CONT.	PERENNIALS, Calamagrostis x acutifolia 'Karl Foerster', Clump, #1 CONT.	PERENNIALS, Hemerocallis 'Happy Returns Daylily, Clump, #1 CONT.	DECIDUOUS SHRUB, 18" HEIGHT, Hydrangea quercifolia 'Pee Wee', #3 CONT.	DECIDUOUS SHRUB, 15" HEIGHT, Spiraea japonica 'Tracy', #3 CONT.	DECIDUOUS SHRUB, 18" HEIGHT, Itea virginica 'Virginia Sweetpire', #3 CONT.	EVERGREEN SHRUB, 15" HEIGHT, Juniperus chinensis 'Old Gold', #3 CONT.	EVERGREEN SHRUB, 6' HEIGHT, Thuja Plicata 'Virescens', B&B	DECIDUOUS TREE, 2 1/2" CALIPER, Acer Rebrum 'Red Maple', B&B	DECIDUOUS TREE, 2 1/2" CALIPER, Ulmus Americana 'Valley Forge', B&B	DECIDUOUS TREE, 2 1/2" CALIPER, Pyrus calleryana 'Redspire', B&B	PLANTING, MISC. Narcissus 'Dutch Master', BULB; TOP SIZE	PLANTING, MISC.; PLANTING SOIL MIX
			CU YD	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
		SQ FT	P x 3														P x 18	
		PLANTING P	12 x 27														12 x 27	
ALL CALCULATIONS ARE BASED ON CADD AREAS, LENGTHS, OR COUNTS																		
1	ARBY'S PARKING LOT	187	1.73	63.00	21.00	258.00		87.00			12.00	12.00					10.39	
2	TRAILHEAD	1559	(1) 28.44	16.00	31.00	798.00	34.00	167.00	29.00	31.00	15.00	16.00	9.00	6.00	4.00	236.00	100.61	
WATER STREET																		
3	NORTH CONNECTION																	
4	SOUTH NODE	548.23	5.08				20.00	65.00	5.00	5.00		10.00			1.00	325.00	30.46	
PARK AVENUE																		
5	NORTH NODE	801.3	7.42				31.00	106.00	5.00	10.00		13.00			1.00	518.00	44.52	
6	SOUTH NODE	479.88	4.44				18.00	55.00		5.00		13.00			2.00	295.00	26.66	
7	HANGING ROCK																	
SOUTH STREET																		
8	NORTH NODE	627.69	5.81				28.00	86.00		6.00		13.00			2.00	322.00	34.87	
9	SOUTH NODE	878.61	8.14					69.00		20.00		43.00			2.00	340.00	48.81	
10	101+06	104+68	13.67					160.00								820.00	82.03	
11	GREENWAY DRIVE		11.67							12.00		34.00					70.05	
Notes: (1) add 2 CY for each tree outside of planting areas. 7 Total trees @ 2 CY each = 14 CY add (2) add 2 CY for each tree outside of planting areas. 7 trees total @ 2 CY each = 14 CY add																		
SUBTOTALS			86.40	79.00	52.00	1056.00	131.00	795.00	39.00	89.00	27.00	120.00	34.00	9.00	6.00	12.00	2856.00	448.40
TOTALS CARRIED TO GENERAL SUMMARY			86	79	52	1056	131	795	39	89	27	120	34	9	6	12	2856	449