SHEET NUMBER								PARTICIPATION	ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
OC	4	5	8	24	32	33	34	01/NHS/CV						
													ROADWAY	
	LUMP							LUMP	201	11000	LUMP		CLEARING AND GRUBBING	4
940								940	202	23001	940	SY	PAVEMENT REMOVED, AS PER PLAN	4
				87				87	202	32000	87	FT	CURB REMOVED	
				133				133	202	35100	133	FT	PIPE REMOVED, 24" AND UNDER	
				2				2	202	58100	2	EACH	CATCH BASIN REMOVED	
				24				24	SPECIAL	20270000	24	FT	FILL AND PLUG EXISTING CONDUIT	5
				232				232	202	75000	232	FT	FENCE REMOVED	
					464			464	203	10000	464	CY	EXCAVATION	
					342			342	203	20000	342	CY	EMBANKMENT	
1094								1094	204	10000	1094	SY	SUBGRADE COMPACTION	
	1							1	204	45000	1	HOUR	PROOF ROLLING	
				192				192	607	98000	192	FT	FENCE, MISC.: TEMPORARY FENCE	4
													EROSION CONTROL	
		4						4	601	21050	4	SY	TIED CONCRETE BLOCK MAT, TYPE 1	
						52		52	601	32000	52	CY	ROCK CHANNEL PROTECTION, TYPE A WITH FILTER	
				4				4	601	32100	4	CY	ROCK CHANNEL PROTECTION, TYPE B WITH FILTER	
		197						197	659	00300	197	CY	TOPSOIL	
		1772						1772	659	10000	1772	SY	SEEDING AND MULCHING	
		0.24						0.24	659	20000	0.24	TON	COMMERCIAL FERTILIZER	
		0.37						0.37	659	31000	0.37	ACRE	LIME	
		10						10	659	35000	10	MGAL	WATER	
								2000	832	30000	2000	EACH	EROSION CONTROL	
													ENVIRONMENTAL / REMEDIATION	
		150						150	SPECIAL	69065016	150	TON	WORK INVOLVING PETROLEUM CONTAMINATED SOIL	5
		500						500	SPECIAL	69065020	500	GAL	WORK INVOLVING WATER	5
		500						500	SPECIAL	69065024	500	GAL	WORK INVOLVING REGULATED WATER	5
													DRAINAGE	
				1.2		1.7		2.9	602	20000	2.9	CY	CONCRETE MASONRY	
		20						20	605	13300	20	FT	6" UNCLASSIFIED PIPE UNDERDRAINS	
		150						150	611	01400	150	FT	6" CONDUIT, TYPE E	
		20						20	611	01500	20	FT	6" CONDUIT, TYPE F	
				57				57	611	04400	57	FT	12" CONDUIT, TYPE B	
				50				50	611	04600	50	FT	12" CONDUIT, TYPE C	
				69				69	611	06100	69	FT	15" CONDUIT, TYPE C	
				28				28	611	09100	28	FT	21" CONDUIT, TYPE C	
						106		106	611	53000	106	FT	38" X 60" CONDUIT, TYPE A, 706.04	
				1				1	611	98150	1	EACH	CATCH BASIN, NO. 3	
				1				1	611	98470	1	EACH	CATCH BASIN, NO. 2-2B	
				3				3	611	99574	3	EACH	MANHOLE, NO. 3	
		2						2	611	99710	2	EACH	PRECAST REINFORCED CONCRETE OUTLET	
													PAVEMENT	
243								243	301	46000	243	CY	ASPHALT CONCRETE BASE, PG64-22	
176								176	304	20000	176	CY	AGGREGATE BASE	
155								155	407	10000	155	GAL	TACK COAT	
79								79	441	50000	79	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
				87				87	609	26000	87	FT	CURB, TYPE 6	
													TRAFFIC CONTROL	
							29	29	621	00100	29	EACH	RPM	
							13	13	621	54000	13	EACH	RAISED PAVEMENT MARKER REMOVED	
							26.0	26.0	630	02100	26.0	FT	GROUND MOUNTED SUPPORT, NO. 2 POST	
							14.0	14.0	630	03100	14.0	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
							19.0	19.0	630	80100	19.0	SF	SIGN, FLAT SHEET	
							3	3	630	84900	3	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
							3	3	630	86002	3	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
							0.45	0.45	644	00104	0.45	MILE	EDGE LINE, 6"	
							0.22	0.22	644	00300	0.22	MILE	CENTER LINE	
							235	235	644	00404	235	FT	CHANNELIZING LINE, 12"	

OC = OFFICE CALCS

CALCULATED PRS
CHECKED PEK

GENERAL SUMMARY

GEA-422-14.90

pw:\\gfnet-pw.bentley.com:gfnet-pw-01\Documents\Projects\63152\105821\Roadway\sheets\105821_GG001.dgn Sheet1 4/6/2021 9:54:57 AM prschroeder