BEGIN PROJECT
STA. 0+00.00
S.L.M. = 0.00

E260178

STA. 0+00.00 AH

STA. 406+60.04 BK =

LAKE COUNTY
GEAUGA COUNTY

MONUMENT ASSEMBLY
ADJUSTED TO GRADE

7' x 4' CULVERT
CFN 1900815
NO WORK

36" CULVERT
CFN 1977460
NO WORK

PC STA. 2+06.09

PT STA. 6+57.62

18" CULVERT
CFN 1820897
TO BE REPLACED BY OTHERS
ON PID 116938

CUTTY SARK DR.

CURVE DATA
P.I. = STA. 4+32.28
Δ = 08°37'25" RT
Dc = 01°54'35"
R = 3,000.00'
T = 226.19'
L = 451.53'
E = 8.51'

CURVE DATA
P.I. = STA. 37+08.62
Δ = 19°29'06" LT
Dc = 05°43'46"
R = 1,000.00'
T = 171.70'
L = 340.08'
E = 14.63'

PC STA. 35+36.92

PT STA. 38+77.00

12" CULVERT
CFN 1820898
NO WORK

ARROW LN.

3' X 2' CULVERT
CFN 1820899
NO WORK

12" CULVERT
CFN 1280900
NO WORK

PC STA. 51+48.61

PT STA. 58+38.69

COTTAGE HILL LN.

CURVE DATA
P.I. = STA. 54+93.72
Δ = 02°43'37" RT
Dc = 00°23'43"
R = 14,500.00'
T = 345.11'
L = 690.08'
E = 4.11'

12" CULVERT
CFN 1820901
NO WORK

12" CULVERT
CFN 1820902
NO WORK

CURVE DATA
P.I. = STA. 87+68.85
Δ = 54°29'34" RT
Dc = 11°00'41"
R = 520.33'
T = 267.95'
L = 494.88'
E = 64.94'

KIRTLAND-CHARDON RD.

12" CULVERT
CFN 1820903
NO WORK

PC STA. 89+95.78

PT STA. 85+00.90

MATCH LINE STA. 95+00

HORIZONTAL
SCALE IN FEET
0 200 400 800

PLAN SPLIT 1
STA. 101+37.60
S.L.M. = 1.92
01/STR

PLAN SPLIT 2
STA. 101+37.60
S.L.M. = 1.92
02/S5K

MATCH LINE STA. 95+00

36" CULVERT
CFN 1977461
NO WORK

3' X 2' CULVERT
CFN 1820905
NO WORK

12" CULVERT
CFN 1820910
NO WORK

12" CULVERT
CFN 1820906
NO WORK

SHASTA DR.

WILDER DR.

CALICO LN.

FINCHERIE DR.

FOX DR.

HENNING DR.

15" CULVERT
CFN 1820904
NO WORK

CURVE DATA
P.I. = STA. 151+44.37
Δ = 24°08'40" LT
Dc = 07°09'43"
R = 800.00'
T = 171.10'
L = 337.12'
E = 18.09'

PC STA. 149+73.27

BRANCH OF
CHAGRIN RIVER

PT STA. 153+10.39

AUBURN RD. (C.R. 4)

4' X 3' CULVERT
CFN 1820909
NO WORK

12" CULVERT
CFN 1820908
NO WORK

MONUMENT ASSEMBLY
ADJUSTED TO GRADE

6' X 4' CULVERT
CFN 1820907
BRANCH OF CHAGRIN RIVER
NO WORK

END PROJECT
STA. 184+42.00
S.L.M. = 3.50

E260178

CITY OF CHARDON
CHARDON TOWNSHIP

TWP.

CITY OF CHARDON

CHARDON TOWNSHIP

SCHEMATIC PLAN
U.S.-6, STA. 401+60.04 TO STA. 195+00

DESIGN AGENCY

DESIGNER KDH
REVIEWER DAB 02/26/26
PROJECT ID 117181
SHEET P.02 TOTAL 23

GEA-6-0.00

MODEL: CLX_U006 - Plan 1 [Sheet] PAPERSIZE: 34x22 (in.) DATE: 11/16/2026 TIME: 1:04:57 PM PLTDRV: OHDOT_PDF.pltcfg PENTBL: OHDOT_Pen.tbl USER: Keith.Hamilton@dot.ohio.gov WORKSPACE: OHDOTCivil02 WORKSET: 117181 PRODUCT: OpenRoadsDesigner 24.00.00.205
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 12\Geauga\117181\400-Engineering\Roadway\Sheets\117181_GB001.dgn