

REF. NO.	SHEET NO.	PLAN SPLIT NO.	STATION TO STATION	LENGTH	BEGIN WIDTH	ENDING WIDTH	AVERAGE WIDTH	AREA			209	441	254	407		617	874		
											LINEAR GRADING, AS PER PLAN	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446), AS PER PLAN, 1-1/2"	PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN, 1.5"	NON-TRACKING TACK COAT	COMPACTED AGGREGATE, AS PER PLAN	LONGITUDINAL JOINT PREPARATION			
				FT.	FT.	FT.	FT.	SQ. YD.			MILE	CY	SY	GAL		CY	FT		
			<u>S.R. 608</u>																
	1		0+17.49	0+56.82	39.33	135.00	26.00	80.50	351.79		0.01	15	351.79	30		0.2	39.33		
	1		0+56.82	39+67.84	3911.02	26.00	26.00	26.00	11298.51		1.48	471	11298.51	960		24.1	3911.02		
	1		39+67.84	39+96.21	28.37	26.00	39.00	32.50	102.45		0.01	4	102.45	9		0.2	28.37		
	1		39+96.21	40+36.50	40.29	39.00	40.00	39.50	176.83		0.02	7	176.83	15		0.2	40.29		
	1		40+36.50	40+62.65	26.15	40.00	26.00	33.00	95.89		0.01	4	95.89	8		0.2	26.15		
	1		40+62.65	165+13.24	12450.59	26.00	26.00	26.00	35968.38		4.72	1499	35968.38	3057		76.9	12450.59		
	1		165+13.24	165+37.30	24.06	26.00	36.00	31.00	82.88		0.01	3	82.88	7		0.1	24.06		
	1		165+37.30	165+57.79	20.49	36.00	26.00	31.00	70.58		0.01	3	70.58	6		0.1	20.49		
	1		165+57.79	166+82.32	124.53	CADD AREA			15526.5		0.05	647	15526.5	1320		0.8	124.53		
SUBTOTALS											6.32	2653	63674	5412		102.87	16664.8		
TOTALS CARRIED TO GENERAL SUMMARY											6.32	2653	63674	5412		102.87	3.16 MI		

Pavement Subsummary

DESIGN AGENCY	
DESIGNER	JDA
REVIEWER	EJK 08-03-20
PROJECT ID	99628
SHEET	11
TOTAL	22