

SHEET NUM.											PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
4-6	7-9	11	12							01/MPO/PV								
ROADWAY																		
		148									148	209	60201	148	STA	LINEAR GRADING, AS PER PLAN	5	
		2.74									2.74	209	72051	2.74	MILE	PREPARING SUBGRADE FOR SHOULDER PAVING, AS PER PLAN	5	
EROSION CONTROL																		
											1,000	832	30000	1,000	EACH	EROSION CONTROL		
DRAINAGE																		
1											1	611	98631	1	EACH	CATCH BASIN ADJUSTED TO GRADE, AS PER PLAN	5	
150											150	SPECIAL	61199820	150	LB	MISCELLANEOUS METAL	5	
PAVEMENT																		
200											200	251	01000	200	SY	PARTIAL DEPTH PAVEMENT REPAIR (441)		
100											100	253	02000	100	CY	PAVEMENT REPAIR		
		20,068									20,068	254	01001	20,068	SY	PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN , 1.5"	5	
		2,810									2,810	407	20000	2,810	GAL	NON-TRACKING TACK COAT		
		831									831	441	10101	831	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446), AS PER PLAN, PG70-22M, (1-1/2")	6	
		19									19	441	50101	19	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), AS PER PLAN, PG64-22, 1.5"	6	
		548									548	441	50200	548	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), (1")		
		20									20	441	50400	20	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), (DRIVEWAYS) , 2"		
		44									44	617	10101	44	CY	COMPACTED AGGREGATE, AS PER PLAN	5	
		1,807									1,807	875	10000	1,807	LB	LONGITUDINAL JOINT ADHESIVE		
TRAFFIC CONTROL																		
68			107								107	621	00100	107	EACH	RPM		
											68	621	54000	68	EACH	RAISED PAVEMENT MARKER REMOVED		
			1								1	642	01110	1	EACH	SCHOOL SYMBOL MARKING, 96", TYPE 1		
			2.74								2.74	646	10010	2.74	MILE	EDGE LINE, 6"		
			1.37								1.37	646	10200	1.37	MILE	CENTER LINE		
LS			20								20	646	10400	20	FT	STOP LINE		
											LS	SPECIAL	69098400	LS		INVENTORY EXISTING PAVEMENT MARKINGS	5	
MAINTENANCE OF TRAFFIC																		
	80										80	614	11110	80	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE		
	15										15	614	13001	15	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC, AS PER PLAN	8	
	6										6	614	18601	6	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	9	
	1.37										1.37	614	21100	1.37	MILE	WORK ZONE CENTER LINE, CLASS I, 642 PAINT		
	1.37										1.37	614	21550	1.37	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT		
	2.74										2.74	614	22110	2.74	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 642 PAINT		
	2.74										2.74	614	22360	2.74	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT		
	20										20	614	26200	20	FT	WORK ZONE STOP LINE, CLASS I, 642 PAINT		
	20										20	614	26610	20	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT		
	1										1	614	31744	1	EACH	WORK ZONE SCHOOL SYMBOL MARKING, 96", CLASS I, 642 PAINTs		
	1										1	614	31750	1	EACH	WORK ZONE SCHOOL SYMBOL MARKING, 96", CLASS III, 642 PAINTS		
	300										300	630	97800	300	SF	SIGNING, MISC.:ADDITIONAL SIGNS, GROUND MOUNTED, AS DIRECTED BY THE ENGINEER	8	
INCIDENTALS																		
											LS	614	11000	LS		MAINTAINING TRAFFIC		
6											6	619	16010	6	MNTH	FIELD OFFICE, TYPE B, AS PER PLAN	4	
LS											LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING		
											LS	624	10000	LS		MOBILIZATION		

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER
JDA

REVIEWER
EJK 6-3-21

PROJECT ID
99700

SHEET TOTAL
10 16