

**GRE-72-0.25 PAVEMENT QUANTITY COMPUTATIONS**



CALC: DPF		CHK: 4/28/2023 15:21		441	407	407	441	254	301	304	204	202										
		DEPTH or RATE		1.25	0.055	0.085	1.75		8	6												
STATION		LENGTH	PLAN AREA	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22		TACK COAT (ON INTERMEDIATE & BASE COURSES)		TACK COAT (ON PLANING)		ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (449)		PAVEMENT PLANING, ASPHALT CONCRETE, 3"		ASPHALT CONCRETE BASE, (449)		AGGREGATE BASE		SUBGRADE COMPACTION		PAVEMENT REMOVED		
FROM	TO			WIDTH	CU YD	WIDTH	GAL	WIDTH	GAL	WIDTH	CU YD	WIDTH	SY	WIDTH	CU YD	WIDTH	CU YD	WIDTH	SQ YD	WIDTH	SQ YD	
<b>SR 72</b>																						
17+50.00	18+00.00	50.00	2033.00		7.8		24.8		19.2		11.0		225.9									
18+00.00	18+50.00	50.00		32.05	6.2	32.05	19.6			32.05	8.7			32.72	40.4	33.72	31.2	35.05	195			
18+00.00	20+61.16	261.16	5930.00																		659	
18+50.00	20+60.09	210.09		32.00	25.9	32.00	82.2			32.00	36.3			32.67	169.5	33.67	131.0	35.00	817			
20+60.09	20+85.09	25.00		34.17												36.17	16.7	36.17	100			
23+72.64	23+97.64	25.00		34.17												36.17	16.7	36.17	100			
23+97.64	26+00.00	202.36		32.00	25.0	32.00	79.1			32.00	35.0			32.67	163.2	34.67	129.9	35.00	787			
23+98.58	26+50.00	251.42	5790.00																		643	
26+00.00	26+50.00	50.00		32.45	6.3	32.45	19.8			32.45	8.8			33.12	40.9	34.12	31.6	35.45	197			
26+50.00	27+00.00	50.00	1830.00		7.1		22.4		17.3		9.9		203.3									
<b>TOTALS</b>				<b>78</b>	<b>248</b>	<b>36</b>	<b>110</b>	<b>429</b>	<b>414</b>	<b>357</b>	<b>2197</b>	<b>1302</b>										
				<b>284</b>																		