SHEET NUM. 3	4	7	8	9	10	13	PART. 01/S>2/CY	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
												ROADWAY	
							LS	201	11000	LS		CLEARING AND GRUBBING	
				1			1	202	20010	1	EACH	HEADWALL REMOVED	
		53	12.6				65.6	202	23000	65.6	SY	PAVEMENT REMOVED	
			85				85	202	30000	85	SF	WALK REMOVED	
				57			57	202	35100	57	FT	PIPE REMOVED, 24" AND UNDER	
				1			1	202	58100	1	EACH	CATCH BASIN REMOVED	
			50				50	SPECIAL	20270000	50	FT	FILL AND PLUG EXISTING CONDUIT, 15"	3
		53					53	204	10000	53	SY	SUBGRADE COMPACTION	
							LS	503	11100	LS		COFFERDAMS AND EXCAVATION BRACING	
						7	7	623	40520	7	EACH	RIGHT-OF-WAY MONUMENT	
							LS	878	25000	LS		INSPECTION AND COMPACTION TESTING OF UNBOUND MATERIALS	
												EROSION CONTROL	
			1.9				1.9	601	32204	1.9	CY	ROCK CHANNEL PROTECTION, TYPE C WITH GEOTEXTILE FABRIC	
450							450	659	10000	450	SY	SEEDING AND MULCHING	
0.06							0.06	659	20000	0.06	TON	COMMERCIAL FERTILIZER	
0.09							0.09	659	31000	0.09	ACRE	LIME	
2.4							2.4	659	35000	2.4	MGAL	WATER	
							3,000	832	30000	3,000	EACH	EROSION CONTROL	
												DRAINAGE	
			0.27	0.46			0.73	602	20000	0.73	CY	CONCRETE MASONRY	
			44				44	611	05900	44	FT	15" CONDUIT, TYPE B	
			75				75	611	04600	75	FT	12" CONDUIT, TYPE C	
				57			57	611	07600	57	FT	18" CONDUIT, TYPE A, 707.02, 706.02 ALUMINIZED, 707.33	
				4			4	611	10600	4	FT	24" CONDUIT, TYPE C	
					46		46	893	10000	46	FT	CURED-IN-PLACE PIPE LINER, 12"	
			1				1	611	98470	1	EACH	CATCH BASIN, NO. 2-2B	
				1			1	611	98300	1	EACH	CATCH BASIN, NO. 5	
												PAVEMENT	
		9					9	301	46000	9	CY	ASPHALT CONCRETE BASE, PG64-22	
		9	3.5				12.5	304	20000	12.5	CY	AGGREGATE BASE	
		6					6	407	10000	6	GAL	TACK COAT	
		4					4	441	50000	4	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
			21				21	452	10010	21	SY	6" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P	
												TRAFFIC CONTROL	
			1	1			2	621	00100	2	EACH	RPM	
			1	1			2	621	54000	2	EACH	RAISED PAVEMENT MARKER REMOVED	
			0.02	0.02			0.04	642	00104	0.04	MILE	EDGE LINE, 6", TYPE 1	
			0.01	0.01			0.02	642	00300	0.02	MILE	CENTER LINE, TYPE 1	
												MAINTENANCE OF TRAFFIC	
	LS						LS	614	12420	LS		DETOUR SIGNING	
												INCIDENTALS	
							LS	614	11000	LS		MAINTAINING TRAFFIC	
							LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
							LS	624	10000	LS		MOBILIZATION	

CALCULATED MLB
CHECKED TRB

GENERAL SUMMARY

HAM SR264
CULVERTS FY22

I:\ProjectData\HAM\09992_HAM-SR264-CulvertsFY22\Design\Drainage\Sheets\09992_GG01.dgn Sheet 8/5/2021 2:36:01 PM mbailey5