

ROUTE	FROM	TO	DISTANCE		PAVT WIDTH	TYPICAL SECTION	PLAN SPLITS	PAVT AREA	407	421	
			SLM	SLM					MILES	FEET	FEET
									0.15 GAL/SY	24' WIDE (PLACED ON TRAVELED LANES)	TOTAL WIDTH OF PAVEMENT
									GAL	SQ YD	SQ YD
SR 31	0.00	0.09	0.09	475	35 Avg. *	1	01/STR/PV	1848	277	1267	1848
SR 31	0.09	1.92	1.83	9662	29 *	1	01/STR/PV	31134	4670	25766	31134
SR 31	1.92	2.75	0.83		No work						
SR 31	2.75	3.60	0.85	4488	28 *	1	01/STR/PV	13963	2094	11968	13963
SR 31	3.60	3.65	0.05	264	31 Avg. *	1	01/STR/PV	909	136	704	909
SR 31	3.65	3.68	0.03		No work						
SR 31	3.68	3.73	0.05	264	32 Avg. *	1	01/STR/PV	939	141	704	939
SR 31	3.73	7.05	3.32	17530	29 *	1	01/STR/PV	56484	8473	46746	56484
SR 31	7.05	7.08	0.03		No work						
SR 31	7.08	8.74	1.66	8765	30 *	1	01/STR/PV	29216	4382	23373	29216
SR 31	8.74	9.28	0.54	2851	30 *	1	02/S5K/PV	9504	1426	7603	9504
SR 31	9.28	9.30	0.02		No work						
SR 31	9.30	10.16	0.86	4541	30 *	1	02/S5K/PV	15136	2270	12109	15136
Plan Split 01										110528	134493
Plan Split 02										19712	24640
Totals									23869	130240	159133

* Note: Pavement width is outside edge of paved shoulder to outside edge of paved shoulder. Additional quantities for mailbox turn outs, drive approaches and intersections are not accounted for and will not be included with the work.

** Not carried to General Summary. Item is incidental to Microsurfacing per CMS 421.16. The quantity is provided for informational purposes only.

ROUTE	FROM	TO	DISTANCE		PLAN SPLITS	423	618	621		642		644		643			
			SLM	SLM		MILES	FEET	CRACK SEALING TYPE 1	CENTER LINE RUMBLE STRIPES	RPM	RPM REMOVED	EDGE LINE	CENTER LINE	STOP LINE	RR SYMBOL	REMOVAL OF PAVEMENT MARKING	REMOVAL OF PAVEMENT MARKING
						LB	MILE	EACH	EACH	MILE	MILE	FEET	EACH	FEET	EACH	MILE	
SR 31	0.00	1.92	1.92	10138	01/STR/PV	1935	1.92	127	127	3.84	1.92						5.76
SR 31	1.92	2.75	0.83	4382	NO WORK												
SR 31	2.75	3.65	0.90	4752	01/STR/PV	907	0.90	59	59	1.80	0.90						2.70
SR 31	3.65	3.68	0.03	158	01/STR/PV			2	2	0.06	0.03						
SR 31	3.68	7.05	3.37	17794	01/STR/PV	3397	3.37	222	222	6.74	3.37						10.11
SR 31	7.05	7.08	0.03	158	01/STR/PV			2	2	0.06	0.03						
SR 31	7.08	8.74	1.66	8765	01/STR/PV	1673	1.66	110	110	3.32	1.66						4.98
SR 31	8.74	9.28	0.54	2851	02/S5K/PV	544	0.54	36	36	1.08	0.54						1.62
SR 31	9.28	9.30	0.02	106	02/S5K/PV			1	1	0.04	0.02						
SR 31	9.30	10.16	0.86	4541	02/S5K/PV	222	0.22 #	57	57	1.72	0.86	26	2	26	2	26	2.58
Plan Split 01						7912	7.85	522	522	15.82	7.91						23.55
Plan Split 02						766	0.76	94	94	2.84	1.42	26	2	26	2	26	4.20
SUB-TOTALS						8678	8.61	616	616	18.66	9.33	26	2	26	2	26	27.75

- Center Line Rumble Stripes end at 9.52 mile marker.

DESIGN AGENCY



DESIGNER
GLI
 REVIEWER
MPB 08-11-22
 PROJECT ID
116153
 SHEET TOTAL
5 6

