

SHEET NUM.											PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
4	9	10									01/SAF/OT	02/SAF/OT						
<b>ROADWAY</b>																		
											LS	LS	201	11000	LS		CLEARING AND GRUBBING	
	560										560		202	30000	560	SF	WALK REMOVED	
	75										75		202	32000	75	FT	CURB REMOVED	
	25										25		608	10001	25	SF	4" CONCRETE WALK, AS PER PLAN	5
	764										540	224	608	52001	764	SF	CURB RAMP, AS PER PLAN	4
	36										36		609	26001	36	FT	CURB, TYPE 6, AS PER PLAN	5
<b>EROSION CONTROL</b>																		
0.75											0.75		659	00300	0.75	CY	TOPSOIL	
6											6		659	10000	6	SY	SEEDING AND MULCHING	
1											0.5	0.5	659	14000	1	SY	REPAIR SEEDING AND MULCHING	
1											0.5	0.5	659	15000	1	SY	INTER-SEEDING	
0.01											0.01	0.01	659	20000	0.01	TON	COMMERCIAL FERTILIZER	
1											0.5	0.5	659	35000	1	MGAL	WATER	
											1,000	1,000	832	30000	2,000	EACH	EROSION CONTROL	
<b>TRAFFIC CONTROL</b>																		
	2	2									2	2	630	97700	4	EACH	SIGNING, MISC.:SOLAR POWERED RECTANGULAR RAPID FLASHING BEACON (RRFB)	5
	80										80		644	00601	80	FT	CROSSWALK LINE, AS PER PLAN	5
<b>TRAFFIC SIGNALS</b>																		
	35										35		625	25408	35	FT	CONDUIT, 2", 725.051	
	35										35		625	29000	35	FT	TRENCH	
	2										2		625	30706	2	EACH	PULL BOX, 725.08, 24"	
	4										2	2	625	32000	4	EACH	GROUND ROD	
	2										2		632	20751	2	EACH	ACCESSIBLE PEDESTRIAN PUSHBUTTON, AS PER PLAN	5
	120										120		632	40200	120	FT	SIGNAL CABLE, 2 CONDUCTOR, NO. 14 AWG	
	2										2		632	64020	2	EACH	PEDESTAL FOUNDATION	
	25										25		632	68300	25	FT	POWER CABLE, 3 CONDUCTOR, NO. 6 AWG	
	25										25		632	69900	25	FT	SERVICE CABLE, 3 CONDUCTOR, NO. 4 AWG	
	1										1		632	70001	1	EACH	POWER SERVICE, AS PER PLAN	5
	4										4		632	70400	4	EACH	CONDUIT RISER, 2" DIAMETER	
	2										2		632	89802	2	EACH	PEDESTAL, 5', TRANSFORMER BASE	
<b>INCIDENTALS</b>																		
											LS		614	11000	LS		MAINTAINING TRAFFIC	
											LS		623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
											LS		624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER  
DEK

REVIEWER  
DF

PROJECT ID  
109641

SHEET TOTAL  
P.7 | 10

SHEET NO.	LOCATIONS	202	202	608	608	609	625	625	625	625	630	632	632	632	632	632	632	632	632	644		
		WALK REMOVED SF	CURB REMOVED FT	4" CONCRETE WALK, AS PER PLAN SF	CURB RAMP, AS PER PLAN SF	CURB, TYPE 6, AS PER PLAN FT	CONDUIT, 2", 725.051 FT	TRENCH FT	PULL BOX, 725.08, 24" EACH	GROUND ROD EACH	SIGNING, MISC.: SOLAR POWERED RECTANGULAR RAPID FLASHING BEACON (RRFB) EACH	ACCESSIBLE PEDESTRIAN PUSHBUTTON, AS PER PLAN EACH	PEDESTAL FOUNDATION EACH	SIGNAL CABLE, 2 CONDUCTOR, NO. 14 AWG FT	POWER CABLE, 3 CONDUCTOR, NO. 6 AWG FT	SERVICE CABLE, 3 CONDUCTOR, NO. 4 AWG FT	POWER SERVICE, AS PER PLAN EACH	CONDUIT RISER, 2" DIAMETER EACH	PEDESTAL, 5', TRANSFORMER BASE EACH	CROSSWALK LINE, AS PER PLAN FT		
<b>HEN-109-21.06</b>																						
9	PED SUPPORT 1 TO PULLBOX 1						6	6	1	1		1	1	120					1	1		
9	PULLBOX 1 TO RRFB UTILITY POLE						10	10			1			25	25	1			1			
9	PED SUPPORT 2 TO PULLBOX 2						10	10	1	1		1	1						1	1		
9	PULLBOX 2 TO RRFB UTILITY POLE						9	9			1								1			
9	CR-1	58	6		45	6																
9	CR-2	85	15		85																	
9	CR-3	80	15		80																	
9	CR-4	75	13		75	15																
9	CR-5	85	13	25	85	15																
9	CR-6	122	6		115																	
9	CR-7	55	7		55																	
9	CW-1																				23	
9	CW-2																				34	
9	CW-3																				23	
<b>SEN-67-2.68</b>																						
10	CR-1				132						1											
10	CR-2				92						1											
<b>TOTALS CARRIED TO GENERAL SUMMARY</b>		560	75	25	764	36	35	35	2	2	4	2	2	120	25	25	1	4	2	80		

SUBSUMMARY

DESIGN AGENCY



DESIGNER

DEK

REVIEWER

CDW

PROJECT ID

109641

SHEET

P.8

TOTAL

10