* - FOR TYPICALS, SEE SHEET 3

COUNTY	ROUTE	LOG POINT TO LOG POINT (STRAIGHT LINE MILEAGE)		LENGTH MILE	LENGTH FEET	WIDTH FEET AVG.	*TYPICAL	PAVEMENT AREA (SY)	254 PAVEMENT PLANING, ASPHALT CONCRETE (1.50") (SY)	254 PATCHING PLANED SURFACE (SY)	407 TACK COAT @ 0.08 GAL/SY (GAL)		442 ASPHALT CONCRETE SURFACE COURSE, 9.5 MM, TYPE A (446), AS PER PLAN (INCHES)	442 (CY)	442 ASPHALT CONCRETE SURFACE COURSE, 9.5 MM, TYPE A (448), AS PER PLAN (INCHES)	442 (CY)		AGGREGATE SHOULDER PROPOSED WIDTH SL (FT)	AGGREGATE SHOULDER PROPOSED WIDTH SR (FT)	AGGREGATE SHOULDER AREA (SY)	209 LINEAR GRADING (MILE)		617 COMPACTED AGGREGATE 1.5 INCHES AVG. THICKNESS (CY)	617 SHOULDER PREPARATION (SY)	618 EDGE LINE, RUMBLE STRIPE (ASPHALT CONCRETE) (MILE)
LOR	511	13.41	13.50	0.09	475	31.0	1	1,636	1,636	16	131		1.5	68				2.0	2.0	211	0.18		9	211	0.2
LOR	511	13.50	13.61	0.11	581	29.5	1	1,904	1,904	19	152		1.5	79				2.0	2.0	258	0.22		11	258	0.2
LOR	511	13.61	14.00	0.39	2059	30.0	2	6,863	6,863	69	549				1.5	286		2.0	2.0	915	0.78		38	915	
LOR	511	14.00	14.31	0.31	1637	30.5	2	5,548	5,548	55	444				1.5	231		2.0	2.0	728	0.62		30	728	
LOR	511	14.31	14.50	0.19	1003	28.5	1	3,176	3,176	32	254		1.5	132				2.0	2.0	446	0.38		19	446	0.4
LOR	511	14.50	15.00	0.50	2640	28.5	1	8,360	8,360	84	669		1.5	348				2.0	2.0	1,173	1.00		49	1,173	1.0
LOR	511	15.00	15.50	0.50	2640	29.3	1	8,595	8,595	86	688		1.5	358				2.0	2.0	1,173	1.00		49	1,173	1.0
LOR	511	15.50	16.00	0.50	2640	29.5	1	8,653	8,653	87	692		1.5	361				2.0	2.0	1,173	1.00		49	1,173	1.0
LOR	511	16.00	16.50	0.50	2640	28.8	1	8,448	8,448	84	676		1.5	352				2.0	2.0	1,173	1.00		49	1,173	1.0
LOR	511	16.50	17.00	0.50	2640	29.0	1	8,507	8,507	85	681		1.5	354				2.0	2.0	1,173	1.00		49	1,173	1.0
LOR	511	17.00	17.50	0.50	2640	29.3	1	8,595	8,595	86	688		1.5	358				2.0	2.0	1,173	1.00		49	1,173	1.0
LOR	511	17.50	18.00	0.50	2640	29.5	1	8,653	8,653	87	692		1.5	361				2.0	2.0	1,173	1.00		49	1,173	1.0
LOR	511	18.00	18.46	0.46	2429	28.5	1	7,692	7,692	77	615		1.5	320				2.0	2.0	1,080	0.92		45	1,080	0.9
		REDUCTIONS FOR VILLIAGE		0.06	317													2.0	2.0	141	-0.12		-6	-141	
		EXTRA AREA FOR INTERSECTIONS						2096	2096	21	168		1.5	87											
		EXTRA AREA FOR PAVED DRIVES						315	315	3	25		1.5	13											
		EXTRA AREA FOR AGGREGATE DRIVES						630												630			26	630	
		EXTRA AREA FOR EX. & PR. MAILBOX APPROACHES						610	610	6	49				1.5	25									
		EXTRA AREA FOR PARKING AREA						620	620	6	50				1.5	26									
		TOTALS TO GENERAL SUMMARY							90,271	903	7,223			3,191		568					9.98		515	12,338	8.7

CALCULATED CAG
CHECKED CAD

PAVEMENT & SHOULDER DATA

LOR-511-13.41

DESIGN FILE:i:\projects\88767\roadway\sheets\88767GQ001.dgn MODELNAME: Sheet
WORKSTATION:tgoodnig DATE:8/28/2014