


SHEET NUM.										PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
3	4	6	7	8	9	10				01/STR/PV	02/STR/BR							
					335					335			202	30000	335	SF	ROADWAY WALK REMOVED	
					100					100			608	10000	100	SF	4" CONCRETE WALK	
					335					335			608	52000	335	SF	CURB RAMP	
					48					48			608	53020	48	SF	DETECTABLE WARNING	
12										12			611	98630	12	EACH	CATCH BASIN ADJUSTED TO GRADE	
4										4			611	99654	4	EACH	MANHOLE ADJUSTED TO GRADE	
										900	100		832	30000	1,000	EACH	EROSION CONTROL	
																	PAVEMENT	
1,500										1,500			251	01001	1,500	SY	PARTIAL DEPTH PAVEMENT REPAIR (441), AS PER PLAN	
20										20			253	01001	20	SY	PAVEMENT REPAIR, AS PER PLAN	
		116,469	37,523							153,992			254	01000	153,992	SY	PAVEMENT PLANING, ASPHALT CONCRETE	
32,122										32,122			254	01600	32,122	SY	PATCHING PLANED SURFACE	
		10,482	3,377							13,859			407	20000	13,859	GAL	NON-TRACKING TACK COAT	
		4,853	1,563							6,416			441	50000	6,416	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
400										400			617	10100	400	CY	COMPACTED AGGREGATE	
50										50			617	25000	50	MGAL	WATER	
			2.46							2.46			874	21000	2.46	MILE	LONGITUDINAL JOINT PREPARATION	
																	TRAFFIC CONTROL	
				20						20			618	41000	20	MILE	RUMBLE STRIPES, EDGE LINE (ASPHALT CONCRETE)	
				2						2			618	43000	2	MILE	RUMBLE STRIPES, CENTER LINE (ASPHALT CONCRETE)	
				1,623						1,623			621	00100	1,623	EACH	RPM	
				1,623						1,623			621	54000	1,623	EACH	RAISED PAVEMENT MARKER REMOVED	
				20.08						20.08			644	00104	20.08	MILE	EDGE LINE, 6"	
				10.04						10.04			644	00300	10.04	MILE	CENTER LINE	
				56						56			644	00500	56	FT	STOP LINE	
																	STRUCTURE REPAIR (JAC-279-1695 4003187)	
						593				593			254	01000	593	SY	PAVEMENT PLANING, ASPHALT CONCRETE	
						50				50			407	20000	50	GAL	NON-TRACKING TACK COAT	
						24				24			441	50000	24	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
						84					84		516	10900	84	FT	ELASTOMERIC COMPRESSION SEAL	
						253				253			254	01000	253	SY	PAVEMENT PLANING, ASPHALT CONCRETE	
						22				22			407	20000	22	GAL	NON-TRACKING TACK COAT	
						88					88		409	30000	88	FT	SAWING AND SEALING ASPHALT CONCRETE PAVEMENT JOINTS	
						11				11			441	50000	11	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
																	MAINTENANCE OF TRAFFIC	
	92									92			614	12460	92	EACH	WORK ZONE MARKING SIGN	
	22.54									22.54			614	21550	22.54	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
	40.16									40.16			614	22360	40.16	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT	
																	INCIDENTALS	
						0.9				0.9	0.1		614	11000	LS		MAINTAINING TRAFFIC	
						0.9				0.9	0.1		623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
						0.9				0.9	0.1		624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY

 DESIGNER
 JBS
 REVIEWER
 CLC MM-DD-YY
 PROJECT ID
 114730
 SHEET TOTAL
 P.5 10