SHEET NUM.											PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
P.3	P.4	P.8	P.9	P.10	P.17						01/NHS/17								
																		ROADWAY	
LS											LS			201	11000	LS		CLEARING AND GRUBBING	
			200								200			202	38000	200	FT	GUARDRAIL REMOVED	
			26								26			203	20000	26	CY	EMBANKMENT	
			200								200			606	15050	200	FT	GUARDRAIL, TYPE MGS	
																		EROSION CONTROL	
			174								174			659	10000	174	SY	SEEDING AND MULCHING	
			0.04								0.04			659	31000	0.04	ACRE	LIME	
			1								1			659	35000	1	MGAL	WATER	
											5,000			832	30000	5,000	EACH	EROSION CONTROL	
																		PAVEMENT	
				197							197			254	01000	197	SY	PAVEMENT PLANING, ASPHALT CONCRETE (T=1.5")	
				36							36			407	10000	36	GAL	TACK COAT	
				13							13			442	22000	13	CY	ASPHALT CONCRETE SURFACE COURSE, 9.5 MM, TYPE A (449)	
				200							200			618	40100	200	FT	RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE)	
																		TRAFFIC CONTROL	
			5								5			626	00110	5	EACH	BARRIER REFLECTOR, TYPE 2 (ONE-WAY)	
			0.04								0.04			644	00104	0.04	MILE	EDGE LINE, 6"	
																		RETAINING WALLS (1)	
LS											LS			503	11100	LS		COFFERDAMS AND EXCAVATION BRACING	P.17
960											960			507	00400	960	FT	STEEL PILES, MISC.:W24X68 STEEL BEAM, FURNISHED	P.17
588											588			524	94703	588	FT	DRILLED SHAFTS, 36" DIAMETER, ABOVE BEDROCK, AS PER PLAN	P.17
300											300			524	94705	300	FT	DRILLED SHAFTS, 36" DIAMETER, INTO BEDROCK, AS PER PLAN	P.17
539											539			524	95000	539	FT	DRILLED SHAFTS, MISC.:PLUG PILES, 36" DIAMETER, UNREINFORCED, AS PER PLAN	P.17
																		MAINTENANCE OF TRAFFIC	
		1									1			614	12380	1	EACH	WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (UNIDIRECTIONAL)	
		10									10			614	13310	10	EACH	BARRIER REFLECTOR, TYPE 1 (ONE-WAY)	
		10									10			614	13350	10	EACH	OBJECT MARKER, ONE WAY	
		0.32									0.32			614	22010	0.32	MILE	WORK ZONE EDGE LINE, CLASS I, 6"	
		720									720			614	24000	720	FT	WORK ZONE DOTTED LINE, CLASS I	
	1										1			616	10000	1	MGAL	WATER	
		487									487			622	41100	487	FT	PORTABLE BARRIER, UNANCHORED	
																		INCIDENTALS	
	LS										LS			614	11000	LS		MAINTAINING TRAFFIC	
											2			619	16000	2	MNTH	FIELD OFFICE, TYPE A	
											LS			623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
											LS			624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY
BG
www.bgenggroup.com
5960 WILCOX PLACE, SUITE C
DUBLIN, OHIO 43016

DESIGNER
EAK

REVIEWER
RG 1-10-24

PROJECT ID
116242

SHEET P.7 TOTAL 24

JAC-35-15.36

MODEL: Sheet PAPERSIZE: 17x11 (in.) DATE: 5/4/2024 TIME: 10:01:32 AM USER: jperchinske
P:\Transportation\WorkSets\117406_VAR-D09 Genl Eng Servs FY 23-24\407-Engineering_JAC-35-1536\Roadway\Sheets\116242_GG001.dgn