

MODEL: Sheet PAPER SIZE: 17x11 (in.) DATE: 7/14/2025 TIME: 11:08:16 AM USER: jme\lman
Q:\ODOT_D12\0121497A.00 - LAK-283-1434 Deck PID111005111005400-Engineering\Roadway\Sheets\111005_GG003.dgn

[illegible]

DESIGN AGENCY



JLM

REVIEWER

DWS 06/09/23

PROJECT ID

111005

SHEET TOTAL

22A | 84

SLM RANGE			TYPICAL SECTION	SIDE	DISTANCE (D)	AVERAGE WIDTH (W)	SURFACE AREA (A) A=DxW/9	CADD GENERATED AREA	204	204		302		304		305		407		441		442		442		452
					FT	FT	SQ YD	SQ FT	SUBGRADE COMPACTION	PROOF ROLLING		ASPHALT CONCRETE BASE, PG 64-22 (449)		AGGREGATE BASE		9" CONCRETE BASE, CLASS QC1		NON-TRACKING TACK COAT		ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), AS PER PLAN, PG70-22M		ASPHALT CONCRETE SURFACE COURSE, 12.5MM, TYPE A (449), AS PER PLAN, PG76-22M		ASPHALT CONCRETE INTERMEDIATE COURSE, 12.5MM, TYPE A (449)		10" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC1
									SY	HOURL		CY		CY		SY		GAL		CY		CY		CY		SY
	TO																									
S.R. 283																										
27+12.84		28+73.01			160.17	61.12	1087.67	9789	1141.06	0.57		277.48		189.19				180.12		90.64						
28+73.01		28+98.01			25.00	63.88	177.44	1597	185.78	0.09				30.04												
31+38.45		31+63.45			25.00	63.88	177.44	1597	185.78	0.09				30.04												
31+63.45		32+50.00			86.55	61.07	587.33	5286	616.18	0.31		149.84		102.16				97.26		48.94						
32+81.15		34+04.52			123.37	8.00	109.65	987	109.65	0.05		27.41		18.28				18.09		9.14						
S.R 44																										
72+79.83		74+14.53			134.70	3.70	55.33	498	77.78	0.04				11.72		55.33		6.09					2.31		3.07	
73+96.49		74+14.53			18.04	2.83	5.67	51	8.67	0.00				1.28		5.67		0.62				0.24		0.31		
74+14.53		77+00.98			286.45	16.62	529.00	4761	529.00	0.26				88.17		529.00		52.35				17.62		29.39		
77+12.10		77+30.14			18.04	2.83	5.67	51	8.67	0.00				1.28		5.67		0.62				0.24		0.31		
77+12.10		78+46.81			134.71	3.70	55.33	498	77.79	0.04				11.72		55.33		6.09				2.31		3.07		
RAMP A																										
12+28.95		13+50.65			121.70	27.58	372.89	3356	413.46	0.21				64.40												372.89
RAMP B																										
3+74.24		4+21.00			46.76	32.76	170.22	1532	185.81	0.09				29.24												170.22
SUBTOTALS									3539.63	1.77		454.73		577.50		651.00		361.25		148.72		22.70		36.17		543.11
TOTALS CARRIED TO GENERAL SUMMARY									3540	2		455		578		651		362		149		23		37		544