

GENERAL

Contingency Quantities

The contractor shall not order materials or perform work for items designated by plan note to be used "as directed by the engineer" unless authorized by the engineer. The actual work locations and quantities used for such items shall be incorporated into the final change order governing completion of this project.

Equipment and Material Storage

In order to provide for the safety of the traveling public the Contractor's attention is directed to 614.03. In addition the following provisions shall apply:

1. Any removed items shall not be stored on the right of way for more than thirty (30) days.
2. The storage of equipment, materials, and vehicles within the highway right of way will be permitted. The number of areas and exact locations shall be approved by the Engineer.
3. All disturbed areas shall be returned to their original condition at no expense to the state.

Construction Noise

Construction noise restrictions shall apply to the LAK-174-1.34 and the LAK-306-4.66 locations.

Activities and land use adjacent to this project may be affected by construction noise. In order to minimize any adverse construction noise impacts, do not operate power-operated construction-type devices between the hours of 7 pm and 7 am. In addition, do not operate at any time any device in such a manner that the noise created substantially exceeds the noise customarily and necessarily attendant to the reasonable and efficient performance of such equipment.

Cooperation Between Contractors

The contractor shall cooperate and coordinate operations with the contractors on other projects that may be in force during the life of the contract. No waiver of any provisions of the Constructions and Material Specifications is intended.

Work Limits

The work limits shown on these plans are for physical construction only. The installation and operation of all temporary traffic control and temporary traffic control devices required by these plans shall be provided by the contractor whether inside or outside these work limits.

Right Of Way

All work shall be performed within the existing right of way or easements.

Staging Areas

There are no specific areas given in the plans for the Contractor to use as a staging area(s). If the Contractor wants to use an area(s) for staging, regardless if it falls within the project limits or not, the Contractor is to use the Right of Way E-Permitting System at <https://odhcp.bemcorp.net/Accounts/Account/Account> in order to apply for a permit per Section 107.02 of the CMS. For specific permitting questions, the Contractor can contact the District Permitting Office, (Melvin Safford) at 216-584-2137 or at District12Permits@dot.ohio.gov.

If a permit is granted, all conditions of the permit shall be met in addition to the requirements of 104.04 of the CMS, at no additional cost to the State. If the Project Engineer deems that all the conditions of the permit were not met, then 10% of the

Contract bid amount for mobilization shall be withheld until all the conditions of the permit are satisfied.

Plan Sheet Stationing

The roadway was not surveyed prior to the preparations of these plans. Stationing was provided to prepare plan sheets.

Protection of Right-of-Way Landscaping

Prior to beginning work, the Contractor, the Project Engineer and a representative of the maintaining agency will review and record all landscaping items within the right-of-way (both within and outside the construction limits). A record of this review will be kept in the Project Engineer's files. Prior to final acceptance, a final review of landscaping items will be made.

Constrict all activities, equipment storage and staging to within the construction limits. Unless otherwise identified in the plans or proposal, the construction limits are identified as 30 feet from the edge of pavement.

Submit a written request to the Project Engineer to use any area outside these limits. The document submitted must clearly identify the area and explain the proposed use and restoration of the area. Use of these areas for disposal of waste material and construction debris, excavation of borrow material and placement of portable plants is prohibited. The request must be approved, in writing, before the Contractor has permission to use the area.

Any items damaged beyond the construction limits, as defined above, will be replaced in kind or as approved by the Project Engineer.

Utilities

Listed below are all known utilities located within the project construction limits together with their respective owners:

AQUA Ohio – Lake County
8644 Station Street
Mentor, Ohio 44060-4316
Attn: Bill Bowers, Area Manager
Phone: 440255-7280, ext 50611
Cell: 216-905-8362
wmbowers@aquaaamerica.com

Air Products and Chemicals, Inc.
James E. Jones
2820 Quigley Rd.
Cleveland, Ohio 44113
216-781-2817
jonese@airproducts.com

AT&T
13630 Lorain Ave. – 2nd Floor
Cleveland, Ohio 44111
Attn: James Janis
Phone: (216) 476-6142
Fax: (216) 476-6013
pj8191@att.com

City of Painesville – Electric
325 Richmond St.
Painesville, OH 44077
Jeffrey McHugh, Superintendent

City of Willoughby Hills
Mark Grubiss – Superintendent
Phone: 440-918-8742
Fax: 440-918-8744
markgrubiss@willoughbyhills-oh.gov
Richard L. Bower & Associates, Inc
Pietro A. DiFranco, City Engineer
13000 Shaker Blvd
Cleveland, OH 44120
Phone: 216-377-3813
Fax: 216-491-8053
PDifranco@RLBA.com

City of Willoughby – Sewer
Rick Palmisano – Service Director
One Public Square
Willoughby, Ohio 44094
Office: 440-953-4308
Cell: 440-221-8732
rpalmisano@willoughbyohio.com

Charter Communications
David Sobotka
578 Ternes Ln
Elyria, OH 44035
Phone: 216-575-8016
Ext 2165554263

Phone: 440-392-5939
jmchugh@painesville.com

Illuminating Company
John M. Zassick
FirstEnergy
6896 Miller Rd, Suite 101
Brecksville, OH 44141
Office 440-546-8706
jmzassick@firstenergycorp.com

Northeast Ohio Natural Gas Corp.
Mark Wetzel
6081 State Route 250
Strasburg, OH 44680
Office: 330-878-4303
Emergency: 800-848-5589
Fax: 330-878-5614
Mobile: 330-204-3008
mwetzel@egas.net

Windstream
560 Ternes Ave.
Elyria, Ohio 44035
Attn: Geoffrey Hamm (Cuyahoga County)
OSP Engineer II
Phone: (440) 329-4245 (office)
Phone: (330) 256-6133 (cell)
geoffrey.p.hamm@windstream.com

Painesville Township
55 Nye Road
Painesville Township, OH 44077
Michael P. Manary, Administrator
Phone: 440-352-1443, Ext. 104
Fax: 440-352-8169
mmanary@painesvilletwp.com

The location of all existing utilities shall be verified by the Contractor as required by section 153.64 of the Ohio Revised Code and be shown on the shop drawing.

Lake County Department of Utilities Inspector Coordination and Project Observation

Contractor shall contact Lake County Department of Utilities (LCDU) at 440-350-2652, a minimum of 2 business days prior to any excavation at the LAK-306-4.66 and LAK-174-1.34. An inspector from LCDU shall be onsite during all earthwork, utility test hole work and plate pile placement. Coordination and inspection fees for the LCDU inspector shall be incidental to the ITEM 690 – Special, Misc: Utility Test Holes Item.

LAK-306 Abandoned Utilities

The contractor is advised that an abandoned coal line was noted on historic plans within the project area, the location of the line is unknown. AT&T has noted that abandoned lines are located within the hill side, the location of the lines are unknown.

If encountered, contact the engineer immediately. Any changes to the work will be directed by the engineer and shall be compensated under CMS 109.05.

Cell: (216) 854-0899
David.Sobotka@charter.com

Dominion Energy Ohio
320 Springside Drive, Suite 320
Akron, OH 44333
Phone: 330-664-2409
Relocation@dominionenergy.com

Everstream (In cooperation with One Community)
Tom Trusnik, OSP Engineer
800 W. St. Clair Avenue, 2nd Floor
Cleveland, OH 44113
Office: 216-923-2348

Lake County – Department of Utilities
Attn: Randy Rothlisberger
Phone: 440-350-3652
Randy.rothlisberger@lakecountyohio.gov

Lake County – Water Administration Building
105 Main St.
Painesville, Ohio 44077
Sarah A. Cerovski, Deputy Sanitary Engineer
Phone: 440-350-2652
Fax: 440-350-5784
www.lakecountyohio.gov/utilities

MCI
Dan Arz MCI/XO OSP engineer (Cleveland metro area)
12300 Ridge Road
North Royalton, Ohio 44133
Office: 440.457.4832
Cell: 216.570.9343
daniel.arz@verizon.com

DESIGN AGENCY



DESIGNER
KJD

REVIEWER
DB 10/03/22

PROJECT ID
113805

SHEET TOTAL
P.04 31