

**LAK-IR 90 VACANT REST AREAS TP
PID 122879
FINAL TRACINGS SUBMISSION
EARTHWORK AND SEEDING**

CREATED BY:	GG	10/15/2025
CHECKED BY:	TSB	10/17/2025
CORRECTED BY:	GG	11/18/2025
APPROVED BY:	TSB	11/26/2025

122879 EB Decel Earthwork 10-14-2025							
sheet	Station	End Area		Volume		volume sheet totals	
		Cut	Fill	Cut	Fill	CUT	FILL
		SF	SF	CY	CY	CY	CY
	63+26.23	23	0				
	63+50.00	25	0	21	0		
	64+00.00	28	1	68	3	89	3
N/A	64+26.23	11	2	19	2		
	64+26.24	0	0	0	0		
	00+00.00	0	0	0	0		
TOTAL						89	3
						CUT	FILL
						C.Y.	C.Y.
Note: STA. 66+26.23 not included in plans, volume included with STA. 64+00.0							
122879 EB Ramp Earthwork 10-14-2025							
sheet	Station	End Area		Volume		volume sheet totals	
		Cut	Fill	Cut	Fill	CUT	FILL
		SF	SF	CY	CY	CY	CY
	100+00.00	30	2				
	100+50.00	28	3	54	5		
	101+00.00	28	4	52	6	106	11
	101+50.00	28	4	52	7		
	102+00.00	29	2	54	5		
	102+50.00	29	1	54	3	160	15
	103+00.00	30	0	55	1		
	103+50.00	30	1	56	1		
	104+00.00	30	1	55	1	166	3
	104+50.00	31	0	57	1		
	105+00.00	35	0	62	0		
	105+50.00	43	0	72	0	191	1
	106+00.00	48	0	84	0		
	106+50.00	59	0	99	0		
	107+00.00	73	0	122	0	305	0
	107+50.00	84	0	146	0		
	108+00.00	55	1	129	1		
	108+50.00	60	0	107	1	382	2
	109+00.00	90	0	139	0		
	109+50.00	68	0	147	0		
	110+00.00	66	1	124	0	410	0
	110+50.00	87	2	141	2		
	111+00.00	111	7	183	8		
	111+50.00	83	10	180	16	504	26
	112+00.00	400	12	447	21	447	21
	112+50.00	1959	23	2184	32	2184	32
	113+00.00	1981	34	3648	53	3648	53
	113+50.00	1951	47	3641	75	3641	75
	114+00.00	1966	59	3627	98	3627	98
	114+50.00	1488	52	3198	103	3198	103
	115+00.00	1350	57	2627	101	2627	101
	115+50.00	1273	62	2429	110	2429	110
	116+00.00	1034	67	2136	119	2136	119
	116+50.00	350	66	1281	123	1281	123
	117+00.00	117	41	432	99		
	117+50.00	91	27	193	63		
	118+00.00	116	12	192	36	817	198
	118+50.00	124	7	222	17		
	119+00.00	126	3	232	9		
	119+50.00	99	0	208	3	662	29
	120+00.00	72	0	159	0		
	120+50.00	93	0	153	0		
	121+00.00	79	1	159	1	471	1
	121+50.00	65	0	133	1		
	122+00.00	62	0	118	0		
	122+50.00	56	0	109	0	360	1
	123+00.00	46	0	94	0		
	123+50.00	43	1	97	1	191	1
	123+60.04	33	0	14	0		
	123+60.05	0	0	0	0		
TOTAL						29943	1123
						CUT	FILL
						C.Y.	C.Y.
Note: STA. 123+60.04 not included in plans, volume included with STA. 123+5							

122879 WB Accel Earthwork 10-14-2025							
sheet	Station	End Area		Volume		volume sheet totals	
		Cut	Fill	Cut	Fill	CUT	FILL
		SF	SF	CY	CY	CY	CY
	71+01.50	21	0				
	71+50.00	19	0	36	0		
	72+00.00	17	0	34	0	70	0
	72+50.00	19	0	34	0		
	73+00.00	20	0	36	0		
	73+50.00	22	0	39	0	109	0
	74+00.00	22	0	40	0		
	74+50.00	24	0	43	0		
	75+00.00	25	0	45	0	128	0
	75+50.00	25	0	46	0		
	76+00.00	27	0	48	0		
	76+50.00	29	0	51	0	145	0
	77+00.00	30	0	55	0		
	77+50.00	29	0	55	0		
	78+00.00	31	0	55	0	165	0
	78+50.00	32	0	58	0		
	79+00.00	34	0	61	0		
	79+50.00	35	0	64	0	183	0
	80+00.00	37	2	67	1		
	80+50.00	36	2	68	3		
	81+00.00	38	3	69	5	204	9
	81+50.00	38	3	71	5		
	82+00.00	42	2	75	4		
	82+50.00	42	1	78	3	224	12
	83+00.00	44	1	80	3		
	83+50.00	45	2	85	3		
	83+51.57	10	2	2	0		
	83+51.58	0	0	0	0	167	6

Note: STA. 83+51.57 not included in plans, volume included with STA. 83+50

TOTAL	1395	27
	CUT	FILL
	C.Y.	C.Y.

122879 WB Ramp Earthwork 10-14-2025							
sheet	Station	End Area		Volume		volume sheet totals	
		Cut	Fill	Cut	Fill	CUT	FILL
		SF	SF	CY	CY	CY	CY
1							
	200+00.00	45	2	52	2		
	200+50.00	47	2	85	3		
	201+00.00	50	0	90	2	227	7
2							
	201+50.00	53	0	96	0		
	202+00.00	55	1	100	0		
	202+50.00	61	0	107	0	303	0
3							
	203+00.00	76	0	127	0		
	203+50.00	85	1	149	0		
	204+00.00	19	3	96	3	372	3
4							
	204+50.00	20	6	36	8		
	205+00.00	32	2	47	7		
	205+50.00	36	2	62	4	145	19
5							
	206+00.00	26	7	57	9		
	206+50.00	51	6	72	12	129	21
6							
	207+00.00	63	77	106	77	106	77
7							
	207+50.00	97	12	148	83	148	83
8							
	208+00.00	149	198	228	195	228	195
9							
	208+50.00	113	260	243	425	243	425
10							
	209+00.00	129	155	224	385	224	385
11							
	209+50.00	202	17	307	160	307	160
12							
	210+00.00	314	13	478	27	478	27
13							
	210+50.00	418	14	678	24	678	24
14							
	211+00.00	448	15	802	26	802	26
15							
	211+50.00	254	143	650	145	650	145
16							
	212+00.00	86	19	315	149		
	212+50.00	18	20	96	35		
	213+00.00	53	11	66	29	477	213
17							
	213+50.00	80	0	123	11		
	214+00.00	73	0	141	0		
	214+50.00	62	0	125	0	389	11
18							
	215+00.00	58	1	111	1		
	215+50.00	58	0	107	1		
	216+00.00	53	0	103	1	321	3

122879 EB Decel Seeding, Class 1, APP 10-15-2025				
sheet	Station	Slope	Area	Area
		Distance		sheet totals
		FT	SQ. YD.	SQ. YD.
100	63+26.23	3.0		
	63+50.00	4.3	10	
	64+00.00	6.4	42	
	64+26.23	7.9	21	
				52
			TOTAL	52
				S.Y.
122879 EB Ramp Seeding, Class 1, APP 10-15-2025				
sheet	Station	Slope	Area	Area
		Distance		sheet totals
		FT	SQ. YD.	SQ. YD.
	100+00.00	7.9		
	100+50.00	9.3	48	
	101+00.00	10.6	55	103
	101+50.00	10.2	58	
	102+00.00	7.8	50	
	102+50.00	27.1	97	205
	103+00.00	27.1	151	
	103+50.00	27.1	151	
	104+00.00	27.1	151	453
	104+50.00	27.0	150	
	105+00.00	27.0	150	
	105+50.00	24.2	142	442
	106+00.00	32.3	157	
	106+50.00	35.2	188	
	107+00.00	36.6	199	544
	107+50.00	33.7	195	
	108+00.00	3.4	103	
	108+50.00	8.2	32	330
	109+00.00	16.0	67	
	109+50.00	26.3	118	
	110+00.00	35.3	171	356
	110+50.00	41.2	213	
	111+00.00	47.7	247	
	111+50.00	55.2	286	746
	112+00.00	55.6	308	308
	112+50.00	76.6	367	367
	113+00.00	83.7	445	445
	113+50.00	81.7	459	459
	114+00.00	78.6	445	445
	114+50.00	80.1	441	441
	115+00.00	86.4	463	463
	115+50.00	90.9	493	493
	116+00.00	94.0	514	514
	116+50.00	37.8	366	366
	117+00.00	41.4	220	
	117+50.00	41.2	229	
	118+00.00	39.6	224	673
	118+50.00	35.7	209	
	119+00.00	28.5	178	
	119+50.00	21.9	140	527
	120+00.00	14.5	101	
	120+50.00	2.9	48	
	121+00.00	3.1	17	166
	121+50.00	4.9	22	
	122+00.00	21.6	74	
	122+50.00	24.5	128	224
	123+00.00	8.6	92	
	123+50.00	9.8	59	151
	123+60.04	4.4	8	
	123+60.05	0.0	0	
			TOTAL	9221
				S.Y.

Note: STA. 66+26.23 not included in plans, volume included with STA. 64+00.00

Note: STA. 123+60.04 not included in plans, volume included with STA. 123+50

122879 WB Decel Seeding, Class 1, APP 10-15-2025				
sheet	Station	Slope	Area	Area
		Distance		sheet totals
		FT	SQ. YD.	SQ. YD.
	105+50.00	5.0		
	106+00.00	4.9	28	
	106+04.25	0.0	1	
				29
			TOTAL	29 S.Y.
122879 WB Ramp Seeding, Class 1, APP 10-15-2025				
sheet	Station	Slope	Area	Area
		Distance		sheet totals
		FT	SQ. YD.	SQ. YD.
	200+00.00	25.1		
	200+50.00	27.1	145	
	201+00.00	27.1	151	296
	201+50.00	27.1	151	
	202+00.00	25.1	145	
	202+50.00	3.3	79	375
	203+00.00	5.0	23	
	203+50.00	3.0	22	
	204+00.00	11.1	39	84
	204+50.00	14.8	72	
	205+00.00	19.0	94	
	205+50.00	25.4	123	289
	206+00.00	29.9	154	
	206+50.00	37.1	186	340
	207+00.00	57.2	262	262
	207+50.00	46.3	288	288
	208+00.00	63.0	304	304
	208+50.00	63.4	351	351
	209+00.00	56.4	333	333
	209+50.00	44.8	281	281
	210+00.00	41.0	238	238
	210+50.00	40.6	227	227
	211+00.00	40.4	225	225
	211+50.00	44.0	234	234
	212+00.00	26.1	195	
	212+50.00	21.5	132	
	213+00.00	36.8	162	489
	213+50.00	27.4	178	
	214+00.00	24.3	144	
	214+50.00	30.0	151	473
	215+00.00	19.4	137	
	215+50.00	22.0	115	
	216+00.00	21.4	121	373
	216+50.00	21.5	119	
	217+00.00	23.2	124	
	217+50.00	23.1	129	372
	218+00.00	21.1	123	
	218+50.00	17.7	108	
	219+00.00	15.1	91	322
	219+50.00	15.0	84	
	220+00.00	18.2	92	
	220+50.00	17.1	98	274
	221+00.00	15.8	91	
	221+50.00	14.6	84	
	221+56.62	14.6	11	186
			TOTAL	6616 S.Y.

EARTHWORK TOTALS (EASTBOUND TRUCK PARKING)

ITEM 203	EXCAVATION	31509	CY
ITEM 203	EMBANKMENT	1150	CY
ITEM 659	SEEDING AND MULCHING	9901	SY

TOTALS CARRIED TO GENERAL SUMMARY

EARTHWORK TOTALS (WESTBOUND TRUCK PARKING)

ITEM 203	EXCAVATION	8595	CY
ITEM 203	EMBANKMENT	1863	CY
ITEM 659	SEEDING AND MULCHING	9030	SY

TOTALS CARRIED TO GENERAL SUMMARY

EARTHWORK TOTALS

ITEM 203	EXCAVATION	40104	CY
ITEM 203	EMBANKMENT	3013	CY
ITEM 659	SEEDING AND MULCHING	18931	SY

TOTALS CARRIED TO GENERAL SUMMARY

