

MODEL: Sheet PAPER SIZE: 17x11 (in.) DATE: 4/21/2025 TIME: 4:57:18 PM USER: sheikha2048
www.tbhinfo-dpw.bentley.com/shdinfo-dpw-02/Documents/01 Active Projects/District 09/Lawrence/117529/401-Engineering_BIR/Roadway/Sheets/117529_GG002.dgn

GENERAL SUMMARY - 2

ARCADIS 23 TRIANGLE PARK DRIVE SUITE 2000 CINCINNATI, OH 45246 (513) 962-9141 www.arcadis.com	
DESIGNER MJT	
REVIEWER KDK 01-17-25	
PROJECT ID 117529	
SHEET	TOTAL
P.7	29

ESTIMATED QUANTITIES					
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	SHEET #
202	11201	LS		PORTIONS OF STRUCTURE REMOVED, AS PER PLAN	2 OF 9
202	98000	LS		REMOVAL, MISC.: GABION WALLS	2 OF 9
503	11100	LS		COFFERDAMS AND EXCAVATION BRACING	
503	21301	LS		UNCLASSIFIED EXCAVATION, AS PER PLAN	2 OF 9
503	31101	41	CY	ROCK EXCAVATION, AS PER PLAN	2 OF 9
509	10000	7174	LB	EPOXY COATED STEEL REINFORCEMENT	
511	46010	17	CY	CLASS QC1 CONCRETE, RETAINING/WINGWALL NOT INCLUDING FOOTING	
511	46510	35	CY	CLASS QC1 CONCRETE, FOOTING	
512	10100	67	SY	SEALING OF CONCRETE SURFACES (EPOXY - URETHANE)	
512	33000	356	SY	TYPE 2 WATERPROOFING	
516	13600	33	SF	1" PREFORMED EXPANSION JOINT FILLER	
518	21200	16	CY	POROUS BACKFILL WITH GEOTECHNICAL FABRIC	
SPECIAL	530E00200	LS		STRUCTURES, MISC.: PRECONSTRUCTION CONDITION SURVEY	2 OF 9
601	11001	5	SY	RIPRAP, TYPE D, AS PER PLAN	2 OF 9
601	32004	53	CY	ROCK CHANNEL PROTECTION, TYPE A WITH GEOTEXTILE FABRIC	
611	94981	121	FT	10'X4' CONDUIT, TYPE A, 706.05, AS PER PLAN	2, 8 OF 9
611	98651	1	EACH	CATCH BASIN FRAME AND GRATE, AS PER PLAN	2 OF 9

 REVISED THE ITEM EXTENSION