

SHEET NUM.										PART.	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
P.4		P.5		P.8		P.22										
															ROADWAY	
				1							201	11000	LS		CLEARING AND GRUBBING	P.4
				747							202	20010	1	EACH	HEADWALL REMOVED	
				44							202	23000	747	SY	PAVEMENT REMOVED	
											202	35100	44	FT	PIPE REMOVED, 24" AND UNDER	
59											203	10000	59	CY	EXCAVATION	
287											203	20000	287	CY	EMBANKMENT	
				868							204	10000	868	SY	SUBGRADE COMPACTION	
				1							204	45000	1	HOUR	PROOF ROLLING	
															EROSION CONTROL	
				11							601	34400	11	CY	ROCK CHANNEL PROTECTION, WITH GROUT, TYPE C	
427											659	10000	427	SY	SEEDING AND MULCHING	P.4
22											659	14000	22	SY	REPAIR SEEDING AND MULCHING	P.4
0.06											659	20000	0.06	TON	COMMERCIAL FERTILIZER	P.4
0.09											659	31000	0.09	ACRE	LIME	P.4
2											659	35000	2	MGAL	WATER	P.4
5,000											832	30000	5,000	EACH	EROSION CONTROL	P.4
															DRAINAGE	
				0.3							602	20000	0.3	CY	CONCRETE MASONRY	
				482							605	11100	482	FT	6" SHALLOW PIPE UNDERDRAINS	
				9							611	00510	9	FT	6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS	
				21							611	00900	21	FT	6" CONDUIT, TYPE B	
				36							611	05700	36	FT	15" CONDUIT, TYPE A, 706.01, 707.01, 707.02, OR 707.33	
															PAVEMENT	
		50									253	02000	50	CY	PAVEMENT REPAIR	P.5
				93							301	56000	93	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
				146							304	20000	146	CY	AGGREGATE BASE	
		200		97							407	10000	297	GAL	TACK COAT	P.5
				16							411	10000	16	CY	STABILIZED CRUSHED AGGREGATE	
		100		68							441	70000	168	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22	P.5
		50									617	10100	50	CY	COMPACTED AGGREGATE	P.5
		10									617	25000	10	MGAL	WATER	P.5
															TRAFFIC CONTROL	
				6							621	00100	6	EACH	RPM	
				6							621	54000	6	EACH	RAISED PAVEMENT MARKER REMOVED	
				0.14							642	00104	0.14	MILE	EDGE LINE, 6", TYPE 1	
				0.07							642	00300	0.07	MILE	CENTER LINE, TYPE 1	
															RETAINING WALLS (LAW-775-19.50)	
						LS					503	21300	LS		UNCLASSIFIED EXCAVATION	
						1,925					507	00400	1,925	FT	STEEL PILES, MISC.: W24X104 STEEL BEAM, FURNISHED, AS PER PLAN	P.22
						3,968					511	71200	3,968	SF	CONCRETE, MISC.: PRECAST REINFORCED CONCRETE LAGGING PANEL	P.22
						187					518	21200	187	CY	POROUS BACKFILL WITH GEOTEXTILE FABRIC	
						471					524	94703	471	FT	DRILLED SHAFTS, 36" DIAMETER, ABOVE BEDROCK, AS PER PLAN	P.22
						600					524	94705	600	FT	DRILLED SHAFTS, 36" DIAMETER, INTO BEDROCK, AS PER PLAN	P.22
															MAINTENANCE OF TRAFFIC	
		8									614	11110	8	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	P.5
											614	12420	LS		DETOUR SIGNING	
		50									616	10000	50	MGAL	WATER	P.5
															INCIDENTALS	
											614	11000	LS		MAINTAINING TRAFFIC	
											619	16000	3	MNTH	FIELD OFFICE, TYPE A	
											623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
											624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY
ARCADIS
 23 TRIANGLE PARK DRIVE, SUITE 2000
 CHARLOTTE, NC 28269
 (704) 513-9421
 www.arcadis.com

DESIGNER
MJT

REVIEWER
JBK

PROJECT ID
10-18-24

SHEET TOTAL
118779
P.7 | **41**