


SHEET NUM.											PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
3	4	5	7	8	14	16	22				01/NHS/10							
												ROADWAY						
											LS	201	11000	LS		CLEARING AND GRUBBING		
				284							284	202	23000	284	SY	PAVEMENT REMOVED		
				165							165	203	10001	165	CY	EXCAVATION, AS PER PLAN	3	
											87	203	20000	87	CY	EMBANKMENT		
4											4	209	15000	4	STA	RESHAPING UNDER GUARDRAIL		
40											40	209	70000	40	CY	BORROW		
				12.5							12.5	606	15050	12.5	FT	GUARDRAIL, TYPE MGS		
				393.75							393.75	606	16051	393.75	FT	GUARDRAIL REBUILT, TYPE MGS, AS PER PLAN	3	
				100							100	606	17350	100	FT	GUARDRAIL, TYPE MGS, 25' LONG-SPAN		
				2							2	606	27861	2	EACH	ANCHOR ASSEMBLY REBUILT, MGS TYPE E, AS PER PLAN	3	
				2							2	606	27911	2	EACH	ANCHOR ASSEMBLY REBUILT, MGS TYPE T, AS PER PLAN	3	
												EROSION CONTROL						
				99							99	601	32104	99	CY	ROCK CHANNEL PROTECTION, TYPE B WITH GEOTEXTILE FABRIC		
750											750	659	00510	750	SY	SEEDING AND MULCHING, CLASS 2		
0.11											0.11	659	20000	0.11	TON	COMMERCIAL FERTILIZER		
0.16											0.16	659	31000	0.16	ACRE	LIME		
4											4	659	35000	4	MGAL	WATER		
											7,000	832	30000	7,000	EACH	EROSION CONTROL		
												PAVEMENT						
				304							304	204	10000	304	SY	SUBGRADE COMPACTION		
				464							464	252	01500	464	FT	FULL DEPTH PAVEMENT SAWING		
				533							533	254	01000	533	SY	PAVEMENT PLANING, ASPHALT CONCRETE (VARIABLE DEPTH)		
				107							107	301	56000	107	CY	ASPHALT CONCRETE BASE, PG64-22, (449)		
				112							112	304	20000	112	CY	AGGREGATE BASE		
				177							177	407	20000	177	GAL	NON-TRACKING TACK COAT		
				48							48	441	50100	48	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG70-22M		
				56							56	441	50300	56	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448)		
												TRAFFIC CONTROL						
				7							7	621	54000	7	EACH	RAISED PAVEMENT MARKER REMOVED		
				0.11							0.11	642	00104	0.11	MILE	EDGE LINE, 6", TYPE 1		
				0.06							0.06	642	00300	0.06	MILE	CENTER LINE, TYPE 1		
												STRUCTURE OVER 20 FOOT SPAN (LIC-37-0963)						
FOR STRUCTURE QUANTITIES, SEE SHEET 17/27																		
												MAINTENANCE OF TRAFFIC						
			10								10	410	13000	10	CY	TRAFFIC COMPACTED SURFACE, TYPE C		
											LS	614	12421	LS		DETOUR SIGNING, AS PER PLAN	5	
			10								10	614	13000	10	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC		
2											2	614	18601	2	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	4	
												INCIDENTALS						
											LS	614	11000	LS		MAINTAINING TRAFFIC		
											LS	623	10001	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER PLAN	3	
											LS	624	10000	LS		MOBILIZATION		

DESIGN AGENCY



DESIGNER
MHK

REVIEWER
JKS 02-20-24

PROJECT ID
109271

SHEET TOTAL
P.6 | 27