ROUTE	STATION FROM	STATION TO	WIDTH FT	SIDE	LENGTH FT	AREA (CA = CADD GENERATED AREA) SF	204 SUBGRADE COMPACTION SY	254 PAVEMENT PLANING, ASPHALT CONCRETE (3.25") SY		301 ASPHALT CONCRETE BASE, PG64-22, (449) CY	304 AGGREGATE BASE CY		407 NON-TRACKING TACK COAT (0.055 GAL/SY) GAL	407 NON-TRACKING TACK COAT (0.085 GAL/SY) GAL	442 ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446) CY	442 ASPHALT CONCRETE INTERMEDIATE COURSE, 19 MM, TYPE A (446) CY	452 9" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P SY		255 FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT, CLASS SY						
							DEPTH	T=3.25"		T=6.00"	T=6.00"		DEPTH	DEPTH	T=1.50"	T=1.75"	T=9.00"		DEPTH							
THORNWOOD DRIVE	44+25.00	44+50.00	20.7	LT/RT	25.0			57.5					3.2	4.9	2.4	2.8										
	44+50.00	44+91.52	20.6	LT/RT	41.6		117.8			15.8	21.2		10.5		4.0	4.7										
	44+91.52	47+61.82	VARIES	LT/RT	270.3	10403.0	1306.1			192.7	227.7		127.2		48.2	56.2										
	47+61.82	48+15.64	45.4	LT/RT	53.9		300.9			45.2	52.2		29.9		11.3	13.2										
	48+15.64	49+13.88	VARIES	LT	98.3	1626.2	48.7			30.2	39.4		19.9		7.6	8.8										
	48+15.64	49+13.88	VARIES	RT	98.3	3908.6	44.5			72.4	80.8		47.8		18.1	21.2										
THORNWOOD CROSSING	50+84.74	52+46.14	VARIES	LT	161.5	5570.0	678.8			103.2	115.3		68.1		25.8	30.1										
	50+84.74	52+46.14	VARIES	RT	161.5	6388.2	769.7			118.3	130.5		78.1		29.6	34.6										
	52+46.14	54+99.02	64	LT/RT	252.9		1938.8			299.8	332.5		197.9		75.0	87.5										
	54+99.02	55+29.02	71.2	LT/RT	30.0		254.0				42.4															
	59+53.01	59+83.01	71.2	LT/RT	30.0		254.0				42.4															
	59+83.01	63+21.96	64	LT/RT	339.0		2598.7				434.9						2410.4									
	63+21.96	65+61.96	VARIES	LT/RT	240.0	13442.9	1493.7				249.0						1493.7									
	63+21.96	65+61.96	4	LT	240.0		146.7				20.0						106.7									
	63+36.00	65+61.96	4	RT	226.0		138.1				18.9						100.5									
	65+61.96	66+18.08	56	LT/RT	56.2		22.3				59.3						349.2									
RIVER RD	88+61.00	88+80.95	VARIES	RT	20.0	39.9	7.8			0.9	1.1		0.5		0.2	0.3										
	88+61.00	90+85.00	VARIES	RT	224.0	657.6	110.4			12.2	12.2		8.1		3.1	3.6										
	88+80.95	90+89.57	VARIES	RT	208.7	890.1	133.7			17.8	19.7		10.9		4.2	4.9										
	90+40.00	90+85.00	18.3	LT/RT	45.0			91.5					5.1	7.8	3.9	4.5										
	90+85.00	91+16.00	VARIES	LT/RT	31.0	725.3	91.0			13.5	13.5		8.9		3.4	4.0										
	90+85.00	91+28.65	VARIES	LT	43.7	124.1	21.1			2.6	3.0		1.6		0.6	0.7										
	90+89.57	92+43.59	4	RT	154.1		94.2			12.4	13.8		7.6		2.9	3.4										
	91+16.00	96+95.00	24	LT/RT	579.0		1737.0			257.4	257.4		169.9		64.4	75.1										
	91+28.65	91+71.38	VARIES	LT	42.8	221.8	31.8			4.4	4.8		2.8		1.1	1.2										
	91+71.38	96+95.00	4	LT	523.7		320.0			42.0	46.9		25.6		9.7	11.4										
	92+43.59	92+97.91	VARIES	RT	54.4	291.0	41.4			5.8	6.3		3.6		1.4	1.6										
	92+97.91	94+18.06	4	RT	120.2		73.5			9.7	10.8		5.9		2.3	2.6										
	94+84.08	96+95.00	4	RT	211.0		128.9			17.0	18.9		10.4		4.0	4.6										
	96+95.00	98+97.79	VARIES	LT	202.8	3333.1	444.1			61.8	79.6		40.8		15.5	18.1										
	96+95.00	98+97.79	VARIES	RT	202.8	3246.2	431.3			60.2	74.6		39.7		15.1	17.6										
RIGID PAVEMENT REPLACEMENT																										
	62+28.00	62+98.00	VARIES	LT/RT	70.0	9073.7													1008.2							
SUBTOTAL							13779.0	149.0		1395.3	2429.1		924.0	12.7	353.8	412.7	4460.5		1008.2							
SUBTOTAL							13779.0	149.0		1396.0	2430.0		937		354.0	413.0	4461.0		1009							
TOTALS CARRIED TO GENERAL SUMMARY							22669	4715		2553	3927		2353		836	975	4787		1009							

ROUTE	STATION		WIDTH	SIDE	LENGTH	AREA (CA = CADD GENERATED AREA)	204	254		301	304		407	407	442	442	452
							DEPTH	T=3.25"		T=6.00"	T=6.00"		DEPTH	DEPTH	T=1.50"	T=1.75"	T=9.00"
							SUBGRADE COMPACTION	PAVEMENT PLANING, ASPHALT CONCRETE (3.25")		ASPHALT CONCRETE BASE, PG64-22, (449)	AGGREGATE BASE		NON-TRACKING TACK COAT (0.055 GAL/SY)	NON-TRACKING TACK COAT (0.085 GAL/SY)	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446)	ASPHALT CONCRETE INTERMEDIATE COURSE, 19 MM, TYPE A (446)	9" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P
	FROM	TO	FT		FT	SF	SY	SY		CY	CY		GAL	GAL	CY	CY	SY
REDDINGTON RD	101+02.00	101+93.43	16	LT	91.5		3.0			27.1	34.8		17.9		6.8	8.0	
	101+02.00	101+93.43	18.9	LT	91.5		208.2			31.9	35.3		21.1		8.0	9.3	
	101+02.00	101+93.43	18	RT	91.5		215.0			30.5	38.1		20.2		7.7	8.9	
	101+93.43	104+94.94	VARIES	LT/RT	301.6	11230.0	1415.3			208.0	247.1		137.3		52.0	60.7	
	104+94.94	105+02.94	5	LT	8.0		5.8			0.8	0.9		0.5		0.2	0.3	
	104+94.94	105+50.00	9	RT	55.1		64.3			9.6	10.1		6.1		2.3	2.7	
	105+02.94	112+20.63	6	LT	717.7		598.1			84.2	90.8		52.7		20.0	23.3	
	105+50.00	106+00.00	16.5	LT/RT	50.0			91.7					5.1	7.8	3.9	4.5	
	105+50.00	106+00.00	7.5	RT	50.0		50.0			7.3	7.8		4.6		1.8	2.1	
	106+00.00	111+00.00	18	LT/RT	500.0			1000.0					55.0	85.0	41.7	48.7	
	106+00.00	111+00.00	6	RT	500.0		416.7			58.7	63.3		36.7		13.9	16.3	
	111+00.00	114+50.00	20	LT/RT	350.0			777.8					42.8	66.2	32.5	37.9	
	111+00.00	112+84.32	4	RT	184.4		112.7			14.8	16.5		9.1		3.5	4.0	
	112+20.73	112+71.17	9	LT	50.5		58.9			8.8	9.2		5.6		2.2	2.5	
	112+71.17	113+71.00	12	LT	99.9		149.8			22.8	23.8		14.7		5.6	6.5	
	113+71.00	115+50.00	VARIES	LT	110.6	1245.8	18.5			0.7	1.7		15.3		5.8	6.8	
	114+50.00	115+50.00	18	LT/RT	100.0			200.0					11.0	17.0	8.4	9.8	
	114+50.00	115+50.00	4	RT	100.0		61.2			8.1	9.0		4.9		1.9	2.2	
CHERRY VALLEY RD	26+47.00	26+72.00	VARIES	LT/RT	25.0	940.7		104.6					5.8	8.9	4.4	5.1	
	26+72.00	27+50.74	37.5	LT/RT	78.8		328.1				54.7						82.1
	26+72.00	27+63.59	VARIES	LT	91.6	1067.4	137.1				21.5						29.7
	26+72.00	27+48.83	VARIES	RT	76.9	1274.8	172.2				30.8						35.5
	28+18.18	28+55.02	VARIES	LT/RT	36.9	803.8	106.0				17.7						22.4
	28+55.02	33+50.00	20	LT/RT	495.0			1100.0					60.5	93.5	45.9	53.5	
	38+39.04	38+97.97	VARIES	LT	59.0	529.0		58.8					3.3	5.0	2.5	2.9	
	38+52.65	39+24.50	36	LT/RT	71.9			287.4					15.9	24.5	12.0	14.0	
	38+56.38	38+91.20	VARIES	RT	34.9	677.7		75.3					4.2	6.5	3.2	3.7	
	38+66.66	39+24.50	VARIES	RT	57.9	996.1	128.2			19.1	20.1		12.2	9.5	4.7	5.4	
	39+24.50	41+64.00	VARIES	LT/RT	239.5	7806.3		867.4					47.8	73.8	36.2	42.2	
	41+64.00	41+71.53	3	LT	7.6			2.6					0.2	0.3	0.2	0.2	
OLD RIVER RD	10+10.81	10+36.19	VARIES	RT	25.4	175.1	26.2			3.5	3.9		2.2		0.9	1.0	
	10+12.11	14+20.33	20	LT/RT	408.3		1043.3			156.2	163.9		99.8		37.8	44.1	
	10+13.22	10+44.16	VARIES	LT	31.0	261.9	35.8			5.1	5.5		3.3		1.3	1.5	
	14+20.33	15+37.79	VARIES	LT/RT	117.5	6386.3	761.1			120.2	123.1		78.1		29.6	34.5	
ROUNDABOUT	1+00.00	6+27.79	16	LT	373.9	5607.8	677.1				112.9						155.8
	1+00.00	6+27.79	16	LT/RT	373.9	18323.6	2096.6			339.4	353.9		224.0		84.9	99.0	
SUBTOTAL							8889.2	4565.6		1156.8	1496.4		1017.9	398.0	481.8	561.6	325.5
TOTAL							8890.0	4566.0		1157.0	1497.0		1416		482.0	562.0	326.0