SHEET NUMBER										PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
4	5	6	7	11	12	13	14	15	19	01/STR	02/S>2						
																ROADWAY	
				576						576		202	23000	576	SY	PAVEMENT REMOVED	
37.6										37.6		202	23001	37.6	SY	PAVEMENT REMOVED, AS PER PLAN	4
						725				525	200	202	38000	725	FT	GUARDRAIL REMOVED	
						4					4	202	42000	4	EACH	ANCHOR ASSEMBLY REMOVED, TYPE A	
						1				1		202	42010	1	EACH	ANCHOR ASSEMBLY REMOVED, TYPE E	
						1				1		202	42040	1	EACH	ANCHOR ASSEMBLY REMOVED, TYPE T	
						2				2		202	42050	2	EACH	ANCHOR ASSEMBLY REMOVED, TYPE B	
						4					4	202	47000	4	EACH	BRIDGE TERMINAL ASSEMBLY REMOVED	
76.4										41.4	35	203	20000	76.4	CY	EMBANKMENT	
				576						576		204	10000	576	SY	SUBGRADE COMPACTION	
				192						192		204	13000	192	CY	EXCAVATION OF SUBGRADE, 12"	
				192						192		204	30020	192	CY	GRANULAR MATERIAL, TYPE C, 12"	
				576						576		204	50000	576	SY	GEOTEXTILE FABRIC	
						11				6	5	209	15000	11	STA	RESHAPING UNDER GUARDRAIL	
				19						10	9	209	60500	19	MILE	LINEAR GRADING	
17.94										9.44	8.5	209	72050	17.94	MILE	PREPARING SUBGRADE FOR SHOULDER PAVING	
						175				13	162	606	15050	175	FT	GUARDRAIL, TYPE MGS	
						387.5				387.5		606	15100	387.5	FT	GUARDRAIL, TYPE MGS WITH LONG POSTS	
						50				50		606	17360	50	FT	GUARDRAIL, TYPE MGS, LONG-SPAN	
						7				3	4	606	26150	7	EACH	ANCHOR ASSEMBLY, MGS TYPE E	
						5				1	4	606	26550	5	EACH	ANCHOR ASSEMBLY, MGS TYPE T	
						4					4	606	35140	4	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE 4	
1										1		623	39500	1	EACH	MONUMENT ASSEMBLY ADJUSTED TO GRADE	
																EROSION CONTROL	
25.5										13.8	11.7	601	20010	25.5	CY	CRUSHED AGGREGATE SLOPE PROTECTION	
636.7										345.3	291.4	659	10000	636.7	SY	SEEDING AND MULCHING	
0.09										0.05	0.04	659	20000	0.09	TON	COMMERCIAL FERTILIZER	
4										2	2	659	35000	4	MGAL	WATER	
										300		832	30000	300	EACH	EROSION CONTROL	
																PAVEMENT	
1,175										625	550	253	02000	1,175	CY	PAVEMENT REPAIR	
				93,662						74,908	18,754	254	01000	93,662	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1 ½"	
				47,992	777						48,769	254	01000	48,769	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1 ¾"	
				64						64		301	56000	64	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
16.7										16.7		301	56001	16.7	CY	ASPHALT CONCRETE BASE, (449), AS PER PLAN, PG64-22	4
				17						17		304	20000	17	CY	AGGREGATE BASE	
				7,872	43					4,201	3,714	407	10000	7,915	GAL	TACK COAT	
59				444						473	30	442	10000	503	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446)	
				5,848	38					2,734	3,152	442	10001	5,886	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446), AS PER PLAN, PG70-22M	4
	69										69	SPECIAL	51631200	69	FT	SAWING AND SEALING BITUMINOUS CONCRETE JOINTS	5
				1,779						926	853	617	10100	1,779	CY	COMPACTED AGGREGATE	
				7						4	3	618	43000	7	MILE	RUMBLE STRIPES, CENTER LINE (ASPHALT CONCRETE)	
				5,646						5,646		872	10000	5,646	FT	VOID REDUCING ASPHALT MEMBRANE (VRAM)	
																TRAFFIC CONTROL	
							513	161		346	328	621	00100	674	EACH	RPM	
							513	161		346	328	621	54000	674	EACH	RAISED PAVEMENT MARKER REMOVED	
						23				12	11	626	00116	23	EACH	BARRIER REFLECTOR, TYPE 5, 50FT SPACING, BI-DIRECTIONAL	
							13.8	4.9		9.7	9	642	00104	18.7	MILE	EDGE LINE, 6", TYPE 1	
							7.2	2.5		5	4.7	642	00300	9.7	MILE	CENTER LINE, TYPE 1	
							215			215		642	01500	215	FT	DOTTED LINE, 4", TYPE 1	
							557			557		644	00404	557	FT	CHANNELIZING LINE, 12"	
							47				47	644	00500	47	FT	STOP LINE	
								87			87	644	00630	87	FT	CROSSWALK LINE, 24"	
							243			243		644	00700	243	FT	TRANSVERSE/DIAGONAL LINE	
							128			128		644	00900	128	SF	ISLAND MARKING	
							6			6		644	01300	6	EACH	LANE ARROW	

GENERAL SUMMARY

DESIGN AGENCY

DESIGNER MEK

REVIEWER DEK 05/11/26

PROJECT ID 114881

SHEET P.9 TOTAL 19

LUC-295-2.48

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 10/19/2026 TIME: 12:03:29 PM PLTDRV: OHDOT_PDF_Color.pltcfg PENTBL: OHDOT_PenC.tbl USER: Matthew.Kelner@dot.ohio.gov WORKSPACE: OHDOTCEv02 WORKSET: 114881 PRODUCT: OpenRoadsDesigner 24.00.00.205
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 02\Lucas\114881400-Engineering\Roadway\Sheets\114881_GG001.dgn

REF NO.	SHEET NO.	STATION TO STATION			OFFSET	SIDE	202 GUARDRAIL REMOVED	202 ANCHOR ASSEMBLY REMOVED, TYPE A	202 ANCHOR ASSEMBLY REMOVED, TYPE E	202 ANCHOR ASSEMBLY REMOVED, TYPE T	202 ANCHOR ASSEMBLY REMOVED, TYPE B	202 BRIDGE TERMINAL ASSEMBLY REMOVED	209 RESHAPING UNDER GUARDRAIL	606 GUARDRAIL, TYPE MGS	606 GUARDRAIL, TYPE MGS WITH LONG POSTS	606 GUARDRAIL, TYPE MGS, LONG-SPAN	606 ANCHOR ASSEMBLY, MGS TYPE E	606 ANCHOR ASSEMBLY, MGS TYPE T	606 BRIDGE TERMINAL ASSEMBLY, TYPE 4	626 BARRIER REFLECTOR, TYPE 5, 50FT SPACING, BI-DIRECTIONAL
							FT	EACH	EACH	EACH	EACH	EACH	STA	FT	FT	FT	EACH	EACH	EACH	EACH
		SR-295																		
GR-1	17	288+07.44	TO	291+32.41	VARIES	RT	275				2		3.0		200	25	2			6
GR-2	17	288+37.32	TO	291+20.39	VARIES	LT	250		1	1			2.8	12.5	187.5	25	1	1		6
GR-3	17	507+16.28	TO	508+42.63	16.0	LT	50	1				1	1.1	37.5			1	1	1	3
GR-4	17	507+21.10	TO	508+34.95	17.0	RT	50	1				1	1.0	25			1	1	1	2
GR-5	17	509+11.26	TO	509+47.34	VARIES	RT	50	1				1	1.1	37.5			1	1	1	3
GR-6	17	509+23.51	TO	510+74.90	16.4	LT	50	1				1	1.4	62.5			1	1	1	3
TOTALS CARRIED TO GENERAL SUMMARY							725	4	1	1	2	4	11	175	387.5	50	7	5	4	23

ROADWAY SUBSUMMARY

LUC-295-2.48

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 10/19/2026 TIME: 11:59:14 AM PLTDRV: OHDOT_PDF_Color.pltcfg PENTBL: OHDOT_PenC.tbl USER: Matthew.Ketner@dot.ohio.gov WORKSPACE: OHDOTCEv02 WORKSET: 114881 PRODUCT: OpenRoadsDesigner 24.00.00.205
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 02\Lucas\114881\400-Engineering\Roadway\Sheets\114881_GS002.dgn

DESIGN AGENCY

DESIGNER MEK

REVIEWER DEK 05/11/26

PROJECT ID 114881

SHEET P.13 | TOTAL 19