

**CONTINGENCY QUANTITIES**  
THE CONTRACTOR SHALL NOT ORDER MATERIALS OR PERFORM WORK FOR ITEMS DESIGNATED BY PLAN NOTE TO BE USED "AS DIRECTED BY THE ENGINEER" UNLESS AUTHORIZED BY THE ENGINEER. THE ACTUAL WORK LOCATIONS AND QUANTITIES USED FOR SUCH ITEMS SHALL BE INCORPORATED INTO THE FINAL CHANGE ORDER GOVERNING COMPLETION OF THIS PROJECT.

**UTILITIES**  
LISTED BELOW ARE ALL UTILITIES LOCATED WITHIN THE PROJECT CONSTRUCTION LIMITS TOGETHER WITH THEIR RESPECTIVE OWNERS:

OHIO EDISON COMPANY 730 SOUTH AVENUE YOUNGSTOWN, OHIO 44502 (330) 740-7635 ATTN.: MR. BILL SPEECE	A1&T 2933 SALT SPRINGS ROAD YOUNGSTOWN, OHIO 44509 (330) 270-8816 ATTN.: MR. HAROLD MAYNARD
---	---

DOMINION EAST OHIO GAS 320 SPRINGSIDE DRIVE AKRON, OHIO 44333 (330) 664-2409 ATTN.: MS. MARY LONG	ACCESS 425 W. MAIN STREET CANFIELD, OHIO 44406 (330) 702-9832 ATTN.: MS. LISA SMITH
---	---

COMCAST 7820 DIVISION DRIVE MENTOR, OHIO 44060 (440) 974-3401 ATTN.: MR. MICHAEL JONES	AQUA OHIO STRUTHERS/MAHONING VALLEY DIVISION 235 STATE STREET STRUTHERS, OHIO 44471 (330) 755-2163 ATTN.: MR. ROBERT KIMMEL
--	--

THE LOCATION OF THE UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE AS OBTAINED FROM THE OWNERS AS REQUIRED BY SECTION 153.64 O.R.C.

**PERMITS, LICENSES AND TAXES**  
THE CONTRACTOR SHALL PROCURE ALL PERMITS AND LICENSES, PAY ALL CHARGES, FEES AND TAXES, AND GIVE ALL NOTICES NECESSARY AND INCIDENTAL TO THE DUE AND LAWFUL PROSECUTION OF THE WORK.

PAYMENT FOR THE ABOVE SHALL BE INCLUDED IN THE VARIOUS ITEMS OF WORK TO BE PERFORMED IN THIS CONTRACT. NO SEPARATE PAYMENT WILL BE MADE.

**PROPERTY PINS**  
DUE TO THE CLOSE PROXIMITY OF PROPERTY IRON PINS TO THE CONSTRUCTION AREA, SPECIAL CARE SHALL BE TAKEN TO AVOID THEIR DISTURBANCE. IF ANY PROPERTY IRON PIN SHOULD HAPPEN TO BE DISTURBED, THE CONTRACTOR SHALL HAVE THE PIN RESET BY A REGISTERED SURVEYOR AT HIS OWN EXPENSE. THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER WRITTEN DOCUMENTATION THAT THE PROPERTY PINS WERE RESET BY A REGISTERED SURVEYOR. ALL PROPERTY PINS NEEDING RESETTING MUST BE RESET PRIOR TO THE "FINAL WALK THRU" OF THE PROJECT.

**RECORD RETENTION**  
AS THE LPA (NEW MIDDLETOWN VILLAGE), ODOT, OR THE UNITED STATES GOVERNMENT MAY LEGITIMATELY REQUEST FROM TIME TO TIME, THE CONTRACTOR AGREES TO MAKE AVAILABLE FOR INSPECTION AND/OR REPRODUCTION BY THE LPA, ODOT OR UNITED STATES GOVERNMENT, ALL RECORDS, BOOKS, AND DOCUMENTS OF EVERY KIND AND DESCRIPTION THAT RELATE TO THIS PROJECT.

**MAINTENANCE OF PEDESTRIAN TRAFFIC**  
THE CONTRACTOR IS NOT PERMITTED TO CLOSE THE EXISTING WALK TO PEDESTRIANS AT ANY TIME. PEDESTRIAN TRAFFIC IS TO BE MAINTAINED BY THE CONTRACTOR AT ALL TIMES. OPEN TRENCHES ON THIS PROJECT WILL BE BACKFILLED TO THE EXISTING GROUND LEVEL BY THE END OF EACH WORK DAY. THE CONTRACTOR SHALL BE CLEAR OF THE EXISTING WALK AT THE END OF EACH WORK DAY. PAYMENT FOR THE ABOVE STATED SHALL BE INCLUDED WITH ITEM 614 - MAINTAINING TRAFFIC.

**TELEVISIONING OF THE SITE**  
PRIOR TO ACTUAL CONSTRUCTION, THE CONTRACTOR SHALL TAKE, OR HAVE TAKEN TELEVISED PICTURES OF THE ENTIRE LENGTH AND WIDTH OF THE WORK SITE.

THE CONTRACTOR SHALL NOTIFY THE OFFICE OF THE VILLAGE OF NEW MIDDLETOWN ROAD DEPARTMENT PRIOR TO TAKING OF PICTURES. REPRESENTATIVES OF NEW MIDDLETOWN AND THE ENGINEER SHALL BE PRESENT WHEN THE PICTURES ARE TAKEN.

PICTURES SHALL BE RECORDED ON A DIGITAL MEDIA CARD, HAVING A MINIMUM PLAYBACK TIME OF 30 MINUTES, COLOR, WITH AUDIO.

THE CARD SHALL BECOME THE PROPERTY OF THE VILLAGE OF NEW MIDDLETOWN AND SHALL BE DELIVERED BY THE CONTRACTOR TO THE OFFICE OF THE ROAD SUPERINTENDENT. PAYMENT FOR THE PERFORMANCE OF THIS WORK SHALL BE INCLUDED IN THE VARIOUS ITEMS OF WORK TO BE PERFORMED IN THIS CONTRACT. NO SEPARATE PAYMENT WILL BE MADE.

**SPECIAL CARE**  
SPECIAL CARE SHALL BE TAKEN DURING THE INSTALLATION OF THE IMPROVEMENTS IN THESE PLANS SO AS NOT TO DAMAGE THE EXISTING TREES OR SHRUBS CLOSE TO THE CONSTRUCTION AREA. SHOULD ANY TREES REQUIRE PRUNING, THEY SHALL BE PRUNED TO MAKE THEM LOOK SHAPELY, TYPICAL OF THEIR SPECIES. ALL CUTS OR WOUNDS SHALL BE PAINTED WITH TREE WOUND DRESSING. THE CONTRACTOR SHALL NOTIFY THE OWNER PRIOR TO SUCH WORK SO THAT THE OWNER MAY PERFORM THIS TASK THEMSELVES IF THEY SO DESIRE.

IN SOME AREAS OF THE CONSTRUCTION SITE, VARIOUS PRIVATE RESIDENTIAL AND COMMERCIAL IMPROVEMENTS EXIST, SUCH AS SHRUBS, FLOWER BEDS, ROCK GARDENS, FENCE AND VARIOUS OTHER SIMILAR ITEMS. SPECIAL CARE SHALL BE TAKEN IN THE REMOVAL OF THESE ITEMS SO THAT THEY MAY BE REPLACED IN THEIR ORIGINAL POSITION. THE CONTRACTOR SHALL NOTIFY THE OWNER PRIOR TO SUCH WORK SO THAT THE OWNER MAY REMOVE IT THEMSELVES IF THEY SO DESIRE. PAYMENT FOR ALL OPERATIONS DESCRIBED ABOVE SHALL BE INCLUDED IN THE CONTRACT PRICE FOR THE PERTINENT 603 CONDUIT ITEMS.

**CONSTRUCTION NOISE**  
ACTIVITIES AND LAND USE ADJACENT TO THIS PROJECT MAY BE AFFECTED BY CONSTRUCTION NOISE. IN ORDER TO MINIMIZE ANY ADVERSE CONSTRUCTION NOISE IMPACTS, ANY POWER-OPERATED CONSTRUCTION-TYPE DEVICE SHALL NOT BE OPERATED BETWEEN THE HOURS OF 7:00 P.M. AND 8:00 A.M. IN ADDITION, ANY SUCH DEVICE SHALL NOT BE OPERATED AT ANY TIME IN SUCH A MANNER THAT THE NOISE CREATED SUBSTANTIALLY EXCEEDS THE NOISE CUSTOMARILY AND NECESSARILY ATTENDANT TO THE REASONABLE AND EFFICIENT PERFORMANCE OF SUCH EQUIPMENT.

**SAFETY COORDINATOR**  
THE CONTRACTOR SHALL DESIGNATE ONE RESPONSIBLE INDIVIDUAL FROM HIS FORCES TO BE THE SAFETY COORDINATOR FOR THE PROJECT SITE. THIS INDIVIDUAL SHALL BE RESPONSIBLE FOR THE SAFETY OF THE GENERAL PUBLIC, AS WELL AS THE SUB-CONTRACTORS AND CONTRACTOR'S PERSONNEL AT ALL TIMES DURING CONSTRUCTION. THE CONTRACTOR SHALL SUBMIT THIS INDIVIDUAL'S NAME, ADDRESS, WORK AND HOME PHONE NUMBERS TO THE VILLAGE OF NEW MIDDLETOWN PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SAFETY REQUIREMENTS OF ALL GOVERNING AGENCIES.

PAYMENT FOR THE PERFORMANCE OF THIS WORK SHALL BE INCLUDED IN THE VARIOUS ITEMS OF WORK TO BE PERFORMED IN THIS CONTRACT. NO SEPARATE PAYMENT WILL BE MADE.

**MAINTENANCE OF TRAFFIC**  
TWO WAY TRAFFIC SHALL BE MAINTAINED AT ALL TIMES, EXCEPT THAT ONE WAY TRAFFIC, CONTROLLED BY FLAGGERS, WILL BE PERMITTED FOR MINIMUM PERIODS OF TIME FOR CONSTRUCTION AND EQUIPMENT REQUIREMENTS. ALL TRAFFIC CONTROL DEVICES SHALL BE IN CONFORMANCE WITH ODOT SPECIFICATION ITEM 614 AND THE OHIO MANUAL OF TRAFFIC CONTROL DEVICES, LATEST EDITION.

THE FOLLOWING QUANTITIES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY FOR THE MAINTENANCE OF TRAFFIC:

ITEM 614 MAINTAINING TRAFFIC

LUMP

**DOMINION EAST OHIO GAS**  
THE CONTRACTOR SHALL BE INFORMED THAT DEO = THE EAST OHIO GAS COMPANY, DBA DOMINION EAST OHIO, 1-800-362-7557.

**ITEM 832 - EROSION CONTROL**  
REFER TO SUPPLEMENTAL SPECIFICATIONS 832 FOR FURTHER DETAILS.

THE FOLLOWING ESTIMATED QUANTITY HAS BEEN INCLUDED IN THE GENERAL SUMMARY FOR EROSION CONTROL:

832, EROSION CONTROL 1000 EACH

**ROADWAY QUANTITIES**  
THE FOLLOWING QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY:

ITEM	TOTAL	DESCRIPTION
201	LUMP	CLEARING AND GRUBBING
623	LUMP	CONSTRUCTION LAYOUT STAKES
624	LUMP	MOBILIZATION

**ITEM SPECIAL - MAILBOX SUPPORT**

THIS WORK SHALL CONSIST OF FURNISHING AND ERECTING MAILBOX SUPPORTS AND ANY ASSOCIATED MOUNTING HARDWARE IN ACCORDANCE WITH THE LOCATION & DESIGN MANUAL OF OHIO, VOLUME ONE, ROADWAY DESIGN SECTION 803.1, AND ATTACHING AN OWNER-SUPPLIED MAILBOX AT LOCATIONS SPECIFIED IN THE PLAN, OR OTHERWISE ESTABLISHED BY THE ENGINEER.

WOOD POSTS SHALL BE NOMINAL 4"x4" SQUARE OR 4-1/2" DIAMETER ROUND, AND CONFORM TO 710.14.

STEEL POSTS SHALL BE NOMINAL PIPE SIZE 2" I.D., AND CONFORM TO AASHTO M 181.

HARDWARE (PLATES, SCREWS, BOLTS, ETC.) SHALL BE COMMERCIAL-GRADE GALVANIZED STEEL.

POSTS SHALL BE SET PER THE FIRST PARAGRAPH OF 606.03, AND SHALL IN NO INSTANCE BE ENCASED IN CONCRETE.

SUPPORT HARDWARE SHALL ACCOMMODATE EITHER A SINGLE OR A DOUBLE MAILBOX INSTALLATION, AND NO MORE THAN TWO BOXES MAY BE MOUNTED ON A SINGLE POST.

THE MAILBOX SHALL BE SECURELY AND NEATLY ATTACHED BY THE CONTRACTOR TO THE NEW SUPPORT. THE CONTRACTOR SHALL FURNISH ALL NECESSARY ATTACHMENT HARDWARE (NUTS, BOLTS, PLATES, SPACERS, AND WASHERS) AS NECESSARY TO ACCOMMODATE THE COMPLETE INSTALLATION.

IN THE ABSENCE OF A NEW BOX SUPPLIED BY THE OWNER, THE CONTRACTOR SHALL SALVAGE THE EXISTING BOX AND PLACE IT ON THE NEW SUPPORT. DUE CARE SHALL BE EXERCISED IN SUCH AN OPERATION, AND THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIRING OR REPLACING ANY BOX DAMAGED BY IMPROPER HANDLING ON HIS PART, AS JUDGED AND DIRECTED BY THE ENGINEER.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING WITH THE LOCAL POST MASTER REGARDING THE TIMING OF THE MOVEMENT OF ANY MAILBOX TO A NEW LOCATION.

PAYMENT UNDER THIS ITEM SHALL BE LIMITED TO FINAL PERMANENT INSTALLATIONS. TEMPORARY INSTALLATIONS SHALL BE IN ACCORDANCE WITH 107.12. HOWEVER, THE SAME MATERIAL AND SIZE LIMITATIONS AS FOR PERMANENT INSTALLATIONS SHALL APPLY.

MAILBOX SUPPORTS, COMPLETE IN PLACE, WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER EACH, FOR THE FOLLOWING ITEM:

ITEM SPECIAL - MAILBOX SUPPORT SYSTEM, SINGLE 2 EACH