SHEET NUM. 3	4	5	6	8	9	10	11	15	PART. 01/S>2/ PV	02/S>2/ PV/YOUN	03/S>2/ OT/YOUN	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
																ROADWAY	
						4,971	788		2,602		3,157	202	30000	5,759	SF	WALK REMOVED	
						80	16		44		52	202	32000	96	FT	CURB REMOVED	
17									11		6	203	10000	17	CY	EXCAVATION	
						1,229	98		360		967	608	10000	1,327	SF	4" CONCRETE WALK	
						3,972	691		2,368		2,295	608	52000	4,663	SF	CURB RAMP	
	9								7	2		623	39501	9	EACH	MONUMENT ASSEMBLY ADJUSTED TO GRADE, AS PER PLAN	3
																EROSION CONTROL	
									3,000			832	30000	3,000	EACH	EROSION CONTROL	
																DRAINAGE	
41									22	19		611	98630	41	EACH	CATCH BASIN ADJUSTED TO GRADE	
6									3		3	611	98634	6	EACH	CATCH BASIN RECONSTRUCTED TO GRADE	
						2			1		1	611	99654	2	EACH	MANHOLE ADJUSTED TO GRADE	
	70								47	23		611	99655	70	EACH	MANHOLE ADJUSTED TO GRADE, AS PER PLAN	3
	4								3		1	611	99660	4	EACH	MANHOLE RECONSTRUCTED TO GRADE	
2,350	200								1,400	950	200	SPECIAL	61199820	2,550	LB	MISCELLANEOUS METAL	4
																PAVEMENT	
500									235		165	251	01000	500	SY	PARTIAL DEPTH PAVEMENT REPAIR (441)	
600									402		198	252	01500	600	FT	FULL DEPTH PAVEMENT SAWING	
100									67		33	253	01000	100	SY	PAVEMENT REPAIR	
17									11		6	304	20000	17	CY	AGGREGATE BASE	
				5,644	213				3,468	2,389		407	20000	5,857	GAL	NON-TRACKING TACK COAT @ 0.09 GAL/SY	
				1,742	66				1,071	738		424	14001	1,808	CY	FINE GRADED POLYMER ASPHALT CONCRETE, TYPE B, (448), AS PER PLAN (T = 1")	3
						80	16		44		52	609	26000	96	FT	CURB, TYPE 6	
				62,709	2,359				38,532	26,537		897	01010	65,068	SY	PAVEMENT PLANING, ASPHALT CONCRETE, CLASS A (T = 1")	
																WATER WORK	
						1					1	638	10400	1	EACH	FIRE HYDRANT ADJUSTED TO GRADE	
						2					2	638	10800	2	EACH	VALVE BOX ADJUSTED TO GRADE	
	22								15	7		638	10801	22	EACH	VALVE BOX ADJUSTED TO GRADE, AS PER PLAN	3
																TRAFFIC CONTROL	
								0.31		0.32		646	10010	0.31	MILE	EDGE LINE, 6"	
								4.64	2.78	1.86		646	10110	4.64	MILE	LANE LINE, 6"	
								2.32	1.39	0.93		646	10200	2.32	MILE	CENTER LINE	
								948	848	100		646	10310	948	FT	CHANNELIZING LINE, 12"	
								525	295	230		646	10400	525	FT	STOP LINE	
								513	277	236		646	10510	513	FT	CROSSWALK LINE, 12"	
								857	625	232		646	10520	857	FT	CROSSWALK LINE, 24"	
								179	150	29		646	10600	179	FT	TRANSVERSE/DIAGONAL LINE	
								91	91			646	10800	91	SF	ISLAND MARKING	
								4		4		646	20000	4	EACH	RAILROAD SYMBOL MARKING	
								18	18			646	20300	18	EACH	LANE ARROW	
																TRAFFIC SIGNALS	
			8							8		632	27005	8	EACH	LOOP DETECTOR UNIT, AS PER PLAN	6
																MAINTENANCE OF TRAFFIC	
		200							134	66		614	11110	200	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
		40							27	13		614	12460	40	EACH	WORK ZONE MARKING SIGN	
		20							13	7		614	13000	20	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	
			6						4	2		614	18601	6	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	5
		3.55							2.17	1.38		614	20100	3.55	MILE	WORK ZONE LANE LINE, CLASS I, 4", 642 PAINT	
		3.55							2.17	1.38		614	20550	3.55	MILE	WORK ZONE LANE LINE, CLASS III, 4", 642 PAINT	
		4.33							2.95	1.38		614	21100	4.33	MILE	WORK ZONE CENTER LINE, CLASS I, 642 PAINT	
		4.33							2.95	1.38		614	21550	4.33	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
		847							708	139		614	23200	847	FT	WORK ZONE CHANNELIZING LINE, CLASS I, 8", 642 PAINT	
		847							708	139		614	23680	847	FT	WORK ZONE CHANNELIZING LINE, CLASS III, 8", 642 PAINT	
		521							338	183		614	26200	521	FT	WORK ZONE STOP LINE, CLASS I, 642 PAINT	
		521							338	183		614	26610	521	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
																INCIDENTALS	
									LS			614	11000	LS		MAINTAINING TRAFFIC	
									6			619	16010	6	MNTH	FIELD OFFICE, TYPE B	
									LS			623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
									LS			624	10000	LS		MOBILIZATION	

updated plan split

updated plan split

updated plan split

GENERAL SUMMARY

DESIGN AGENCY

DESIGNER ROF

REVIEWER MJA 04-01-22

PROJECT ID 110681

SHEET P-7 TOTAL 15

MAH-170-13.19

MODEL: Sheet PAPERSIZE: 17x11 (in.) DATE: 8/18/2022 TIME: 1:41:57 PM USER: rfreno
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 04\Mahoning\110681\400-Engineering\Roadway\Sheets\110681_GG001.dgn