SHEET NUM.													PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
OFFICE CALCS	P.13	P.14	P.15	P.81	P.82	P.84	P.85	P.86	P.147	P.162	P.168		01/SAE		EXT	TOTAL			
																		DRAINAGE CONT.	
						24							24	611	10400	24	FT	24" CONDUIT, TYPE B	
						45							45	611	10600	45	FT	24" CONDUIT, TYPE C	
						259							259	611	16400	259	FT	36" CONDUIT, TYPE B	
						16							16	611	16400	16	FT	36" CONDUIT, TYPE B, 706.02	
						5							5	611	98150	5	EACH	CATCH BASIN, NO. 3	
						1							1	611	98151	1	EACH	CATCH BASIN, NO. 3, AS PER PLAN	P.14
						6							6	611	98180	6	EACH	CATCH BASIN, NO. 3A	
						6							6	611	98181	6	EACH	CATCH BASIN, NO. 3A, AS PER PLAN	P.14
						2							2	611	98470	2	EACH	CATCH BASIN, NO. 2-2B	
						2							2	611	98630	2	EACH	CATCH BASIN ADJUSTED TO GRADE	
						7							7	611	99574	7	EACH	MANHOLE, NO. 3	
							1						1	611	99654	1	EACH	MANHOLE ADJUSTED TO GRADE	
								3					3	611	99710	3	EACH	PRECAST REINFORCED CONCRETE OUTLET	
		400											400	SPECIAL	61199820	400	LB	MISCELLANEOUS METAL	P.14
																		PAVEMENT	
2,544													2,544	252	01500	2,544	FT	FULL DEPTH PAVEMENT SAWING	
1,797													1,797	301	56000	1,797	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
2,077				268									2,345	304	20000	2,345	CY	AGGREGATE BASE	
2,378			677										3,055	407	20000	3,055	GAL	NON-TRACKING TACK COAT	
101													101	408	10000	101	GAL	PRIME COAT	
194			294										488	424	14000	488	CY	FINE GRADED POLYMER ASPHALT CONCRETE, TYPE B, (448)	
4													4	441	70500	4	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), (DRIVEWAYS)	
3													3	441	70700	3	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (449), (DRIVEWAYS)	
388													388	442	10000	388	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446), PG76-22M	
388													388	442	10080	388	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, 12.5 MM, TYPE A (446), PG76-22M	
				1,158									1,158	452	09011	1,158	SY	4" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P, AS PER PLAN	P.15
338													338	452	10010	338	SY	6" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P	
1,361													1,361	452	12010	1,361	SY	8" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P	
				833									833	452	13011	833	SY	9" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P, AS PER PLAN	P.15
				1,404	2,240								3,644	609	12000	3,644	FT	COMBINATION CURB AND GUTTER, TYPE 2	
				3,386	591								3,977	609	26000	3,977	FT	CURB, TYPE 6	
				819									819	609	31001	819	FT	COMBINATION CURB AND GUTTER, TYPE 9, AS PER PLAN	P.12
56													56	617	10101	56	CY	COMPACTED AGGREGATE, AS PER PLAN	P.12
	472												472	SPECIAL	69012060	472	SY	PAVEMENT OVERLAY FABRIC COMPOSITE	P.13
5,559			8,455										14,014	897	01010	14,014	SY	PAVEMENT PLANING, ASPHALT CONCRETE, CLASS A, 1.25"	
																		WATER WORK	
			1										1	638	10800	1	EACH	VALVE BOX ADJUSTED TO GRADE	
																		LIGHTING	
											16		16	625	00450	16	EACH	CONNECTION, FUSED PULL APART	
											8		8	625	00460	8	EACH	CONNECTION, UNFUSED PULL APART	
											9		9	625	00480	9	EACH	CONNECTION, UNFUSED PERMANENT	
											8		8	625	10490	8	EACH	LIGHT POLE, CONVENTIONAL, AT18B40	
											8		8	625	14200	8	EACH	LIGHT POLE FOUNDATION, 24" X 10' DEEP	
											681		681	625	23200	681	FT	NO. 4 AWG 2400 VOLT DISTRIBUTION CABLE	
											947		947	625	24320	947	FT	1-1/2" DUCT CABLE WITH THREE NO. 4 AWG 2400 VOLT CABLES	
											197		197	625	25500	197	FT	CONDUIT, 3", 725.04	
											8		8	625	26253	8	EACH	LUMINAIRE, CONVENTIONAL, SOLID STATE (LED), AS PER PLAN, 240V, 3000K CCT, 10064-10230LM	P.167
											1,034		1,034	625	29002	1,034	FT	TRENCH, 24" DEEP	
											6		6	625	30700	6	EACH	PULL BOX, 725.08, 18"	
									2		9		11	625	32000	11	EACH	GROUND ROD	
											1		1	625	34001	1	EACH	POWER SERVICE, AS PER PLAN	P.167
											1,034		1,034	625	36011	1,034	FT	UNDERGROUND WARNING/MARKING TAPE, AS PER PLAN	P.167
											1		1	625	76000	1	EACH	ARC FLASH CALCULATIONS AND LABEL, CONTROL CENTER	P.167

GENERAL SUMMARY

MAH-46-13.55

MODEL: Sheet_SurvFt PAPERSIZE: 34x22 (in.) DATE: 10/15/2026 TIME: 3:20:25 PM USER: SFink
pw:\\jmt-pw.bentley.com:jmt-pw-01\Documents\Projects\2023\23-02825-001\120083\400-Engineering\Roadway\Sheets\120083_GG002.dgn

DESIGN AGENCY
JMT
4215 Worth Ave Suite K-230
Columbus, OH 43219

DESIGNER SLF

REVIEWER BD 06/12/26

PROJECT ID 120083

SHEET P.78 TOTAL 182