

J:\ODOT\102738_MED-3-12-00\Design\Roadway\Sheet\102738_GG00.dgn Sheet 10/9/2019 11:48:54 AM davi d-m

SHEET NUM.										PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
3	10	18	32	53	OFFICE CALCS.	01/S/2/BR	ITEM	EXT	TOTAL							
ROADWAY																
LS							LS	201	11000	LUMP					CLEARING AND GRUBBING	3
		22					22	202	23000						PAVEMENT REMOVED	
							180	202	23500	180	SY				WEARING COURSE REMOVED	
							180	202	23900	180	SY				CONCRETE BASE REMOVED	
	600						600	202	30000	600	SF				WALK REMOVED	
	172		288				460	202	35100	460	FT				PIPE REMOVED, 24" AND UNDER	
	3						3	202	58100	3	EACH				CATCH BASIN REMOVED	
	80						80	202	75000	80	FT				FENCE REMOVED	
			4				4	202	75610	4	EACH				VALVE BOX REMOVED	
							122	203	10000	122	CY				EXCAVATION	
							24	203	20000	24	CY				EMBANKMENT	
							246	268	204	10000	268	SY			SUBGRADE COMPACTION	
1							1	204	45000	1	HOUR				PROOF ROLLING	
	40						40	607	98000	40	FT				FENCE, MISC.:WOOD FENCE	3
	750						750	608	12000	750	SF				5" CONCRETE WALK	
							2	623	38500	2	EACH				MONUMENT ASSEMBLY	
							1	SPECIAL	69050100	1	EACH				MAILBOX SUPPORT SYSTEM, SINGLE	4
EROSTON CONTROL																
	2						2	659	00100	2	EACH				SOIL ANALYSIS TEST	
	50						50	659	00300	50	CY				TOPSOIL	
	448						448	659	00500	448	SY				SEEDING AND MULCHING, CLASS 1	
	22						22	659	14000	22	SY				REPAIR SEEDING AND MULCHING	
	22						22	659	15000	22	SY				INTER-SEEDING	
	0.06						0.06	659	20000	0.06	TON				COMMERCIAL FERTILIZER	
	0.09						0.09	659	31000	0.09	ACRE				LIME	
	2						2	659	35000	2	MGAL				WATER	
							16,327	16,327	832	30000	16,327	EACH			EROSION CONTROL	
DRAINAGE																
	16						16	611	02000	16	FT				8" CONDUIT, TYPE C	
	4						4	611	06100	4	FT				15" CONDUIT, TYPE C	
	41						41	611	07400	41	FT				18" CONDUIT, TYPE B	
	14						14	611	07600	14	FT				18" CONDUIT, TYPE C	
	125						125	611	10600	125	FT				24" CONDUIT, TYPE C	
	1						1	611	98470	1	EACH				CATCH BASIN, NO. 2-2B	
	2						2	611	98510	2	EACH				CATCH BASIN, NO. 2-3	
	2						2	611	99574	2	EACH				MANHOLE, NO. 3	
LS							LS	611	97300	LS					CONDUIT, MISC.: SUPPORT OF SANITARY SEWER	3
PAVEMENT																
							219	219	254	01000	219	SY			PAVEMENT PLANING, ASPHALT CONCRETE, 1 1/2" AVG.	
							50	50	301	46000	50	CY			ASPHALT CONCRETE BASE, PG64-22	
							39	39	304	20000	39	CY			AGGREGATE BASE	
							47	47	407	10000	47	GAL			TACK COAT	
							28	28	441	50000	28	CY			ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
							22	452	10010	22	SY				6" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC1	

CALCULATED DAM CHECKED DPF
GENERAL SUMMARY
MED - SR 3 - 12.00
 8
 57