

STATION RANGE			TYPICAL SECTION	SIDE	DISTANCE (D) FT	AVERAGE WIDTH (W) FT	SURFACE AREA (A) A = DxW/9 SY	CADD GENERATED AREA SY	202	202	204	254	301	304	407	411	441	441			
									PAVEMENT REMOVED SY	PAVEMENT REMOVED, ASPHALT SY	SUBGRADE COMPACTION SY	PAVEMENT PLANING, ASPHALT CONCRETE SY	ASPHALT CONCRETE BASE, PG64-22 CY	AGGREGATE BASE CY	TACK COAT (0.06 GAL./S.Y.) GAL	STABILIZED CRUSHED AGGREGATE CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22 CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448)PG64-22 CY			
SR 3																					
1284+45.00	TO	1284+70.00			25.00	25.30	70.28				70.28				4.22			2.44			
1284+70.00	TO	1285+30.00			60.00	2.60	17.33									3.85					
1284+70.00	TO	1285+30.00			60.00	25.30	168.67	168.67							20.24			5.86	8.20		
1284+70.00	TO	1285+30.00			60.00	26.47	176.44					34.31			10.59						
1284+70.00	TO	1285+30.00			60.00	27.97	186.44						31.07								
1284+70.00	TO	1285+30.00			60.00	28.30	188.67			188.67											
1285+30.00	TO	1285+55.00			25.00	25.30	70.28				70.28				4.22			2.44			
SR 94																					
1061+00.00	TO	1061+25.00			25.00	24.70	68.61				68.61				4.12			2.38			
1061+25.00	TO	1061+75.00			50.00	2.00	11.11									2.47					
1061+25.00	TO	1061+75.00			50.00	24.70	137.22		137.22						16.47			4.76	6.67		
1061+25.00	TO	1061+75.00			50.00	25.87	143.70					27.94			8.62						
1061+25.00	TO	1061+75.00			50.00	27.37	152.04						25.34								
1061+25.00	TO	1061+75.00			50.00	27.70	153.89			153.89											
1061+75.00	TO	1062+00.00			25.00	24.70	68.61				68.61				4.12			2.38			
SUBTOTALS								168.67	137.22	342.56	277.78	62.25	56.41	72.58	6.32	20.27	14.87				
TOTALS CARRIED TO GENERAL SUMMARY								169	138	343	278	63	57	73	7	21	15				