SHEET NUM. 01/SAF/PV														PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
9	10	12	16	17	18	56	57	61	62	67	68	73	74	01/SAF/PV	02/SAF/OT						
																				1 ABANDONED HEADWALLS AND PIPE TO BE REMOVED	
																				ROADWAY	
														LS		201	11000	LS		CLEARING AND GRUBBING	
2														2		202	20011	2	EACH	HEADWALL REMOVED, AS PER PLAN 1	9
					4,420									4,420		202	23000	4,420	SY	PAVEMENT REMOVED	
			242											175	67	202	35100	242	FT	PIPE REMOVED, 24" AND UNDER	
40														40		202	35101	40	FT	PIPE REMOVED, 24" AND UNDER, AS PER PLAN 1	9
						60								60		202	35200	60	FT	PIPE REMOVED, OVER 24"	
			250											250		202	38000	250	FT	GUARDRAIL REMOVED	
			2											2		202	58100	2	EACH	CATCH BASIN REMOVED	
			2												2	202	75610	2	EACH	VALVE BOX REMOVED	
	3,687													3,687		203	10000	3,687	CY	EXCAVATION	
1,000	4,095													5,095		203	20000	5,095	CY	EMBANKMENT	
1,500														1,500		204	10000	1,500	SY	SUBGRADE COMPACTION	
1,000														1,000		204	13000	1,000	CY	EXCAVATION OF SUBGRADE	
4														4		204	45000	4	HOUR	PROOF ROLLING	
	545													545		204	50000	545	SY	GEOTEXTILE FABRIC	
					6,119									6,119		206	11000	6,119	SY	CURING COAT	
					6,119									6,119		206	15020	6,119	SY	CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP	
													3	3		623	38500	3	EACH	MONUMENT ASSEMBLY	
													1	1		623	40500	1	EACH	REFERENCE MONUMENT	
												1	2	3		623	40520	3	EACH	RIGHT-OF-WAY MONUMENT	
	3													3		SPECIAL	69050100	3	EACH	MAILBOX SUPPORT SYSTEM, SINGLE	10
																				EROSION CONTROL	
							3							3		601	11000	3	SY	RIPRAP, TYPE D	
			63											63		601	21060	63	SY	TIED CONCRETE BLOCK MAT, TYPE 2	
						18								18		601	32100	18	CY	ROCK CHANNEL PROTECTION, TYPE B WITH FILTER	
			2				3							5		601	32200	5	CY	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER	
2														2		659	00100	2	EACH	SOIL ANALYSIS TEST	
872														872		659	00300	872	CY	TOPSOIL	
	7,841													7,841		659	00500	7,841	SY	SEEDING AND MULCHING, CLASS 1	
7,841														7,841		659	15000	7,841	SY	INTER-SEEDING	
0.71														0.71		659	20000	0.71	TON	COMMERCIAL FERTILIZER	
8.1														8.1		659	31000	8.1	ACRE	LIME	
																				2 ADDED ITEM 832	
43														43		659	35000	43	MGAL	WATER	
			856											856		670	00710	856	SY	DITCH EROSION PROTECTION MAT, TYPE A	
														LS		832	15000	LS		STORM WATER POLLUTION PREVENTION PLAN 2	
														LS		832	15002	LS		STORM WATER POLLUTION PREVENTION INSPECTIONS 2	
														LS		832	15010	LS		STORM WATER POLLUTION PREVENTION INSPECTION SOFTWARE 2	
			445											445		836	10000	445	SY	SEEDING AND EROSION CONTROL WITH TURF REINFORCING MAT, TYPE 1	
																				DRAINAGE	
				0.51		17.2	0.98							18.69		602	20000	18.69	CY	CONCRETE MASONRY	
				123										123		605	05200	123	FT	4" UNCLASSIFIED PIPE UNDERDRAINS	
				2,172										2,172		605	06000	2,172	FT	4" BASE PIPE UNDERDRAINS	
				236										236		611	00406	236	FT	4" CONDUIT, TYPE F	
										105				105		611	00407	105	FT	4" CONDUIT, TYPE F, AS PER PLAN	67
	100													100		611	01500	100	FT	6" CONDUIT, TYPE F	
				199										199		611	04400	199	FT	12" CONDUIT, TYPE B	
				365										365		611	04600	365	FT	12" CONDUIT, TYPE C	
				69										69		611	07400	69	FT	18" CONDUIT, TYPE B	
YD7				162										162		611	07600	162	FT	18" CONDUIT, TYPE C	
						147								147		611	20700	147	FT	48" CONDUIT, TYPE A, 706.02 OR 707.33, 60" 707.04 (0.109) GALVANIZED	
							60							60		611	52700	60	FT	29" X 45" CONDUIT, TYPE A, 706.04	
				3										3		611	98150	3	EACH	CATCH BASIN, NO. 3	
				3										3		611	98180	3	EACH	CATCH BASIN, NO. 3A	
				2										2		611	98470	2	EACH	CATCH BASIN, NO. 2-2B	
				4										4		611	99574	4	EACH	MANHOLE, NO. 3	
				1										1		611	99710	1	EACH	PRECAST REINFORCED CONCRETE OUTLET	

CALCULATED MJB CHECKED BKM

GENERAL SUMMARY

MED-3-09.04

1.4
8.0

P:\Columbus-OH\Projects_Infrastructure\T0H0DT18.PE01 - MED-3-9.05\107070_MED-3-9.05\Design\Roadway\Sheets\107070_GG001.dgn Sheet 3/26/2021 9:27:06 AM MBurger