



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000	
Section				Sheet no./rev.			
Structure Estimated Quantities – Final Tracings				1			
Calc. by	Date	Chk'd by	Date	App'd by	Date		
EIW	Rev. 10/30/19	PJW	9/16/19	SMK	11/7/19		

Item 202 – Approach Slab Removed

Existing Approach slab width (ft);

$$W_{ex_app} = 20$$

Existing approach slab length (ft);

$$L_{ex_app} = 15$$

Total Area of 202 (SY);

$$T_{ex_app} = \text{ceiling}(2 \times W_{ex_app} \times L_{ex_app} / 9, 1) = 67.000$$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project				Job Ref.	
MED-252-03.95 PID 88883				J20180414.000	
Section				Sheet no./rev.	
Structure Estimated Quantities – Final Tracings				2	
Calc. by	Date	Chk'd by	Date	App'd by	Date
EIW	Rev. 10/30/19	PJW	9/16/19	SMK	11/7/19

Item 202 – Wearing Surface Removed

*See calculation for Item 202 – Approach Slab Removed

*Included with Roadway Quantities on General Summary sheet.

Total Area of 202 (SY);

$T_{ex_ws} = T_{ex_app} = 67.000$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project MED-252-03.95 PID 88883				Job Ref. J20180414.000	
Section Structure Estimated Quantities – Final Tracings				Sheet no./rev. 3	
Calc. by EIW	Date Rev. 10/30/19	Chk'd by PJW	Date 9/16/19	App'd by SMK	Date 11/7/19

Item 503 – Unclassified Excavation

*Unclassified excavation includes areas required for construction of new abutments.

Offset for new porous backfill (ft);	WPB = 2
Proposed abutment footing width (ft);	W _{ftg} = 4.5
Proposed abutment stem width (ft);	W _{stem} = 3
Excavation limit behind abutment footing (ft);	e _b = WPB – (W _{ftg} - W _{stem}) / 2 = 1.250
Excavation limit in front of proposed abutment to back of existing abutment (Ft);	e _r = 7.3
Removal limit of existing RA (ft);	EL _{rem_RA} = 817.68
Removal limit of existing FA (ft);	EL _{rem_FA} = 817.00
Proposed B/Ftg RA (ft);	EL _{ftg_RA} = 818.43
Proposed B/Ftg FA (ft);	EL _{ftg_FA} = 817.80
Proposed abut height – RA (ft);	h _{avg_RA} = 828.57 - EL _{ftg_RA} = 10.140
Proposed abut height – FA (ft);	h _{avg_FA} = 827.94 – EL _{ftg_FA} = 10.140
Abutment length (ft);	L _{abut} = 39
Wingwall length (ft);	L _{WW} = 12.57

Area of 503 at rear abutment (sq ft); $A_{503_RA} = (W_{ftg} + 1 + e_b) \times (h_{avg_RA}) + 0.5 \times (e_r - 1) \times \text{abs}(EL_{rem_RA} - EL_{ftg_RA}) + (e_r - 1) \times (828.57 - \max(EL_{ftg_RA}, EL_{rem_RA})) = \mathbf{134.690}$

Area of 503 at forward abutment (sq ft); $A_{503_FA} = (W_{ftg} + 1 + e_b) \times (h_{avg_FA}) + 0.5 \times (e_r - 1) \times \text{abs}(EL_{rem_FA} - EL_{ftg_FA}) + (e_r - 1) \times (827.94 - \max(EL_{ftg_FA}, EL_{rem_FA})) = \mathbf{134.847}$

TOTAL VOLUME (CY); $T_{503} = \text{ceiling}((A_{503_RA} + A_{503_FA}) \times (L_{abut} + 2 \times L_{WW}) / 27,1) = \mathbf{641.000}$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000					
Section				Structure Estimated Quantities – Final Tracings				Sheet no./rev.		4	
Calc. by	Date	Chk'd by	Date	App'd by	Date						
EIW	Rev. 10/30/19	PJW	9/16/19	SMK	11/7/19						

Item 509 – Epoxy Coated Reinforcing Steel, As Per Plan

Abutments

Abutment & wingwall rebar (lb); $T_{509_abut} = 7184$

Piers

Pier rebar (lb) (lb); $T_{509_pier} = 11951$

Superstructure

Deck & diaphragm (lb); $T_{509_super} = 62634$

Parapet

Parapet rebar (lb); $T_{509_par} = 11618$

TOTAL WEIGHT OF REINFORCING STEEL (LB); $T_{509} = T_{509_abut} + T_{509_pier} + T_{509_super} + T_{509_par} = 93387.000$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000					
Section				Structure Estimated Quantities – Final Tracings				Sheet no./rev.		5	
Calc. by	Date	Chk'd by	Date	App'd by	Date						
EIW	Rev. 10/30/19	PJW	9/16/19	SMK	11/7/19						

ITEM 511 – SEMI-INTEGRAL DIAPHRAGM GUIDE

* 1 per abutment

TOTAL NUMBER OF DIAPHRAGM GUIDES (EACH);

T_{511guide} = 2



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project MED-252-03.95 PID 88883				Job Ref. J20180414.000	
Section Structure Estimated Quantities – Final Tracings				Sheet no./rev. 6	
Calc. by EIW	Date Rev. 10/30/19	Chk'd by PJW	Date 9/16/19	App'd by SMK	Date 11/7/19

ITEM 511 – CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK

**Includes Bridge deck, haunch, additional cantilever thickness, and semi-integral diaphragm concrete.*


Primary Deck

Proposed deck width (ft); $W_{deck} = 35.330$
 Proposed bridge limits (ft); $L_{deck} = 197.210$
 Proposed deck thickness (in); $t_{deck} = 8.75$

Volume of primary deck (cu ft); $V_{deck} = (W_{deck} \times L_{deck} \times t_{deck} / 12) = 5080.417$

Haunches

Average haunch (all beams) (in); $h_{avg} = 2.08$



Top flange width W36X210 (ft); $b_f = 12.2/12 = 1.017$
 Average flange thickness (weighted over length for W36x210 & W36x150 beams) (in);
 $t_f = ((1.36 \times 168) + (0.94 \times 27)) / (168+27) = 1.302$
 Fascia overhang (ft); $L_{fascia} = 3.416667$
 Number of interior beams (each); $N_{int} = 2$
 Number of fascia beams (each); $N_{ext} = 2$

Haunch volume – interior beams (cu ft); $V_{haunch_int} = b_f \times (h_{avg}/12) \times L_{deck} \times N_{int} = 69.506$
 Haunch volume – fascia beams (cu ft); $V_{haunch_ext} = (b_f \times (h_{avg}/12) + (L_{fascia} - (b_f / 2)) \times ((h_{avg} + t_f)/12)) \times L_{deck} \times N_{ext} = 392.783$

Abutment Diaphragms

Proposed abutment stem width (ft); $W_{stem} = 3.000$
 Abutment length (ft); $L_{abut} = 39.000$
 W36x210 beam CS Area (sq ft / ft); $A_{36x210} = 61.8/144 = 0.429$
 W36x210 beam height (ft); $h_{36x210} = 36.7/12 = 3.058$
 Beam length into diaphragm (ft); $L_{diaph_sti} = 2$
 Proposed approach slab thickness (ft); $t_{app} = 13/12 = 1.083$
 Diaphragm height (ft); $h_{diaph} = (t_{deck} + h_{avg})/12 + h_{36x210} + 9/12 = 4.711$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000					
Section				Structure Estimated Quantities – Final Tracings				Sheet no./rev.		7	
Calc. by	Date	Chk'd by	Date	App'd by	Date						
EIW	Rev. 10/30/19	PJW	9/16/19	SMK	11/7/19						

Diaphragm Volume (not including deck concrete) (cu ft); $V_{diaph} = 2 \times (w_{stem} \times (h_{diaph} - (t_{deck} + h_{avg})/12) \times L_{abut} - 2 \times A_{36x210} \times L_{diaph_stl} \times (N_{int} + N_{ext})) = 877.417$

TOTAL VOLUME OF CONCRETE (CU YD); $T_{511deck} = \text{ceiling}((V_{deck} + V_{haunch_int} + V_{haunch_ext} + V_{diaph})/ 27, 5) = 240.000$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000					
Section				Structure Estimated Quantities – Final Tracings				Sheet no./rev.		8	
Calc. by	Date	Chk'd by	Date	App'd by	Date						
EIW	Rev. 10/30/19	PJW	9/16/19	SMK	11/7/19						

ITEM 511 – CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK (PARAPET)

Proposed length (ft);

$$L_{\text{barrier}} = 229.09$$

Proposed barrier with typical section (ft);

$$L_{\text{barrier_typ}} = L_{\text{barrier}} - 2 \times 14 = 201.090$$

Parapet height (ft);

$$h_{\text{bar}} = 3.5$$

Parapet width (ft);

$$W_{\text{bar}} = 1.5$$

Parapet level width (ft);

$$W_{\text{bar_level}} = 10/12 = 0.833$$

Typical parapet section area (sq ft);

$$A_{\text{par}} = (0.5 \times (W_{\text{bar}} - W_{\text{bar_level}}) + W_{\text{bar_level}}) \times h_{\text{bar}} = 4.083$$

SBR-1-13 transition volume (cu yd);

$$V_{\text{bar_trans}} = 1.82$$

TOTAL VOLUME OF CONCRETE (CU YD);

$$T_{511\text{par}} = \text{ceiling}((A_{\text{par}} \times 2 \times L_{\text{barrier_typ}}) / 27 + 4 \times V_{\text{bar_trans}}, 5) = 70.000$$


40



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000	
Section				Structure Estimated Quantities – Final Tracings			
Sheet no./rev.				9			
Calc. by	Date	Chk'd by	Date	App'd by	Date		
EIW	Rev. 10/30/19	PJW	9/16/19	SMK	11/7/19		

ITEM 511 – CLASS QC1 CONCRETE WITH QC/QA, PIERS ABOVE FOOTING



Piers

Pier cap length (ft); $L_{cap} = 35.88$
 Pier cap width (ft); $w_{cap} = 3$
 Pier cap average height (ft); $h_{cap} = 3.58$

Number of columns per pier; $N_{col} = 3$
 Pier column diameter (ft); $d_{col} = 3$
 Pier 1 column height (ft); $h_{col1} = 11.05$
 Pier 2 column height (ft); $h_{col2} = 10.79$

Volume Pier 1 (cu ft); $V_{P1} = ((L_{cap} - d_{col}) + \pi() \times d_{col}^2 / 4) \times w_{cap} \times h_{cap} + N_{col} \times h_{col1} \times \pi() \times d_{col}^2 / 4 = 663.371$

Volume Pier 2 (cu ft); $V_{P2} = ((L_{cap} - d_{col}) + \pi() \times d_{col}^2 / 4) \times w_{cap} \times h_{cap} + N_{col} \times h_{col2} \times \pi() \times d_{col}^2 / 4 = 657.858$

Total Vol of concrete for Piers (CY); $T_{511pier} = \text{ceiling}((V_{P1} + V_{P2}) / 27, 5) = 50.000$




Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project MED-252-03.95 PID 88883				Job Ref. J20180414.000	
Section Structure Estimated Quantities – Final Tracings				Sheet no./rev. 10	
Calc. by EIW	Date Rev. 10/30/19	Chk'd by PJW	Date 9/16/19	App'd by SMK	Date 11/7/19

ITEM 511 – CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT INCLUDING FOOTING

*Includes footing and stem concrete. Semi-integral diaphragm concrete is included with Bridge Deck Concrete Item.



Abutment length (ft); $L_{abut} = 39.000$
 Proposed abutment footing width (ft); $W_{ftg} = 4.500$
 Proposed abutment stem width (ft); $W_{stem} = 3.000$
 Height of footing (ft); $h_{ftg} = 3$

Rear Abutment

Abut stem height – RA (ft); $h_{RA_stem} = 823.61 - 818.43 - 3 = 2.180$
 Volume RA (cu ft); $V_{RA} = L_{abut} \times (h_{RA_stem} \times W_{stem} + W_{ftg} \times h_{ftg}) = 781.560$

Forward Abutment

Abut stem height – FA (ft); $h_{FA_stem} = 822.98 - 817.80 - 3 = 2.180$
 Volume FA (cu ft); $V_{FA} = L_{abut} \times (h_{FA_stem} \times W_{stem} + W_{ftg} \times h_{ftg}) = 781.560$

Wingwalls

Wingwall stem width (ft); $w_{ww} = 2.5$
 NW & SE wingwall average level length (ft); $L_{WW_1avg} = 3$
 NE & SW wingwall average level length (ft); $L_{WW_2avg} = 2.79$
 NW wingwall average ht (ft); $H_{WW_NW} = (827.67 + 823.55) / 2 - 820.80 = 4.810$
 NE wingwall average ht (ft); $H_{WW_NE} = (827.72 + 824.38) / 2 - 820.80 = 5.250$
 SW wingwall average ht (ft); $H_{WW_SW} = (828.30 + 823.93) / 2 - 821.43 = 4.685$
 SE wingwall average ht (ft); $H_{WW_SE} = (828.35 + 824.22) / 2 - 821.43 = 4.855$

Vol for NW wingwall (cu ft); $V_{NW} = ((w_{ww} \times H_{WW_NW}) \times 9.35 + L_{WW_1avg} \times (827.67 - 820.80)) + (W_{ftg} \times h_{ftg})$
 $\times (L_{WW_1avg} + 10) = 308.544$
 Vol for NE wingwall (cu ft); $V_{NE} = ((w_{ww} \times H_{WW_NE}) \times 10 + L_{WW_2avg} \times (827.72 - 820.80)) + (w_{ftg} \times h_{ftg}) \times$
 $(L_{WW_2avg} + 10) = 323.222$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000					
Section				Structure Estimated Quantities – Final Tracings				Sheet no./rev.		11	
Calc. by		Date		Chk'd by		Date		App'd by		Date	
EIW		Rev. 10/30/19		PJW		9/16/19		SMK		11/7/19	

Vol for SW wingwall (cu ft);
(L_{WW_2avg} + 10)) = **308.957**

$$V_{SW} = ((w_{ww} \times H_{ww_sw}) \times 10 + L_{ww_2avg} \times (828.30 - 821.43) + (w_{ftg} \times h_{ftg}) \times$$

Vol for SE wingwall (cu ft);
(L_{WW_1avg} + 10)) = **309.746**

$$V_{SE} = ((w_{ww} \times H_{ww_se}) \times 9.35 + L_{ww_1avg} \times (828.35 - 821.43) + (w_{ftg} \times h_{ftg}) \times$$

Total Vol of concrete for abutments (CY);

$$T_{511sub} = \text{ceiling}((V_{RA} + V_{FA} + V_{NW} + V_{NE} + V_{SW} + V_{SE}) / 27, 5) = \mathbf{105.000}$$




Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project MED-252-03.95 PID 88883				Job Ref. J20180414.000	
Section Structure Estimated Quantities – Final Tracings				Sheet no./rev. 12	
Calc. by EIW	Date Rev. 10/30/19	Chk'd by PJW	Date 9/16/19	App'd by SMK	Date 11/7/19

ITEM 512 – SEALING CONCRETE SURFACES (EPOXY-URETHANE)


Abutments



ABUTMENT SEALING LIMITS
(FOR SEMI-INTEGRAL ABUTMENT STEEL BEAM BRIDGE)

- Diaphragm height (ft); $h_{diaph} = 4.711$
- Bearing height (ft); $h_{brg} = 2.356 / 12 = 0.196$
- Proposed approach slab thickness (ft); $t_{app} = 1.083$
- Beam seat-to-ground clearance (ft); $h_{clr} = 0.5$
- Abutment sealed height (ft); $H_{512_A} = h_{diaph} - t_{app} + h_{brg} + h_{clr} = 4.324$
- Abutment length (ft); $L_{abut} = 39.000$
- Total abutment area (sq ft); $A_{512_abut} = 2 \times H_{512_A} \times L_{abut} = 337.259$

Wingwalls



ITS
WINGWALL SEALING LIMITS
(STRAIGHT WING ABUTMENT)

*Wingwall sealing areas measured in CAD. Generally equation is as follows:



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114


Project MED-252-03.95 PID 88883				Job Ref. J20180414.000	
Section Structure Estimated Quantities – Final Tracings				Sheet no./rev. 13	
Calc. by EIW	Date Rev. 10/30/19	Chk'd by P JW	Date 9/16/19	App'd by SMK	Date 11/7/19

Area = River side face + Embankment side face + Top area + End Area

SW Wingwall elevation area (CAD) (sq ft); $A_{512_SW} = 46.2 + 10.29 + (13.76 \times 2.5) + (1.12 \times 2.5) = \mathbf{93.690}$
 SE Wingwall elevation area (CAD) (sq ft); $A_{512_SE} = 48.3 + 5.25 + (13.23 \times 2.5) + (1.29 \times 2.5) = \mathbf{89.850}$
 NW Wingwall elevation area (CAD) (sq ft); $A_{512_NW} = 47.58 + 5.80 + (13.23 \times 2.5) + (1.25 \times 2.5) = \mathbf{89.580}$
 NE Wingwall elevation area (CAD) (sq ft); $A_{512_NE} = 51.9 + 5.7 + (13.4 \times 2.5) + (2.6 \times 2.5) = \mathbf{97.600}$

Total wingwall area (sq ft); $A_{512_ww} = A_{512_SW} + A_{512_SE} + A_{512_NW} + A_{512_NE} = \mathbf{370.720}$

Deck and Parapet (on bridge deck)



CONCRETE DECK WITH DEFLECTOR PARAPET

**** ODOT D3 preference is to seal to the edge of the beam flange ****

Parapet height (ft); $h_{bar} = 3.5$
 Parapet width (ft); $w_{bar} = 1.5$
 Parapet level width (ft); $w_{bar_level} = 10/12 = \mathbf{0.833}$

Proposed bridge limits (ft); $L_{deck} = \mathbf{197.210}$
 Parapet perimeter (ft); $perim_{bar} = h_{bar} + w_{bar_level} + \sqrt{(w_{bar} - w_{bar_level})^2 + h_{bar}^2} = \mathbf{7.896}$
 Average haunch (all beams) (in); $h_{avg} = \mathbf{2.080}$
 Average flange thickness (weighted over length) (in); $t_f = \mathbf{1.302}$
 Width of deck overhang sealed (ft); $w_{fascia} = (L_{fascia} - b_f / 2) = \mathbf{2.908}$

Sealing perimeter (ft); $P_{deck} = perim_{bar} + (h_{avg} + t_f + t_{deck}) / 12 + w_{fascia} = \mathbf{11.816}$

Total sealing area on bridge deck (sq ft); $A_{512_deck} = P_{deck} \times L_{deck} \times 2 = \mathbf{4660.301}$

Parapets (on approach slabs)

*Parapet perimeter only

Perimeter of parapet (ft); $perim_{bar} = \mathbf{7.896}$
 Length of parapet on approach slabs (ft); $L_{bar_app} = 15.9$
 End area of parapet transition (sq ft); $A_{par_end} = 2.33 \times 10/12 + 8/12 \times 4/12 = \mathbf{2.164}$

Total sealing area of parapets on approaches (sq ft); $A_{512_par} = 4 \times (A_{par_end} + perim_{bar} \times L_{bar_app}) = \mathbf{510.858}$

TOTAL AREA OF SEALING (SY); $T_{512} = \text{ceiling}((A_{512_abut} + A_{512_ww} + A_{512_deck} + A_{512_par}) / 9, 5) = \mathbf{655.000}$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project MED-252-03.95 PID 88883				Job Ref. J20180414.000	
Section Structure Estimated Quantities – Final Tracings				Sheet no./rev. 14	
Calc. by EIW	Date Rev. 10/30/19	Chk'd by PJW	Date 9/16/19	App'd by SMK	Date 11/7/19

ITEM 512 – TYPE B WATERPROOFING

*3' wide at wingwall horizontal construction joint

Width of waterproofing (ft);

$$W_{\text{TypeB}} = 3$$

Wingwall length (ft);

$$L_{\text{WW}} = 12.570$$

Total Area of Type B Waterproofing (SY);

$$A_{\text{Type2}} = \text{ceiling}((4 \times W_{\text{TypeB}} \times L_{\text{WW}}) / 9, 1) = 17.000$$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000			
Section				Structure Estimated Quantities – Final Tracings					
				Sheet no./rev.				15	
Calc. by	Date	Chk'd by	Date	App'd by	Date				
EIW	Rev. 10/30/19	PJW	9/16/19	SMK	11/7/19				

ITEM 513 – STRUCTURAL STEEL MEMBERS, LEVEL 3, AS PER PLAN

Main Steel Members

Length from CL brg to first field splice (ft); $L_{sp1} = 57 + 16.5 + 0.5 = 74.000$
 Length from splice to splice (ft); $L_{sp2} = 81 - 16.5 - 16.5 = 48.000$
 Length from splice to CL brg (ft); $L_{sp3} = 57 + 16.5 + 0.5 = 74.000$

Number of interior beams (each); $N_{int} = 2$
 Number of fascia beams (each); $N_{ext} = 2$
 Total Number of beams (each); $N_{beams} = N_{int} + N_{ext} = 4.000$


Unit Weight of W36x210 (lb/ft); $W_{36x210} = 210$
 Unit Weight of W36x150 (lb/ft); $W_{36x150} = 150$
 Unit weight of field splice (lb/splice); $W_{splice} = 510$
 Unit weight of optional field splice (lb/splice); $W_{splice_opt} = 910$

Total Weight of Main Steel Members (lb); $W_{stL_main} = N_{beams} \times (2 \times W_{splice} + W_{splice_opt} + W_{36x210} \times (L_{sp1} + L_{sp3}) + W_{36x150} \times L_{sp2}) = 160840.000$

Standard Crossframes

*Per GSD-1-19 Designer Supplement, Estimated quantities are to assume the use of Type A Crossframes

*For 3'-5" overhang and 9'-6" beam spacing, angles will be L5x5x1/2 and the alternate connection plates will be used.



Gusset & Connection plate thickness (in); $t_{pl} = 0.375$
 Connection plate width (in); $W_{conn} = 7.75$
 Unit weight of L5x5x1/2 angles (lb/ft); $W_{5x5} = 16.2$
 Leg length of angles (in); $l_a = 5$
 Typical clear distance (in); $clr = 1$
 Typical bolt spacing (in); $spa_b = 3$
 Bolt horizontal edge distance (in); $edge_h = 1.75$
 Bolt vertical edge distance (in); $edge_v = 1.5$
 Unit weight of steel plates (lb/ft³); $W_{stl} = 490$
 Beam spacing (ft); $S_{bm} = 9.5$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000	
Section		Structure Estimated Quantities – Final Tracings		Sheet no./rev.		16	
Calc. by	Date	Chk'd by	Date	App'd by	Date		
EIW	Rev. 10/30/19	PJW	9/16/19	SMK	11/7/19		

W36x210 beam height (ft); $h_{36x210} = 3.058$
W36x210 flange width (ft); $b_f = 1.017$
W36x210 flange thickness (ft); $t_{f,36x210} = 1.26/12 = 0.105$
W36x210 web thickness (ft); $t_{w,36x210} = 0.83/12 = 0.069$

W36x150 beam height (ft); $h_{36x150} = 35.9/12 = 2.992$
W36x150 flange width (ft); $b_{f,36x150} = 12.2/12 = 1.017$
W36x150 flange thickness (ft); $t_{f,36x150} = 0.79/12 = 0.066$
W36x150 web thickness (ft); $t_{w,36x150} = 0.60/12 = 0.050$

****Gusset plate area extend horizontally 6" past connection plate to achieve 5" weld on bottom horizontal angle****

Bottom gusset plate area (sq ft); $A_{bg} = (6 + W_{conn} - clr) \times (3 + (3 \times spa_b) + edge_v) / 144 = 1.195$

Top gusset plate area (sq ft); $A_{tg} = (6 + W_{conn} - clr) \times (3 + (2 \times spa_b) + edge_v) / 144 = 0.930$

Connection plate area (sq ft); $A_{conn} = W_{conn} / 12 \times (h_{36x210} - 2 \times t_{f,36x210}) = 1.840$

Horizontal angle length (ft); $La_h = S_{bm} - t_{w,36x210}/12 - 2 \times (W_{conn} + clr)/12 = 8.036$

Diagonal angle vertical dimension (ft); $vert_{dia} = h_{36x210} - 2 \times t_{f,36x210} - (2 + clr + la + clr)/12 - (2 + clr + la)/12 = 1.432$

Diagonal angle length (ft); $La_{dia} = \sqrt{(La_h)^2 + (vert_{dia})^2} = 8.162$



Weight per standard cross-frame (lb); $W_{cf} = 1.05 \times (W_{5x5} \times (La_h + 2 \times La_{dia}) + 2 \times W_{stl} \times t_{pl} \times (A_{bg} + A_{tg} + A_{conn}) / 12) = 541.862$

(*includes 5% for fill plate and bolts*)

Total number of standard crossframes; $N_{scf} = 38$

Total standard crossframe weight (lb); $W_{stl_scf} = N_{scf} \times W_{cf} = 20590.752$

Special Pipe Support Crossframes



Top gusset plate area (sq ft); $A_{tg} = 0.930$

Connection plate area (sq ft); $A_{conn} = 1.840$

Horizontal angle length (ft); $La_h = 8.036$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project MED-252-03.95 PID 88883				Job Ref. J20180414.000	
Section Structure Estimated Quantities – Final Tracings				Sheet no./rev. 17	
Calc. by EIW	Date Rev. 10/30/19	Chk'd by P JW	Date 9/16/19	App'd by SMK	Date 11/7/19

Weight per special crossframe 1 cross-frame (lb); $W_{cf1} = 1.05 \times (W_{5x5} \times L_{a_h} + 2 \times W_{stl} \times t_{pl} \times (A_{tg} + A_{conn}) / 12) = \mathbf{225.739}$
 (*includes 5% for fill plate and bolts*)

Diagonal angle vertical dimension (ft); $vert_{dia12} = h_{36x210} - 2 \times t_{f_{36x210}} - (2 + clr + l_a) / 12 - (2 + clr) / 12 = \mathbf{1.932}$
 Diagonal angle 1 horizontal dimension (ft); $horiz_{dia1} = 5.75 - t_{w_{36x210}} / 2 / 12 - (w_{conn} + clr) / 12 - 10 / 12 = \mathbf{4.185}$
 Diagonal angle 2 horizontal dimension (ft); $horiz_{dia2} = 3.75 - t_{w_{36x210}} / 2 / 12 - (w_{conn} + clr) / 12 - 7 / 12 = \mathbf{2.435}$

Diagonal angle 1 length (ft); $L_{a_dia1} = \sqrt{(vert_{dia12}^2 + horiz_{dia1}^2)} = \mathbf{4.609}$
 Diagonal angle 2 length (ft); $L_{a_dia2} = \sqrt{(vert_{dia12}^2 + horiz_{dia2}^2)} = \mathbf{3.108}$

Weight per special crossframe 2 cross-frame (lb); $W_{cf2} = 1.05 \times (W_{5x5} \times (L_{a_h} + L_{a_dia1} + L_{a_dia2}) + 2 \times W_{stl} \times t_{pl} \times (A_{tg} + A_{conn} + 1.65) / 12) = \mathbf{410.059}$
 (*includes 5% for fill plate and bolts*)

Total number of Special Pipe Crossframe 1; $N_{pcf1} = 2$
 Total number of Special Pipe Crossframe 2; $N_{pcf2} = 18$

Total special pipe crossframe weight (lb); $W_{stl_pcf} = N_{pcf1} \times W_{cf1} + N_{pcf2} \times W_{cf2} = \mathbf{7832.546}$

TOTAL WEIGHT OF STEEL (LB); $T_{513} = \mathbf{ceiling}(W_{stl_main} + W_{stl_scf} + W_{stl_pcf} , 1) = \mathbf{189264.000}$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project MED-252-03.95 PID 88883				Job Ref. J20180414.000	
Section Structure Estimated Quantities – Final Tracings				Sheet no./rev. 18	
Calc. by EIW	Date Rev. 10/30/19	Chk'd by PJW	Date 9/16/19	App'd by SMK	Date 11/7/19

ITEM 513 – WELDED SHEAR STUD CONNECTORS

Studs per location; $stud = 3$
Studs per beam; $N_{stud} = 68 + 49 + 29 + 29 + 50 + 67 = 292.000$

Number of interior beams (each); $N_{int} = 2.000$
Number of fascia beams (each); $N_{ext} = 2.000$

TOTAL NUMBER OF SHEAR STUDS (EA); $T_{stud} = stud \times N_{stud} \times (N_{int} + N_{ext}) = 3504.000$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project MED-252-03.95 PID 88883				Job Ref. J20180414.000	
Section Structure Estimated Quantities – Final Tracings				Sheet no./rev. 19	
Calc. by EIW	Date Rev. 10/30/19	Chk'd by P JW	Date 9/16/19	App'd by SMK	Date 11/7/19

ITEM 514 – FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT

ITEM 514 – FIELD PAINTING STRUCTURAL STEEL, FINISH COAT

Number of interior beams (each); $N_{int} = 2.000$
 Number of fascia beams (each); $N_{ext} = 2.000$
 W36x210 beam height (ft); $h_{36x210} = 3.058$
 W36x210 flange width (ft); $b_f = 1.017$
 W36x210 flange thickness (ft); $t_{f_{36x210}} = 0.105$
 W36x210 web thickness (ft); $t_{w_{36x210}} = 0.069$

W36x150 beam height (ft); $h_{36x150} = 2.992$
 W36x150 flange width (ft); $b_{f_{36x150}} = 1.017$
 W36x150 flange thickness (ft); $t_{f_{36x150}} = 0.066$
 W36x150 web thickness (ft); $t_{w_{36x150}} = 0.050$

Length from CL brg to first field splice (ft); $L_{sp1} = 74.000$
 Length from splice to splice (ft); $L_{sp2} = 48.000$
 Length from splice to CL brg (ft); $L_{sp3} = 74.000$

W36x210 Beam Section

Length of W36x210 between abutment diaphragms per beam line (ft); $L_{36x210} = L_{sp1} + L_{sp3} - 2 \times 1.5 = 145.000$
 W36x210 perimeter (ft); $P_{36x210} = b_f + 2 \times (b_f - t_{w_{36x210}}) + 2 \times h_{36x210} = 9.028$

W36x150 Beam Section

Length of W36x150 between abutment diaphragms per beam line (ft); $L_{36x150} = L_{sp2} = 48.000$
 W36x150 perimeter (ft); $P_{36x150} = b_{f_{36x150}} + 2 \times (b_{f_{36x150}} - t_{w_{36x150}}) + 2 \times h_{36x150} = 8.933$

Total Painting – main steel members (sq ft); $T_{514_main} = N_{beams} \times (P_{36x210} \times L_{36x210} + P_{36x150} \times L_{36x150}) = 6951.633$

Crossframes

From Steel weight calc

Bottom gusset plate area (sq ft); $A_{bg} = 1.195$
 Top gusset plate area (sq ft); $A_{tg} = 0.930$
 Connection plate area (sq ft); $A_{conn} = 1.840$
 Gusset & Connection plate thickness (in); $t_{pl} = 0.375$
 Leg length of angles (in); $l_a = 5.000$
 Horizontal angle length (ft); $L_{a_h} = 8.036$
 Diagonal angle length (ft); $L_{a_dia} = 8.162$
 Crossframes per bay; $N_{cf} = 16.000$

Perimeter of L5x5x1/2 angles (ft); $P_{5x5} = (5+5+0.5+4.5+4.5+0.5) / 12 = 1.667$

Painted area of crossframe gusset and connection plates (sq ft)



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project				Job Ref.	
MED-252-03.95 PID 88883				J20180414.000	
Section				Sheet no./rev.	
Structure Estimated Quantities – Final Tracings				20	
Calc. by	Date	Chk'd by	Date	App'd by	Date
EIW	Rev. 10/30/19	PJW	9/16/19	SMK	11/7/19

Assumes 1/2 of each gusset plate is covered in connection plate painting area overlap, overlap of angle and gusset plate not considered, plate edge thickness not considered;

$$A_{514_pl} = 2 \times A_{conn} + 0.5 \times 2 \times A_{bg} + 0.5 \times 2 \times A_{lg} = \mathbf{5.804}$$

Painted area of crossframe angle members (sq ft); $A_{514_a} = P_{5 \times 5} \times (L_{a_h} + 2 \times L_{a_dia}) - 6 \times l_a \times 5 / 144 = \mathbf{39.560}$

Total Painting – crossframe members (sq ft); $T_{514_cf} = (N_{beams} - 1) \times N_{cf} \times (A_{514_pl} + A_{514_a}) = \mathbf{2177.459}$

TOTAL AREA OF PAINTING (SQ FT); $T_{514} = \text{ceiling}(T_{514_main} + T_{514_cf}, 1) = \mathbf{9130.000}$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project				Job Ref.	
MED-252-03.95 PID 88883				J20180414.000	
Section				Sheet no./rev.	
Structure Estimated Quantities – Final Tracings				21	
Calc. by	Date	Chk'd by	Date	App'd by	Date
EIW	Rev. 10/30/19	PJW	9/16/19	SMK	11/7/19

ITEM 514 – FINAL INSPECTION REPAIR

*Per CMS, one location per 150 linear foot of girder

Length of beams (ft); $L_{beam} = 195.000$

Number of interior beams (each); $N_{int} = 2.000$

Number of fascia beams (each); $N_{ext} = 2.000$

Number of locations per beam line (each); $N_{inspec} = ceiling(L_{beam} / 150, 1) = 2.000$

TOTAL NUMBER OF INSPECTION LOCATIONS (EA); $T_{insp} = (N_{int} + N_{ext}) \times N_{inspec} = 8.000$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000					
Section				Structure Estimated Quantities – Final Tracings				Sheet no./rev.		22	
Calc. by		Date		Chk'd by		Date		App'd by		Date	
EIW		Rev. 10/30/19		PJW		9/16/19		SMK		11/7/19	

ITEM 514 – FIELD PAINTING MISC.: EXISTING SANITARY PIPE

*Includes surface prep and priming for existing pipe remaining.

Length of existing pipe to remain (ft);


$$L_{\text{pipe_ex}} = 155$$

OD of pipe (ft);

$$OD_{\text{pipe}} = 12.75/12 = 1.063$$

Total pipe surface area for surface prep & painting (SQ FT);

$$T_{514_ex \text{ pipe}} = \text{ceiling}(\pi) \times OD_{\text{pipe}}^2 \times L_{\text{pipe_ex}} / 4, 1) = 138.000$$

 Osborn Engineering 1100 Superior Avenue - Suite 300 Cleveland, Ohio 44114	Project				Job Ref.	
	MED-252-03.95 PID 88883				J20180414.000	
	Section				Sheet no./rev.	
Structure Estimated Quantities – Final Tracings				23		
Calc. by	Date	Chk'd by	Date	App'd by	Date	
EIW	Rev. 10/30/19	PJW	9/16/19	SMK	11/7/19	

ITEM 514 – FIELD PAINTING MISC.: NEW SANITARY PIPE

*Includes intermediate and finish coat for segments of new sanitary line.

Total length of pipe to be painted (ft); $L_{pipe_tot} = 192$
Length of existing pipe to remain (ft); $L_{pipe_ex} = 155.000$
OD of pipe (ft); $OD_{pipe} = 1.063$

Total new pipe surface area for intermediate and finish coat (sq ft);

$$T_{514_pipe_new} = \text{ceiling}(\pi() \times OD_{pipe}^2 \times (L_{pipe_tot} - L_{pipe_ex}) / 4, 1) = 33.000$$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project				Job Ref.	
MED-252-03.95 PID 88883				J20180414.000	
Section				Sheet no./rev.	
Structure Estimated Quantities – Final Tracings				24	
Calc. by	Date	Chk'd by	Date	App'd by	Date
EIW	Rev. 10/30/19	PJW	9/16/19	SMK	11/7/19

ITEM 516 – ARMORLESS PREFORMED JOINT SEAL

**Measured as length of sleeper slab along the bridge skew.*

Width of approach slabs at ends (ft); $W_{app_curb} = 33.000$

Bridge skew; $\Theta = 25$

Seal length along skew (ft); $PJS = W_{app_curb} / \cos(\Theta) = 36.411$

TOTAL SEAL LENGTH (FT); $L_{SEAL} = \text{ceiling}(2 \times PJS, 1) = 73.000$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000					
Section				Structure Estimated Quantities – Final Tracings				Sheet no./rev.		25	
Calc. by		Date		Chk'd by		Date		App'd by		Date	
EIW		Rev. 10/30/19		P JW		9/16/19		SMK		11/7/19	

ITEM 516 – 1” PREFORMED EXPANSION JOINT FILLER

**Located between approach and bridge-mounted parapet*

Typical parapet section area (sq ft);

$$A_{par} = 4.083$$

Bridge skew;

$$\Theta = 25.000$$

Parapet area along skew (ft);

$$A_{par_skew} = A_{par} / \cos(\Theta) = 4.505$$

TOTAL PEJF AREA (SQ FT);

$$L_{PEJF_1} = \text{ceiling}(A_{par_skew} \times 4, 1) = 19.000$$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project MED-252-03.95 PID 88883				Job Ref. J20180414.000	
Section Structure Estimated Quantities – Final Tracings				Sheet no./rev. 26	
Calc. by EIW	Date Rev. 10/30/19	Chk'd by P JW	Date 9/16/19	App'd by SMK	Date 11/7/19

ITEM 516 – 2” PREFORMED EXPANSION JOINT FILLER

**Located between wingwall and abutment diaphragm*

Width of wingwall (ft); $w_{ww} = 2.500$

Bridge skew; $\Theta = 25.000$

Wingwall width along skew (ft); $w_{ww_skew} = w_{ww} / \cos(\Theta) = 2.758$

NW WW height at PEJF (Ft); $h_{pejf_NW} = 827.67 - 822.80 = 4.870$

NE WW height at PEJF (Ft); $h_{pejf_NE} = 827.71 - 822.84 = 4.870$

SW WW height at PEJF (Ft); $h_{pejf_SW} = 828.30 - 823.43 = 4.870$

SE WW height at PEJF (Ft); $h_{pejf_SE} = 828.35 - 823.47 = 4.880$

TOTAL PEJF AREA (SQ FT); $L_{PEJF_2} = \text{ceiling}(w_{ww_skew} \times (h_{pejf_NW} + h_{pejf_NE} + h_{pejf_SW} + h_{pejf_SE}), 1) =$
54.000



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000					
Section				Structure Estimated Quantities – Final Tracings				Sheet no./rev.		27	
Calc. by		Date		Chk'd by		Date		App'd by		Date	
EIW		Rev. 10/30/19		PJW		9/16/19		SMK		11/7/19	

ITEM 516 – SEMI-INTEGRAL EXPANSION JOINT SEAL

Abutment length (ft);

$$L_{abut} = 39.000$$

Length of seal (ft);

$$L_{exp_jt_seal} = L_{abut} + 3 = 42.000$$

Total Length of Semi-integral expansion joint seal (FT);

$$L_{jt_seal} = \text{ceiling}(2 \times L_{exp_jt_seal}, 1) = 84.000$$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project				Job Ref.	
MED-252-03.95 PID 88883				J20180414.000	
Section				Sheet no./rev.	
Structure Estimated Quantities – Final Tracings				28	
Calc. by	Date	Chk'd by	Date	App'd by	Date
EIW	Rev. 10/30/19	PJW	9/16/19	SMK	11/7/19

ITEM 516 – ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE), AS PER PLAN

Total Number of beams (each); $N_{beams} = 4.000$

TOTAL NUMBER OF ABUTMENT BEARINGS(EA); $T_{BRG_abut} = N_{beams} \times 2 = 8.000$

TOTAL NUMBER OF PIER BEARINGS(EA); $T_{BRG_pier} = N_{beams} \times 2 = 8.000$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project MED-252-03.95 PID 88883				Job Ref. J20180414.000	
Section Structure Estimated Quantities – Final Tracings				Sheet no./rev. 29	
Calc. by EIW	Date Rev. 10/30/19	Chk'd by P JW	Date 9/16/19	App'd by SMK	Date 11/7/19

ITEM 518 – POROUS BACKFILL WITH GEOTEXTILE FABRIC

*Item includes 2'-0" thick porous backfill behind abutments and wingwalls.

Proposed approach slab thickness (ft); $t_{app} = 1.083$
 Diaphragm height (ft); $h_{diaph} = 4.711$
 Assumed bearing height (ft); $h_{brg} = 0.196$
 Abutment length (ft); $L_{abut} = 39.000$
 Abut stem height – RA (ft); $h_{RA_stem} = 2.180$
 Abut stem height – FA (ft); $h_{FA_stem} = 2.180$
 Abut stem width (Ft); $W_{stem} = 3.000$
 Footing width (Ft); $W_{ftg} = 4.500$
 Footing height (Ft); $h_{ftg} = 3.000$

Porous backfill thickness (ft); $t_{518} = 2$
 Porous backfill area behind RA (sq ft); $A_{518_RA} = t_{518} \times (h_{RA_stem} + h_{brg} + h_{diaph} - t_{app}) + (t_{518} - (W_{ftg} - W_{stem})/2) \times h_{ftg} = 15.758$
 Porous backfill area behind FA (sq ft); $A_{518_FA} = t_{518} \times (h_{FA_stem} + h_{brg} + h_{diaph} - t_{app}) + (t_{518} - (W_{ftg} - W_{stem})/2) \times h_{ftg} = 15.758$

Average Wingwall length (ft); $L_{WW} = 12.570$
 NW wingwall average ht above footing (ft); $H_{WW_NW} = 4.810$
 NE wingwall average ht above footing (ft); $H_{WW_NE} = 5.250$
 SW wingwall average ht above footing (ft); $H_{WW_SW} = 4.685$
 SE wingwall average ht above footing (ft); $H_{WW_SE} = 4.855$

Porous backfill area behind NW wingwall (sq ft); $A_{518_NW} = (H_{WW_NW} - 1.5) \times t_{518} + (t_{518} - (W_{ftg} - W_{stem})/2) \times h_{ftg} = 10.370$
 Porous backfill area behind NE wingwall (sq ft); $A_{518_NE} = (H_{WW_NE} - 1.5) \times t_{518} + (t_{518} - (W_{ftg} - W_{stem})/2) \times h_{ftg} = 11.250$
 Porous backfill area behind SW wingwall (sq ft); $A_{518_SW} = (H_{WW_SW} - 1.5) \times t_{518} + (t_{518} - (W_{ftg} - W_{stem})/2) \times h_{ftg} = 10.120$
 Porous backfill area behind SE wingwall (sq ft); $A_{518_SE} = (H_{WW_SE} - 1.5) \times t_{518} + (t_{518} - (W_{ftg} - W_{stem})/2) \times h_{ftg} = 10.460$

TOTAL VOL POROUS BACKFILL (CY); $T_{518} = \text{ceiling}((L_{abut} \times (A_{518_RA} + A_{518_FA}) + L_{WW} \times (A_{518_NW} + A_{518_NE} + A_{518_SW} + A_{518_SE}))/ 27, 1) = 66.000$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000					
Section				Structure Estimated Quantities – Final Tracings				Sheet no./rev.		30	
Calc. by		Date		Chk'd by		Date		App'd by		Date	
EIW		Rev. 10/30/19		PJW		9/16/19		SMK		11/7/19	

ITEM 518 – 6” PERFORATED CORRUGATED PLASTIC PIPE

*To run behind abutments and wingwalls

Abutment length (ft); $L_{abut} = 39.000$

Wingwall length (ft); $L_{ww} = 12.570$

TAL LENGTH PCPP (FT); $T_{PCPP} = ceiling(2 \times (L_{abut} + 2 \times L_{ww}), 1) = 129.000$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000					
Section				Structure Estimated Quantities – Final Tracings				Sheet no./rev.		31	
Calc. by		Date		Chk'd by		Date		App'd by		Date	
EIW		Rev. 10/30/19		P JW		9/16/19		SMK		11/7/19	

ITEM 518 – 6” NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS

*From ends of wingwalls to outlet in slope.

NW Wingwall (ft); $NP_{NW} = 12.5$

NE Wingwall (ft); $NP_{NE} = 17.5$

SW Wingwall (ft); $NP_{SW} = 11.5$

SE Wingwall (ft); $NP_{SE} = 15.5$

TOTAL LENGTH NPCPP (FT); $T_{NPCPP} = \text{ceiling}(NP_{NW} + NP_{NE} + NP_{SW} + NP_{SE}, 5) = 60.000$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000					
Section				Structure Estimated Quantities – Final Tracings				Sheet no./rev.		32	
Calc. by		Date		Chk'd by		Date		App'd by		Date	
EIW		Rev. 10/30/19		PJW		9/16/19		SMK		11/7/19	

ITEM 524 – DRILLED SHAFTS, 36” DIAMETER, INTO BEDROCK

*At abutments into rock

Total number of drilled shafts per abutment; $N_{DS_abut} = 4$

Minimum rock socket depth (ft); $d_{sock} = 10$

TOTAL LENGTH OF DS INTO ROCK (ABUT) (FT); $T_{524_rock_abut} = ceiling(2 \times N_{DS_abut} \times d_{sock} , 1) = 80.000$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project MED-252-03.95 PID 88883				Job Ref. J20180414.000	
Section Structure Estimated Quantities – Final Tracings				Sheet no./rev. 33	
Calc. by EIW	Date Rev. 10/30/19	Chk'd by P JW	Date 9/16/19	App'd by SMK	Date 11/7/19

ITEM 524 – DRILLED SHAFTS, 42” DIAMETER, ABOVE BEDROCK

*At abutments above rock & at piers above T/rock elevation

Total number of drilled shafts per abutment; $N_{DS_abut} = 4.000$

Total number of drilled shafts per pier; $N_{DS_pier} = 3$

Proposed top of drilled shaft - RA; $EL_{T_DSra} = 818.43 + 0.25 = 818.680$

Proposed top of drilled shaft – FA; $EL_{T_DSfa} = 817.80 + 0.25 = 818.050$

Top of rock elevation – RA; $TR_{RA} = 811.26$

Top of rock elevation – FA; $TR_{FA} = 809.92$

Proposed top of drilled shaft at piers; $EL_{T_Dsp} = 809.11$

Top of rock elevation – P1; $TR_{P1} = 806.69$

Top of rock elevation – P2; $TR_{P2} = 806.46$

TOTAL LENGTH OF DS ABOVE ROCK (FT); $T_{524_ABOVE} = \text{ceiling}(N_{DS_abut} \times (EL_{T_DSra} - TR_{RA} + EL_{T_DSfa} - TR_{FA}) + N_{DS_pier} \times (EL_{T_Dsp} - TR_{P1} + EL_{T_DS} - TR_{P2}), 1) = 78.000$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000					
Section				Structure Estimated Quantities – Final Tracings				Sheet no./rev.		34	
Calc. by		Date		Chk'd by		Date		App'd by		Date	
EIW		Rev. 10/30/19		PJW		9/16/19		SMK		11/7/19	

ITEM 524 – DRILLED SHAFTS, 42” DIAMETER, INTO BEDROCK

* At pier columns

Total number of drilled shafts per pier; $N_{DS_pier} = 3.000$

Minimum rock socket depth at piers (ft); $d_{sock_pier} = 12$

TOTAL LENGTH OF DS INTO ROCK (PIER) (FT); $T_{524_rock_pier} = ceiling(2 \times N_{DS_pier} \times d_{sock_pier} , 1) = 72.000$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000					
Section				Structure Estimated Quantities – Final Tracings				Sheet no./rev.		35	
Calc. by		Date		Chk'd by		Date		App'd by		Date	
EIW		Rev. 10/30/19		PJW		9/16/19		SMK		11/7/19	

ITEM 526 – REINFORCED CONCRETE APPROACH SLABS WITH QC/QA (T=13”), AS PER PLAN

Length of approach slabs with barrier (Ft); $L_{bar_app} = 15.900$
Width of approach slabs with barrier (ft); $W_{app_bar} = 32 + 1.67 + 1.67 = 35.340$

Length of approach slabs with curb (Ft); $L_{app_curb} = 20 - L_{bar_app} = 4.100$
Width of approach slabs with curb (ft); $W_{app_curb} = 33$

TOTAL APPROACH SLAB AREA (SQ YD); $A_{app} = ceiling(2 \times (L_{bar_app} \times W_{app_bar} + L_{app_curb} \times W_{app_curb}) / 9, 1) = 155.000$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project				Job Ref.	
MED-252-03.95 PID 88883				J20180414.000	
Section				Sheet no./rev.	
Structure Estimated Quantities – Final Tracings				36	
Calc. by	Date	Chk'd by	Date	App'd by	Date
EIW	Rev. 10/30/19	PJW	9/16/19	SMK	11/7/19

ITEM 526 – Type C Installation

**Measured as length of sleeper slab along the bridge skew.*

Width of approach slabs at ends (ft); $W_{app_curb} = 33.000$
Bridge skew; $\Theta = 25.000$
Sleeper slab length along skew (ft); $SS = W_{app_curb} / \cos(\Theta) = 36.411$

TOTAL INSTALLATION LENGTH (FT); $L_{install} = \text{ceiling}(2 \times SS, 1) = 73.000$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000					
Section				Structure Estimated Quantities – Final Tracings				Sheet no./rev.		37	
Calc. by	Date	Chk'd by	Date	App'd by	Date						
EIW	Rev. 10/30/19	PJW	9/16/19	SMK	11/7/19						

ITEM 601 – ROCK CHANNEL PROTECTION, TYPE C

*At forward abutment

*Included with Roadway Quantities on General Summary

Average bank slope; $m_{bank} = 1/5 = 0.200$

Plan view length of slope protection (ft); $L_{601_plan} = 35.25$

Adjusted length of slope protection (ft); $L_{601_adj} = \sqrt{(L_{601_plan}^2 + (L_{601_plan} \times m_{bank})^2)} = 35.948$

Width of slope protection (ft); $W_{601} = 60$

Thickness of slope protection (ft); $t_{601} = 2$

TOTAL VOLUME OF SLOPE PROTECTION (CU YD); $T_{SP} = ceiling(L_{601_adj} \times W_{601} \times t_{601} / 27, 1) = 160.000$



Osborn Engineering
1100 Superior Avenue - Suite 300
Cleveland, Ohio 44114

Project		MED-252-03.95 PID 88883		Job Ref.		J20180414.000					
Section				Structure Estimated Quantities – Final Tracings				Sheet no./rev.		38	
Calc. by	Date	Chk'd by	Date	App'd by	Date						
EIW	Rev. 10/30/19	PJW	9/16/19	SMK	11/7/19						

ITEM 838 – GABIONS, AS PER PLAN

*Included with Roadway Quantities on General Summary

Plan area of new gabions between proposed and existing rear abutment (sq ft); $A_{gab} = 927$
Estimated plan area of replacement gabions at new pier columns (sq ft); $A_{gab_pier} = 6 \times 6 \times 3 = 108.000$
Estimated plan area of infill gabions at existing pier columns removed (sq ft); $A_{gab_fill} = 6 \times 6 \times 2 = 72.000$

Depth of new gabions (ft); $D_{gab} = 3$

TOTAL VOLUME OF GABIONS (CU YD); $T_{GAB} = ceiling((A_{gab} + A_{gab_pier} + A_{gab_fill}) \times D_{gab} / 27, 1) = 123.000$