

U:\Accounts\RAVIO\RAVIO22001 - MEG-Racine Walk_Ride\DESIGN\CT\ProjectData\115332\400-Engineering\Roadway\Sheets\115332_GG001.dwg_February 22, 2024_CKaragory

SHEET NUM.											PART.		ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
5	9	10	11	12	15	16	17	27	50	64			EXT	TOTAL				
ROADWAY																		
													201	11000	LS		CLEARING AND GRUBBING	
	212												202	23000	212	SY	PAVEMENT REMOVED	
295													202	23001	295	SY	PAVEMENT REMOVED, AS PER PLAN	5
	8,996												202	30000	8,996	SF	WALK REMOVED	
	1,701												202	30001	1,701	SF	WALK REMOVED, AS PER PLAN	5
			152										202	35100	152	FT	PIPE REMOVED, 24" AND UNDER	
	3												202	53100	3	EACH	MAILBOX REMOVED	
			2										202	58100	2	EACH	CATCH BASIN REMOVED	
								LS					202	98000	LS		REMOVAL MISC.: CONCRETE BLOCK RETAINING WALL	5
									721				203	10000	721	CY	EXCAVATION	
									184				203	20000	184	CY	EMBANKMENT	
	2,572												204	10000	2,572	SY	SUBGRADE COMPACTION	
	2												204	45000	2	HOUR	PROOF ROLLING	
	14,923												608	10001	14,923	SF	4" CONCRETE WALK, AS PER PLAN	5
	330	1,445											608	52000	1,775	SF	CURB RAMP	
	1,624												608	98000	1,624	SF	WALKWAY, MISC.:BRICK PAVERS	5
	3												SPECIAL	69050000	3	EACH	MAILBOX SUPPORT, SINGLE	
		4											SPECIAL	69098000	4	EACH	STEEL BENCH	5
		5											SPECIAL	69098000	5	EACH	SAFETY BARRIER PLANTER	5
		47											SPECIAL	69098100	47	FT	DECORATIVE BOLLARD FENCE	5
EROSION CONTROL																		
2													659	00100	2	EACH	SOIL ANALYSIS TEST	
143													659	00300	143	CY	TOPSOIL	
									1,290				659	10000	1,290	SY	SEEDING AND MULCHING	
65													659	14000	65	SY	REPAIR SEEDING AND MULCHING	
65													659	15000	65	SY	INTER-SEEDING	
0.18													659	20000	0.18	TON	COMMERCIAL FERTILIZER	
0.27													659	31000	0.27	ACRE	LIME	
7													659	35000	7	MGAL	WATER	
832 15000 LS STORM WATER POLLUTION PREVENTION PLAN																		
832 15002 LS STORM WATER POLLUTION PREVENTION INSPECTIONS																		
832 15010 LS STORM WATER POLLUTION PREVENTION INSPECTION SOFTWARE																		
832 30000 10,000 EACH EROSION CONTROL																		
DRAINAGE																		
			361										611	04400	361	FT	12" CONDUIT, TYPE B	
			5										611	04600	5	FT	12" CONDUIT, TYPE C	
			5										611	98150	5	EACH	CATCH BASIN, NO. 3	
PAVEMENT																		
2,584				2,804									255	20000	5,388	FT	FULL DEPTH PAVEMENT SAWING	
49				34									301	56000	83	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
				157									304	20000	157	CY	AGGREGATE BASE	
				25									407	20000	25	GAL	NON-TRACKING TACK COAT	
16				17									441	70000	33	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22	
				17									441	70300	17	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (449)	
				52									452	10010	52	SY	6" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P	
				78									452	12010	78	SY	8" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P	
	2,584												609	12000	2,584	FT	COMBINATION CURB AND GUTTER, TYPE 2	
	284												609	26000	284	FT	CURB, TYPE 6	
WATER WORK																		
			1										638	10500	1	EACH	FIRE HYDRANT REMOVED AND RESET	
			7										638	10800	7	EACH	VALVE BOX ADJUSTED TO GRADE	

832	ITEMS REMOVED, 15000, 15010
2/22/2024	DESCRIPTION
JMZ	REV. BY
	DATE

CALCULATED SRK CHECKED JMZ
 GENERAL SUMMARY
 MEG RACINE WALK/RIDE
 7
 73