

SHEET NO.	ITEM 203	ITEM 203	ITEM 601	ITEM 203	ITEM 203	ITEM 659	ITEM 690
	EXCAVATION	EMBANKMENT	DUMPED ROCK FILL, TYPE B, APP	GRAN. EMB. APP, (NO. 8 AGG.)	GRAN. MATERIAL, TYPE B, APP (703.16)	SEEDING AND MULCHING	GEOTEXTILE FABRIC, 712.09, TYPE A
	CY	CY	CY	CY	CY	SY	SY
46	106	0	0	0	0	98	0
47	584	332	223	50	130	519	134
48	0	14	0	0	0	413	0
49	135	82	61	8	30	520	23
50	519	244	182	25	90	648	68
51	654	281	121	18	60	887	53
52	1227	870	365	101	182	1007	280
53	968	1427	244	45	122	1258	123
54	568	1567	121	0	60	1146	0
55	1067	155	0	0	0	568	0
56	4005	27	0	0	0	2260	0
57	7623	4	0	0	0	2709	0
58	9705	0	0	0	0	1984	0
59	12602	0	0	0	0	2028	0
60	13694	8	0	0	0	2034	0
61	14549	50	0	0	0	2028	0
62	18188	110	0	0	0	2028	0
63	22887	102	0	0	0	2081	0
64	22768	106	0	0	0	2123	0
65	16092	129	0	0	0	2381	0
66	7391	130	0	0	0	2109	0
67	2463	71	0	0	0	1120	0
68	2994	2614	720	113	170	1454	267
69	1864	3374	749	75	128	1075	178
70	2140	3158	753	75	127	1145	178
71	2160	1289	510	38	88	959	89
72	3242	100	0	0	0	1067	0
73	8221	0	0	0	0	1500	0
74	13796	0	0	0	0	1517	0
75	16230	0	0	0	0	1350	0
76	15587	0	0	0	0	1187	0
77	13977	114	0	0	0	1131	0
78	13302	404	271	25	52	1275	62
79	14588	634	273	45	52	1409	112
80	15703	724	274	57	52	1470	142
81	16607	826	275	68	52	1564	167
82	17287	879	276	75	52	1564	184
83	15941	843	275	72	52	1464	175
84	15008	809	275	70	52	1381	170
85	14851	776	275	73	52	1367	178
86	14222	377	137	38	26	1306	92
87	12550	0	0	0	0	1220	0
88	10246	0	0	0	0	1175	0
89	8011	0	0	0	0	1053	0
90	6627	0	0	0	0	953	0
91	11038	1415	0	0	0	2978	0
92	1477	9011	784	0	387	2917	0
93	1782	9240	904	0	446	3427	0
94	542	1133	0	0	0	1022	0
95	368	783	0	0	0	1316	0
96	414	104	0	0	0	1183	0
SUBTOTAL 1	428,570	44,316	8,068	1,071	2,462	74,378	2,675
SUBTOTAL 2	4,057	3,155	157	-	47	8,447	228
TOTAL	432,627	47,471	8,225	1,071	2,509	82,825	2,903

SHEET NO.	ITEM 203	ITEM 203	ITEM 601	ITEM 203	ITEM 659	ITEM 690
	EXCAVATION	EMBANKMENT	DUMPED ROCK FILL, TYPE B, APP	GRAN. MATERIAL, TYPE B, APP (703.16)	SEEDING AND MULCHING	GEOTEXTILE FABRIC, 712.09, TYPE A
	CY	CY	CY	CY	SY	SY
105	267	558	95	47	461	0
106	163	119	0	0	421	0
107	171	167	0	0	398	0
108	263	271	0	0	587	0
109	261	229	0	0	603	0
110	271	247	0	0	649	0
111	410	204	0	0	848	0
112	482	196	0	0	909	0
113	144	66	0	0	303	0
114	13	80	0	0	241	0
114	11	52	0	0	221	0
115	162	3	0	0	292	0
26	1439	963	62	0	2514	228
SUBTOTAL 2	4,057	3,155	157	47	8,447	228

SEEDING AND MULCHING

THE FOLLOWING QUANTITIES ARE PROVIDED TO PROMOTE GROWTH AND CARE OF PERMANENT SEEDED AREAS:

659 - SEEDING AND MULCHING = 82,825 SQ. YD.

659 - COMMERCIAL FERTILIZER 82,825 SY x 1 TON/7410 SY = 11.18 TON

659 - LIME 82,825 SQ. YD. x 9 / 43,560 = 17.1 ACRES

659 - WATER 82,825 SY x 0.0027M. GAL/SY = 223.6 M. GAL.

TOTALS TO BE CARRIED TO THE GENERAL SUMMARY.

ITEM 642 - EDGE LINE

STA. 162+00 TO STA. 214+00
 2 X 5200 FT / 5280 FT = 1.97 MILE

A TOTAL OF 1.97 MILE TO BE CARRIED TO THE GENERAL SUMMARY.

ITEM 642 - CENTERLINE

STA. 162+00 TO STA. 214+00
 5200 FT / 5280 FT = 0.98 MILE

A TOTAL OF 0.98 MILE TO BE CARRIED TO THE GENERAL SUMMARY.

ITEM 621 - RPM

STA. 162+00 TO STA. 214+00
 5200 FT / 40 FT SPACING = 130 EA

A TOTAL OF 131 EA TO BE CARRIED TO THE GENERAL SUMMARY.

ITEM 621 - RPM REMOVED

STA. 162+00 TO STA. 214+00
 5200 FT / 40 FT SPACING = 132 EA

A TOTAL OF 132 EA TO BE CARRIED TO THE GENERAL SUMMARY.

ITEM 617 - COMPACTED AGGREGATE

STA. 162+00 TO STA. 214+00
 2 x 5200 FT x 2 FT x (3 IN / 12) / 27 = 192.6 CY

A TOTAL OF 193 CY TO BE CARRIED TO THE GENERAL SUMMARY.

SHEET NO.	ITEM 208
	PRESPLITTING
	SY
57	0
58	28
59	128
60	259
61	370
62	459
63	517
64	545
65	545
66	345
67	75
68	0
72	0
73	17
74	170
75	378
76	489
77	539
78	539
79	523
80	514
81	509
82	492
83	442
84	364
85	289
86	225
87	145
88	48
89	0
TOTAL	8,954

