


SHEET NUM.										PART.			ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
3	5	6	7	8						01/NHS/05			EXT	TOTAL				
				1,147						1,147			202	30000	1,147	SF	ROADWAY WALK REMOVED	
				114						114			202	32000	114	FT	CURB REMOVED	
				1,285						1,285			608	52000	1,285	SF	CURB RAMP	
20										20			611	98630	20	EACH	DRAINAGE CATCH BASIN ADJUSTED TO GRADE	
	12									12			209	72050	12	MILE	PAVEMENT PREPARING SUBGRADE FOR SHOULDER PAVING	
350										350			253	02000	350	CY	PAVEMENT REPAIR	
	118,007									118,007			254	01000	118,007	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1.75" DEPTH	
	15,331									15,331			254	01000	15,331	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1.5" DEPTH	
	16,976									16,976			407	20000	16,976	GAL	NON-TRACKING TACK COAT	
	5,632									5,632			408	10000	5,632	GAL	PRIME COAT	
	5,843									5,843			442	10000	5,843	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446)	
	5,866									5,866			442	10080	5,866	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, 12.5 MM, TYPE A (446)	
	1,271									1,271			617	10100	1,271	CY	COMPACTED AGGREGATE	
	11.42									11.42			618	41000	11.42	MILE	RUMBLE STRIPES, EDGE LINE (ASPHALT CONCRETE)	
	5.71									5.71			618	43000	5.71	MILE	RUMBLE STRIPES, CENTER LINE (ASPHALT CONCRETE)	
	6.67									6.67			874	21000	6.67	MILE	LONGITUDINAL JOINT PREPARATION	
																	TRAFFIC CONTROL	
				340						340			621	00100	340	EACH	RPM	
				340						340			621	54000	340	EACH	RAISED PAVEMENT MARKER REMOVED	
				6.73						6.73			642	00300	6.73	MILE	CENTER LINE, TYPE 1	
				13.46						13.46			642	00104	13.46	MILE	EDGE LINE, 6", TYPE 1	
				2						2			644	01100	2	EACH	SCHOOL SYMBOL MARKING, 72"	
		316								316			644	00500	316	FT	STOP LINE	
			102							102			644	00630	102	FT	CROSSWALK LINE, 24" (HIGH VISABILITY)	
																	MAINTENANCE OF TRAFFIC	
46										46			614	12460	46	EACH	WORK ZONE MARKING SIGN	
				20.19						20.19			614	21100	20.19	MILE	WORK ZONE CENTER LINE, CLASS I, 642 PAINT	
				20.19						20.19			614	21500	20.19	MILE	WORK ZONE CENTER LINE, CLASS II, 642 PAINT	
																	INCIDENTALS	
										LS			614	11000	LS		MAINTAINING TRAFFIC	
										LS			623	10001	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER PLAN	3
										LS			624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY  
  
 DESIGNER  
 TDB  
 REVIEWER  
 MRF 05-01-24  
 PROJECT ID  
 118552  
 SHEET TOTAL  
 4 10