



MEG-124-9.20

STATE OF OHIO

E240.(019)

NON

PROJECT TO ADDRESS FLOODING LOCATION BY IMPROVING DRAINAGE

AND RAISING VERTICAL ROADWAY PROFILE OF SR 124, INCLUDING NEW STORM SEWER, GUARDRAIL, TRAFFIC CONTROL SIGNS, AND PAVEMENT MARKINGS.

PROJECT EARTH DISTURBED AREA

PROJECT EARTH DISTURBED AREA:	1.2 ACRES
ESTIMATED CONTRACTOR EARTH DISTURBED AREA:	0.6 ACRES
NOTICE OF INTENT EARTH DISTURBED AREA:	1.8 ACRES

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS, CHANGES LISTED IN THE PROPOSAL, AND THE SUPPLEMENTAL SPECIFICATION 800 VERSION INDICATED ON THE PROPOSAL, SHALL GOVERN THIS IMPROVEMENT.

[illegible]

CURRENT ADT (2026)	1053
DESIGN YEAR ADT (2046)	1163
DESIGN HOURLY VOLUME (2046)	123
DIRECTIONAL DISTRIBUTION	50%
TRUCKS (24 HOUR B&C)	4%
DESIGN SPEED	45 MPH
LEGAL SPEED	45 MPH
DESIGN FUNCTIONAL CLASSIFICATION:	
05 - MAJOR COLLECTOR	
FMS PROJECT	N/D

NONE REQUIRED

NONE REQUIRED

UNDERGROUND UTILITIES

**Contact Two Working Days
Before You Dig.**

OHIO811.org
Before You Dig

OHIO 811, 8-1-1, or 1-800-362-2764
(Non members must be called directly)

PLAN PREPARED BY:
A. MORTON THOMAS AND ASSOCIATES, INC.
250 CIVIC CENTER DRIVE, SUITE 205
COLUMBUS, OH 43215



SIGNED: _____
DATE: _____
21:47:05

STANDARD CONSTRUCTION DRAWINGS										SUPPLEMENTAL SPECIFICATIONS		SPECIAL PROVISIONS
BP-3.1	1-19-24	MG5-1.1	1-17-25	TC-41.20	10-18-13	DM-1.1	1-17-25	MT-101.60	1-17-25	SS800	7-18-25	
BP-4.1	7-19-13	MG5-2.1	1-17-25	TC-42.20	10-18-13	DM-1.2	1-17-25			SS832	7-18-25	
		MG5-4.1	1-20-17	TC-52.10	10-18-13	DM-4.4	1-15-16					
		MG5-4.3	1-18-13	TC-52.20	1-15-21	CB-2.2ABC	7-19-24					
				TC-61.30	7-19-24	MH-1	7-15-22					
				TC-65.10	1-17-14	HW-2.1	7-13-22					
				TC-65.11	1-17-25	HW-2.2	7-20-18					
				TC-71.10	4-21-23							
								</				

ΕΞΗΚΑ ΑΓΕΛΙΚΑ

DESIGNER
JAL

REVIEWER
JAH 07/15/25

119906

SUBJECT	TOTAL
P.O. 1	31

TITLE SHEET