

	Surveying	Engineering	Pı	roject Manag	ement	
Job Name:	MIA-C.R. 25A-3.54		Job No.:	CTCTR0001		
Location:	Tipp City, OH		Sheet:	1	of	3
Task: Water Quality Calculations						
Calculated B	y: DMG		Date:	4/23/2019		
Checked By:			Date:			

#### **Earth Disturbed Area:**

EDA = 2.64 AC

#### **Treatment Required:**

T% = 20% (Redevelopment, no new impervious in new permanent R/W)

 $T_{Req.} = 0.53 \text{ AC}$ 

## **BMP Calculations (Manufactured System):**

$$WQ_F = (C) * (i) * (A)$$

 $A_{Total} = 0.57 \text{ AC}$  (Total contributing area)

 $A_{Imp.} = 0.57 \text{ AC}$  (Contributing impervious area) (C = 0.9)  $A_{Per.} = 0 \text{ AC}$  (Contributing pervious area) (C = 0.3)

 $C_{Comp.} = 0.9$ 

#### **Overland Flow**

### Equation 1:

$$t_o = \frac{(1.8) * (1.1-C) * (L)^{1/2}}{(s)^{1/3}}$$

Where:  $t_{o1}$  = Time of Concentration (minutes)

C = Coefficient of runoff

L = Distance to most remote location in drainage area (feet)

s = Overland slope (percent)

## **Shallow Concentrated Flow**

## Equation 2:

$$V = (3.28) * (k) * (s)^{0.5}$$

Where: V = Velocity (fps)

k = Intercept coefficient

s = Overland slope (percent)

#### Equation 3:

$$t_s \text{ or } t_d = \frac{L}{(60) * (V)}$$

Where:  $t_s$  or  $t_d$  = Time of Concentration (minutes)

L = Flow length (feet)

V = Velocity (fps)



	Surveying	Engineering	Pı	roject Manag	ement	
Job Name:	MIA-C.R. 25A-3.54		Job No.:	CTCTR0001		
Location:	Tipp City, OH		Sheet:	2	of	3
Task:	Water Quality Calcu	ılations				
Calculated By	y: DMG		Date:	4/23/2019		

Time of Concentration #1 (Overland Flow):

Checked By:

$$C = 0.9$$

$$L = 285 \text{ ft}$$

$$s = 0.53 \%$$

$$t_o = \frac{(1.8)*(1.1-0.9)*(285)^1/2}{(0.53)^1/3} = 7.5 \text{ min.}$$

Time of Concentration #2 (Pipe Flow; D2-D3):

$$L = 63 \text{ ft}$$

$$s = 1.43 \%$$

$$V = (3.28) * (0.619) * (1.43)^0.5 = 2.43 \text{ fps}$$

$$t_s = \frac{63}{(60)*(2.43)} = 0.4 \text{ min.}$$

Time of Concentration #3 (Pipe Flow; D3-D3)

$$L = 275 \text{ ft}$$

$$s = 0.32 \%$$

$$V = (3.28) * (0.619) * (0.32)^0.5 = 1.15 \text{ fps}$$

$$t_s = \frac{275}{(60)*(1.15)} = 4 \text{ min.}$$

$$t_c = 7.5 + 0.4 + 4 + = 11.9 \text{ min.}$$

$$WQ_F = (0.9) * (1.68) * (0.57) = 0.86 cfs$$



S	Surveying	Engineering	Pi	roject Manager	nent	
Job Name: N	MIA-C.R. 25A-3.54		Job No.:	CTCTR0001		
Location: T	Tipp City, OH		Sheet:	3	of	3
Task: V	Water Quality Calcu	lations				
Calculated By:	: DMG		Date:	4/23/2019		
Checked By:			Date:			

# Manufactured System Selection (L&D, Vol. 2, Section 1117.1):

Using Tables 1117-1 and 1117-2

- ----> Manufactured System Type 1 (based on WQf = 0.86 cfs)
- ----> No. 3 Manhole, With 84" Base ID and 6" Weir
- ----> Two (2) 10' lengths of 611, 12" Type B Conduit
- ----> System Width = 15'
- ----> System Length = 30'

