

SHEET NUM.										PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
4	6	13	15	17	01/IMS/04	02/STR/04											
<b>ROADWAY</b>																	
12					12		SPECIAL	20120010	12	EACH	TREE REMOVED, 4"-12"	4					
12					12		SPECIAL	20126450	12	EACH	STUMP REMOVED, 4"-12"	4					
		60			60		202	35100	60	FT	PIPE REMOVED, 24" AND UNDER						
		1,072.5			512.5	560	202	38000	1,072.5	FT	GUARDRAIL REMOVED						
		4				4	202	42001	4	EACH	ANCHOR ASSEMBLY REMOVED, TYPE A, AS PER PLAN	4					
		2			2		202	42040	2	EACH	ANCHOR ASSEMBLY REMOVED, TYPE T						
		2			2		202	42050	2	EACH	ANCHOR ASSEMBLY REMOVED, TYPE B						
		1			1		202	58100	1	EACH	CATCH BASIN REMOVED						
74					74		SPECIAL	20270110	74	FT	PIPE CLEANOUT, 24" AND UNDER	4					
466					348	118	SPECIAL	20270130	466	FT	PIPE CLEANOUT OVER 48"	4					
		81			81		202	75001	81	FT	FENCE REMOVED, AS PER PLAN	4					
		975			512.5	462.5	606	15050	975	FT	GUARDRAIL, TYPE MGS						
		2			2		606	26050	2	EACH	ANCHOR ASSEMBLY, MGS TYPE B						
		4				4	606	26150	4	EACH	ANCHOR ASSEMBLY, MGS TYPE ENCHRP 350/MASH						
		2			2		606	26550	2	EACH	ANCHOR ASSEMBLY, MGS TYPE T						
		54			54		607	23001	54	FT	FENCE, TYPE CLT, AS PER PLAN	4					
		27			27		607	23005	27	FT	FENCE REBUILT, TYPE CLT, AS PER PLAN	4					
		500			500		622	41100	500	FT	PORTABLE BARRIER, UNANCHORED						
<b>EROSION CONTROL</b>																	
66						66	659	00300	66	CY	TOPSOIL						
599						599	659	00500	599	SY	SEEDING AND MULCHING, CLASS 1						
500					500		659	00530	500	SY	SEEDING AND MULCHING, CLASS 3B						
157					157		659	00590	157	SY	SEEDING AND MULCHING, CLASS 6						
63					33	30	659	14000	63	SY	REPAIR SEEDING AND MULCHING						
63					33	30	659	15000	63	SY	INTER-SEEDING						
0.01					0.01	0.01	659	20000	0.01	TON	COMMERCIAL FERTILIZER						
0.26					0.14	0.12	659	31000	0.26	ACRE	LIME						
6.9					3.6	3.3	659	35000	6.9	MGAL	WATER						
					3,000	1,000	832	30000	4,000	EACH	EROSION CONTROL						
<b>DRAINAGE</b>																	
		25			25		605	12200	25	FT	6" DEEP PIPE UNDERDRAINS						
		35			35		611	08900	35	FT	21" CONDUIT, TYPE B, 707.05						
		1			1		611	98301	1	EACH	CATCH BASIN, NO. 5, AS PER PLAN	4					
<b>PAVEMENT</b>																	
		48			33	15	304	20000	48	CY	AGGREGATE BASE						
<b>STRUCTURE REPAIR (MER-119-13.74)</b>																	
				LS	LS		201	11000	LS		CLEARING AND GRUBBING						
				LS	LS		503	11100	LS		COFFERDAMS AND EXCAVATION BRACING						
				18.5	18.5		601	32000	18.5	CY	ROCK CHANNEL PROTECTION, TYPE A WITH FILTER						
				118	118		833	10001	118	FT	CONDUIT RENEWAL USING SPRAY APPLIED STRUCTURAL LINER, ROUND CONDUIT, AS PER PLAN, 77"x121"	4					
<b>STRUCTURE REPAIR (MIA-75-16.91)</b>																	
				LS	LS		201	11000	LS		CLEARING AND GRUBBING						
				310.5	310.5		203	20000	310.5	CY	EMBANKMENT						
				LS	LS		503	11100	LS		COFFERDAMS AND EXCAVATION BRACING						
				337	337		509	25000	337	LB	UNCOATED STEEL REINFORCEMENT						
				37	37		601	32000	37	CY	ROCK CHANNEL PROTECTION, TYPE A WITH FILTER						
				358	358		611	96550	358	FT	FIELD PAVING OF EXISTING PIPE, 77"x121"						
<b>MAINTENANCE OF TRAFFIC</b>																	
		24			24		614	11110	24	hour	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE						
		1			1		614	12380	1	EACH	WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (UNIDIRECTIONAL)						
		14			14		614	13310	14	EACH	BARRIER REFLECTOR, TYPE 1, ONE WAY						
		14			14		614	13350	14	EACH	OBJECT MARKER, ONE WAY						
<b>INCIDENTALS</b>																	
					LS	LS	614	11000	LS		MAINTAINING TRAFFIC						
					LS	LS	624	10000	LS		MOBILIZATION						

GENERAL SUMMARY

DESIGN AGENCY



DISTRICT 7  
ENGINEERING

DESIGNER

REB

REVIEWER

CWW 10-16-23

PROJECT ID

114980

SHEET

P.12

TOTAL

18