SHEET NUM.													PART.	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
							3	4	5	7	9		01/NHS/PV						
																		ROADWAY	
							1						1	623	39500	1	EACH	MONUMENT BOX ADJUSTED TO GRADE	
							631						631	SPECIAL	69012150	631	GAL	ASPHALT REJUVENATING AGENT	3
							LS						LS	SPECIAL	69012160	LS		TESTING	3
																		DRAINAGE	
							15						15	611	99654	15	EACH	MANHOLE ADJUSTED TO GRADE	
																		PAVEMENT	
							500						500	253	01001	500	SY	PAVEMENT REPAIR, AS PER PLAN	3
										14,556			14,556	254	01000	14,556	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1 3/4" DEPTH	
							50						50	254	01601	50	SY	PATCHING PLANED SURFACE, AS PER PLAN	3
										1,240			1,240	407	20000	1,240	GAL	NON-TRACKING TACK COAT	
										709			709	442	00100	709	CY	ANTI-SEGREGATION EQUIPMENT	
										709			709	442	20001	709	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (448), AS PER PLAN, PG76-22M	3
																		WATER WORK	
							13						13	638	10800	13	EACH	VALVE BOX ADJUSTED TO GRADE	
																		TRAFFIC CONTROL	
											104		104	621	00100	104	EACH	RPM	
								11					11	621	00101	11	EACH	RPM, AS PER PLAN	4
											165		165	621	54000	165	EACH	RAISED PAVEMENT MARKER REMOVED	
											0.89		0.89	644	00200	0.89	MILE	LANE LINE, 4"	
											0.49		0.49	644	00300	0.49	MILE	CENTER LINE	
											311		311	644	00400	311	FT	CHANNELIZING LINE, 8"	
											96		96	644	00500	96	FT	STOP LINE	
											1,130		1,130	644	00600	1,130	FT	CROSSWALK LINE	
											90		90	644	00700	90	FT	TRANSVERSE/DIAGONAL LINE	
											4		4	644	01100	4	EACH	SCHOOL SYMBOL MARKING, 72"	
											5		5	644	01300	5	EACH	LANE ARROW	
																		TRAFFIC SIGNALS	
								1					1	632	26501	1	EACH	DETECTOR LOOP, AS PER PLAN	4
								1					1	632	27201	1	EACH	LOOP DETECTOR TIE IN, AS PER PLAN	4
																		MAINTENANCE OF TRAFFIC	
									80				80	614	11110	80	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
											1.78		1.78	614	20550	1.78	MILE	WORK ZONE LANE LINE, CLASS III, 4", 642 PAINT	
											0.98		0.98	614	21550	0.98	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
											622		622	614	23680	622	FT	WORK ZONE CHANNELIZING LINE, CLASS III, 8", 642 PAINT	
											192		192	614	26610	192	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
											8		8	614	31740	8	EACH	WORK ZONE SCHOOL SYMBOL MARKING, 72", CLASS III, 642 PAINT	
																		INCIDENTALS	
													LS	614	11000	LS		MAINTAINING TRAFFIC	
													LS	624	10000	LS		MOBILIZATION	

CALCULATED TMK
CHECKED CWW

GENERAL SUMMARY

MOT-725-18.18

I:\ProjectData\MOT\102710_SR725-1815\Design\Roadway\Sheets\102710_GG001.dgn Sheet 10/7/2020 10:30:56 AM cweiss