

SHEET NUMBER					PART	ALT	ITEM	ITEM	TOTAL	UNIT	DESCRIPTION	SHEET NUMBER
8	9	10	11	12	01/MPO	(X)	ITEM	EXT				
											ROADWAY	
			186				202	11001		LS	STRUCTURE REMOVED, AS PER PLAN	6
							202	30001	186	SF	WALK REMOVED, AS PER PLAN	6
52	152	115	43		362		203	10001	362	CY	EXCAVATION, AS PER PLAN	6
19	19	19	9		66		203	20001	66	CY	EMBANKMENT, AS PER PLAN	6
52	152	115	43		362		203	98000	362	CY	ROADWAY MISC., 4" CRUSHED LIMESTONE, AS PER PLAN	6
	1	2	6		9		203	98600	9	EACH	ROADWAY, MISC.:BENCH	6
1	1				2		203	98600	4	EACH	ROADWAY, MISC.:DOG WASTE STATION	6
	4				4		203	98600	4	EACH	ROADWAY, MISC.:SWING	6
473	1375	1043	384		3275		204	10000	3,275	SY	SUBGRADE COMPACTION	
11.25	11.25	22.5	241		286		608	13001	286	SF	6" CONCRETE WALK, AS PER PLAN	6
	49	81	96				608	15001	226	SF	8" CONCRETE WALK, AS PER PLAN	6
	1	1			2		680	14000	2	EACH	SPECIAL - PICNIC TABLE AND SLAB	
1	1	2	3		7		680	14550	7	EACH	SPECIAL - TRASH RECEPTACLE	
											LIGHTING	
6	4	4	9	2	25		625	00450	25	EACH	CONNECTION, FUSED PULL APART	
6	4	4	7	2	23		625	10491	23	EACH	LIGHT POLE, CONVENTIONAL, 16', AS PER PLAN	6
24	16	16	28	8	92		625	10615	92	EACH	LIGHT POLE ANCHOR BOLT ON STRUCTURE, AS PER PLAN 24"	6
2088	2380	2604	2144	412	9628		625	23302	9,628	FT	NO. 6 AWG 2400 VOLT DISTRIBUTION CABLE	
590	595	581	571	108	2445		625	23304	2,445	FT	NO. 8 AWG 600 VOLT DISTRIBUTION CABLE	
96	64	64	112	32	368		625	23410	368	FT	NO. 12 AWG POLE AND BRACKET CABLE	
60	40	40	70		210		625	25604	210	FT	CONDUIT, 4", 725.051	
6	4	4	7	2	23		625	27551	23	EACH	LUMINAIRE, DECORATIVE , AS PER PLAN DARK SKY	6
6	4	4	7		21		625	31600	21	EACH	PULL BOX, MISC., 725.12, SIZE 14"x14"x12"	
6	4	4	7		21		625	32000	21	EACH	GROUND ROD	
		1			1		625	34451	1	EACH	CONTROL CENTER CABINET, COMPLETE, AS PER PLAN	6
10	9	15	9	2	45		625	75401	45	EACH	LIGHT POLE REMOVED, AS PER PLAN	6
4	5	4	2		15		625	75501	15	EACH	LIGHT POLE FOUNDATION, REMOVED, AS PER PLAN	6
10	9	15	9	2	45		625	75507	45	EACH	LUMINAIRE, REMOVED, AS PER PLAN	6
		1		1			625	75511	2	EACH	POWER SERVICE REMOVED, AS PER PLAN	6
552	655	1168	580	104	3059		625	75550	3,059	FT	DISTRIBUTION CABLE REMOVED	
											EROSION CONTROL	
5	2	5	5		17		653	10001	17	CY	TOPSOIL FURNISHED AND PLACED, AS PER PLAN	6
25	11	13	25		74		659	10001	74	SY	SEEDING AND MULCHING, AS PER PLAN	
							659	20000	0.02	TON	COMMERCIAL FERTILIZER	
							832	30000	1000	EACH	EROSION CONTROL	
											TRAFFIC CONTROL	
							614	12421		LS	DETOUR SIGNING, AS PER PLAN	
											INCIDENTALS	
							614	11001		LS	MAINTAINING TRAFFIC, AS PER PLAN	
							623	10000		LS	CONSTRUCTION LAYOUT STAKES AND SURVEYING	
							624	10000		LS	MOBILIZATION	

REVISION DESCRIPTION			
DATE			



MOT-MCD SOUTH RIVER WALK IMPROVEMENTS
 PID:110272
 GENERAL SUMMARY

DATE:
 JANUARY 2026
 DRAWN BY:
 JDK
 MCD NUMBER:
 46041
 SHEET:
 7 of 18