

P:\89130\Design\Roadway\Sheets\89130\_GG001.dgn Sheet 5/20/2020 3:40:35 PM mlJtes

SHEET NUM.											PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
OFFICE		9	20	21		66		68		70	01/NHS/OT	02/NHS/OT						
			LS									LS	201	11001	LS		CLEARING AND GRUBBING, AS PER PLAN	20
						4						4	202	20010	4	EACH	HEADWALL REMOVED	
994												994	202	23000	994	SY	PAVEMENT REMOVED	
15,532												15,532	202	23010	15,532	SY	PAVEMENT REMOVED, ASPHALT	
						646						646	202	30700	646	FT	CONCRETE BARRIER REMOVED	
						321						321	202	32000	321	FT	CURB REMOVED	
						2						2	202	32501	2	FT	CURB AND GUTTER REMOVED, AS PER PLAN	82
						1,233						1,233	202	35100	1,233	FT	PIPE REMOVED, 24" AND UNDER	
						9,916					6,891	3,025	202	38000	9,916	FT	GUARDRAIL REMOVED	
						9,437						9,437	202	38300	9,437	FT	GUARDRAIL REMOVED, BARRIER DESIGN	
						7					6	1	202	42001	7	EACH	ANCHOR ASSEMBLY REMOVED, TYPE A, AS PER PLAN	20
						4					3	1	202	42010	4	EACH	ANCHOR ASSEMBLY REMOVED, TYPE E	
						17					12	5	202	42040	17	EACH	ANCHOR ASSEMBLY REMOVED, TYPE T	
						3					1	2	202	42050	3	EACH	ANCHOR ASSEMBLY REMOVED, TYPE B	
						17					9	8	202	47000	17	EACH	BRIDGE TERMINAL ASSEMBLY REMOVED	
						6						6	202	47800	6	EACH	IMPACT ATTENUATOR REMOVED	
						2						2	202	58000	2	EACH	MANHOLE REMOVED	
						1						1	202	58001	1	EACH	MANHOLE REMOVED, AS PER PLAN	21
						11						11	202	58100	11	EACH	CATCH BASIN REMOVED	
						1						1	202	58500	1	EACH	CATCH BASIN ABANDONED	
			6									6	202	67000	6	EACH	REGULATED UNDERGROUND STORAGE TANK REMOVED	
						80						80	202	75000	80	FT	FENCE REMOVED	
			LS									LS	202	98000	LS		REMOVAL MISC.: TRAFFIC MONITORING EQUIPMENT	21
										14,065		14,065	203	10000	14,065	CY	EXCAVATION	
										518		518	203	20000	518	CY	EMBANKMENT	
												18	204	45000	18	HOUR	PROOF ROLLING	
												1,637	206	10500	1,637	TON	CEMENT	
												54,229	206	11000	54,229	SY	CURING COAT	
												54,229	206	15020	54,229	SY	CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP	
												LS	206	30000	LS		MIXTURE DESIGN FOR CHEMICALLY STABILIZED SOILS	
								7,187.5			6,075	1,112.5	606	15050	7,187.5	FT	GUARDRAIL, TYPE MGS	
								1,112.5				1,112.5	606	15100	1,112.5	FT	GUARDRAIL, TYPE MGS WITH LONG POSTS	
								175				175	606	15550	175	FT	GUARDRAIL, BARRIER DESIGN, TYPE MGS	
								16			13	3	606	26150	16	EACH	ANCHOR ASSEMBLY, MGS TYPE E, MASH 2016	
								17			15	2	606	26550	17	EACH	ANCHOR ASSEMBLY, MGS TYPE T	
								3				3	606	35002	3	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1	
								4			1	3	606	35102	4	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 2	
								3				3	606	60028	3	EACH	IMPACT ATTENUATOR, TYPE 2 (BIDIRECTIONAL), 60 MPH, 24" WIDE	
								80				80	607	23000	80	FT	FENCE, TYPE CLT	
								9,275				9,275	622	10140	9,275	FT	CONCRETE BARRIER, SINGLE SLOPE, TYPE C1	
								712				712	622	10160	712	FT	CONCRETE BARRIER, SINGLE SLOPE, TYPE D	
								1				1	622	10200	1	EACH	BARRIER TRANSITION	
								1				1	622	24850	1	EACH	CONCRETE BARRIER END SECTION, TYPE B1	
								1				1	622	24860	1	EACH	CONCRETE BARRIER END SECTION, TYPE C1	
								6				6	622	25000	6	EACH	CONCRETE BARRIER END SECTION, TYPE D	
								52				52	622	25014	52	EACH	CONCRETE BARRIER, END ANCHORAGE, REINFORCED, TYPE C1	
												7	623	38500	7	EACH	MONUMENT ASSEMBLY	

CALCULATED	KRM	CHECKED	MLL
<b>GENERAL SUMMARY</b>			
<b>MOT-35-18.57</b>			
<b>GRE-35-0.00</b>			
60			
310			

P:\89130\Design\Roadway\Sheets\89130\_CS004.dgn Sheet 5/20/2020 3:40:25 PM mlutes

SHEET NO.	REFERENCE NO.	STATION		SIDE	203		659	601		670									
		FROM	TO		EXCAVATION CY	EMBANKMENT CY	SEEDING AND MULCHING SY	TIED CONCRETE BLOCK MAT, TYPE 2 SY	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER CY	DITCH EROSION PROTECTION SY									
<b>USR 35 - EARTHWORK &amp; EROSION CONTROL</b>																			
90-226		556+40.00	4+26.67	RT/LT	16510	518	2496												
82		601+41.00	604+35.50	LT				27											
80	EC-1	584+00.00		RT					1.33										
82	EC-2	599+50.00		RT					1.11										
83	EC-3	616+00.00		LT					1.33										
85	EC-4	643+85.00		LT					1.33										
87	EC-5	667+70.00		LT					1.33										
89	EC-6	684+24.25		RT					1.33										
89	EC-7	686+26.00	687+76.00	RT/LT						125									
90-110		DEDUCT PAVEMENT REMOVED, ASPHALT STA. 556+40.00 TO STA. 575+00.00 (EB INSIDE SHOULDER)		RT	-303														
110-226		DEDUCT PAVEMENT REMOVED, ASPHALT STA. 575+00.00 TO STA. 689+00.00 (EB & WB INSIDE / OUTSIDE SHOULDER)		RT/LT	-1906														
163-167		DEDUCT PAVEMENT REMOVED STA. 629+70.00 TO STA. 634+90.00 (FULL DEPTH)		RT	-236														
<b>TOTALS CARRIED TO SHEET 21</b>							2496												
<b>TOTALS CARRIED TO GENERAL SUMMARY</b>					14065	518			27	7.76		125							

**EARTHWORK & EROSION CONTROL SUBSUMMARY**

**MOT -35 -18 .57  
GRE -35 -0.00**

CALCULATED  
KRM  
CHECKED  
MLL

70  
310