

J:\144373_CHE_MarionSW\7.0_Production\7.03_Design\04_Civil\Sheets\144373_SUB_SUMMARY.dwg_01 - May - 24 8:40 AM

ROADWAY SUBSUMMARY

REF.	SHEET	STATION TO STATION		SIDE	202		202		204		608	
					PAVEMENT REMOVED	WALK REMOVED	STEPS REMOVED	STEPS REMOVED, AS PER PLAN	SUBGRADE COMPACTION	4" CONCRETE WALK	CONCRETE STEPS, TYPE A	
					S.Y.	S.F.	FT.	LUMP	S.Y.	S.F.	FT.	
R-1	7	14+78.61	19+00	RT.		2072		222		1994		
R-2	8	20+17	NA	RT.	39							
R-3	8	21+13	NA	RT.			28					28
R-4	8	19+00	23+50	RT.		1844		1	178		1600	
R-5	8	21+85	NA	RT.			28					28
R-6	9	23+93	NA	RT.	54							
R-7	9	23+50	28+00	RT.		1985			163		1465	
R-8	9	27+45	NA	RT.			20					20
R-9	10	29+58	29+77	RT.			100					100
R-10	10	30+17	NA	RT.	30							
R-11	10	28+00	32+50	RT.		2213			178		1598	
R-12	11	32+50	37+00	RT.		1941			226		2029	
R-13	11	35+68	NA	RT.			28					28
R-14	11	36+37	NA	RT.			15					15
R-15	12	37+00	38+94.77	RT.		945			119		1066	
R-16	12	38+12	NA	RT.			11					11
R-17	12	38+12	NA	RT.			11					
R-18	12	38+12	NA	RT.			27					27
TOTALS CARRIED TO GENERAL SUMMARY					123	11000	268	1	1086		9752	257

PAVEMENT SUBSUMMARY

REF.	SHEET	STATION TO STATION		SIDE	204		452	
					SUBGRADE COMPACTION	7" NON-REINFORCED CONCRETE PAVEMENT, CLASS OC1 TP		
					S.Y.	S.Y.		
P-1	8	20+17	NA	RT.	39		39	
P-2	9	23+93	NA	RT.	54		54	
P-3	10	30+17	NA	RT.	30		30	
TOTALS CARRIED TO GENERAL SUMMARY						123	123	

EARTHWORK TABLE

SHEET NO.	EARTHWORK AND SEEDING SUMMARY		
	ITEM 659-SEEDING AND MULCHING	ITEM 203-EXCAVATION	ITEM 203-EMBANKMENT
	C.Y.	C.Y.	S.Y.
13	50	0	4
14	72	2	3
15	111	6	4
16	52	0	8
17	89	0	7
18	111	0	11
19	55	1	4
20	50	5	0
21	77	5	2
22	84	2	12
23	86	8	7
24	36	1	2
25	52	2	2
26	177	15	0
27	86	0	8
28	175	0	14
29	167	4	9
TOTALS	1530	51	97

THE CONTRACTOR SHOULD ANTICIPATE PERFORMING/PLACING SEEDING AND MULCHING PER ODOT ITEM 659 AND ODOT ITEM 201 CLEARING AND GRUBBING AT THE LOCATIONS WHERE THE TREES AND STUMPS ARE MARKED FOR REMOVAL PER CMS ITEM 201.03A.

DESIGN AGENCY
 IBI GROUP
 11000 Village Street - Suite 104
 Canton OH 44718 USA
 tel 330 491 9000 fax 330 491 9001
 ibigroup.com



CALCULATED
 JAG
 CHECKED
 MSM

SUBSUMMARY

MRG - CHESTERHILL
 STREETScape PHASE 1

J:\144373_CHE_MarionSW\7.0_Production\7.03_Design\04_Civil\Sheets\144373_GENERAL SUMMARY.dwg 01-May-24 8:40 AM

SHEET NUM.										PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
4	5	35								01/ENH/28		EXT				
										LS	201	11000	LS		ROADWAY	
										6	201	21800	6	EACH	CLEARING AND GRUBBING	
										2	201	23000	2	EACH	TREE REMOVED, 18"	
										10	201	24800	10	EACH	TREE REMOVED, 30"	
										2	201	26500	2	EACH	TREE REMOVED, 48"	
										4	201	26520	4	EACH	STUMP REMOVED, 18"	
										123	202	23000	123	SY	STUMP REMOVED, 48"	
										11,000	202	30000	11,000	SF	PAVEMENT REMOVED	
										268	202	30200	268	FT	WALK REMOVED	
										200	202	30204	200	LS	STEPS REMOVED	
										200	202	32000	200	FT	STEPS REMOVED, AS PER PLAN	4
										200	202	32000	200	FT	CURB REMOVED	4
										51	203	10000	51	CY		
										97	203	20000	97	CY	EXCAVATION	
										1,209	204	10000	1,209	SY	EMBANKMENT	
										9,752	608	10000	9,752	SF	SUBGRADE COMPACTION	
										257	608	40000	257	FT	4" CONCRETE WALK	
										123	452	11010	123	SY	CONCRETE STEPS, TYPE A	
										200	609	26000	200	FT	PAVEMENT	
										1,530	659	00500	1,530	SY	7" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P	
										0.21	659	14000	0.21	SY	CURB, TYPE 6	
										8	659	20000	8	TON	EROSION CONTROL	
										8	659	35000	8	MGAL	SEEDING AND MULCHING, CLASS 1	
										10,000	832	30000	10,000	EACH	REPAIR SEEDING AND MULCHING	
										24	625	00450	24	EACH	COMMERCIAL FERTILIZER	
										8	625	10481	8	EACH	WATER	
										8	625	14001	8	EACH	EROSION CONTROL	
										3,500	625	22990	3,500	FT	LIGHTING	
										8	625	00460	8	EACH	CONNECTION, FUSED PULL APART	
										8	625	10481	8	EACH	CONNECTION, UNFUSED PULL APART	
										8	625	14001	8	EACH	LIGHT POLE, AESTHETIC, AS PER PLAN	33
										3,500	625	22990	3,500	FT	LIGHT POLE FOUNDATION, 24" X 6' DEEP, AS PER PLAN	33
										960	625	23400	960	FT	NO. 6 AWG 600 VOLT DISTRIBUTION CABLE	
										800	625	25400	800	FT	NO. 10 AWG POLE AND BRACKET CABLE	
										8	625	27401	8	EACH	CONDUIT, 2", 725.04	
										794	625	29001	794	FT	LUMINAIRE, POST TOP, AS PER PLAN	33
										4	625	30700	4	EACH	TRENCH, AS PER PLAN	33
										13	625	32000	13	EACH	PULL BOX, 725.08, 18"	
										1	625	34001	1	EACH	GROUND ROD	
										794	625	36010	794	FT	POWER SERVICE, AS PER PLAN	33
										LS	614	11000	LS		UNDERGROUND WARNING/MARKING TAPE	
										LS	623	10000	LS		INCIDENTALS	
										LS	624	10000	LS		MAINTAINING TRAFFIC	
															CONSTRUCTION LAYOUT STAKES AND SURVEYING	
															MOBILIZATION	



DESIGN AGENCY
 IBI GROUP
 4500 Village Street - Suite 104
 Canton OH 44718 USA
 tel: 330.491.9000 fax: 330.491.9001
 ibigroup.com

CALCULATED
 JAG
 CHECKED
 MSM

GENERAL SUMMARY

MRG - CHESTERHILL
 STREETScape PHASE 1