

I:\Project\data\05580\Design\Roadway\Sheets\05580_TS001.dgn Sheet 11/30/2020 9:32:42 AM ikohli

SIGN QUANTITIES															
REF NO.	ROUTE	STATION	SIDE	CODE	SIZE (INCHES)	630	630	630	630		630	630	630	630	
						GROUND MOUNTED SUPPORT, NO. 3 POST FT	STREET NAME SIGN SUPPORT, NO. 3 POST FT	SIGN POST REFLECTOR EACH	SIGN, FLAT SHEET SF		REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL EACH	REMOVAL OF GROUND MOUNTED SIGN AND REECTION EACH	REMOVAL OF GROUND MOUNTED SIGN AND STORAGE EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND STORAGE EACH
S11	SR 114	79+19	LT	R1-1	30"x30"	12		1	6.25		1		2		
S12	SR 114	79+48	RT	R1-1	30"x30"	12		1	6.25		1		2		
S13	SR 114	79+52	RT				11				2		1		
S21	SR 114	157+55	RT	I-H2d	48"x24"	24			8.00		1		2		
S22	SR 114	158+31	LT	R1-1	30"x30"	12		1	6.25		1		2		
S23	SR 114	158+61	RT	R1-1	30"x30"	12		1	6.25		1		2		
S24	SR 114	158+71	RT				12				2		1		
				D10-H8	12"x12"				1.00						
				D10-H8	12"x12"				1.00						
S31	SR 114	474+67	LT	M1-5-3 M3-4	30"x24" 30"x15"	12			5.00 3.12		1		2		
S32	SR 114	475+08	RT	D10-H8 D10-H8	12"x12" 12"x12"	9			1.00 1.00		1		1		
S33	SR 114	476+15	LT	R1-1	30"x30"	12		1	6.25		1		2		
S34	SR 114	476+54	LT									2		2	
S35	SR 114	476+60	LT				11				2		1		
S36	SR 114	476+49	RT	R1-1	30"x30"	12		1	6.25		1		2		
S37	CR 87	25+83	LT								1		2		
TOTALS CARRIED TO GENERAL SUMMARY						117	34	6	57.7		10	6	2	22	2

PAVEMENT MARKING QUANTITIES							
REF NO.	ROUTE	STATION		614	642	642	642
				WORK ZONE CENTER LINE, CLASS 1 MILE	EDGE LINE, 6", TYPE 1 (WHITE) MILE	CENTER LINE, TYPE 1 (DASHED) MILE	CENTER LINE, TYPE 1 (SOLID / DASHED) MILE
		FROM	TO				
P11	SR 114	78+50	79+07	0.011	0.022	0.011	
P12	SR 114	79+55	80+00	0.009	0.018	0.009	
P21	SR 114	157+25	158+23	0.019	0.038	0.019	
P22	SR 114	158+74	159+00	0.005	0.010	0.005	
P31	SR 114	474+25	476+08	0.035	0.070	0.035	
P32	SR 114	476+60	477+25	0.012	0.024	0.012	
P33	CR 87	26+92	27+75	0.016			0.016
TOTALS TO GENERAL SUMMARY				0.11	0.18	0.09	0.02

CROSS REFERENCES	
SHEET NO.	DESCRIPTION
52	SIGN AND PAVEMENT MARKING PLAN

TRAFFIC CONTROL SUBSUMMARY

**PAU-114-1.50
3.00 / 5.01 / 9.02**

CALCULATED
RDM
CHECKED
IMK