

REVIEW OF DRAINAGE FACILITIES

BEFORE ANY WORK IS STARTED ON THE PROJECT AND AGAIN BEFORE FINAL ACCEPTANCE BY THE STATE, REPRESENTATIVES OF THE STATE AND THE CONTRACTOR, ALONG WITH LOCAL REPRESENTATIVES, SHALL MAKE AN INSPECTION OF ALL EXISTING SEWERS WHICH ARE TO REMAIN IN SERVICE AND WHICH MAY BE AFFECTED BY THE WORK. THE CONDITION OF THE EXISTING CONDUITS AND THEIR APPURTENANCE SHALL BE DETERMINED FROM FIELD OBSERVATIONS. RECORDS OF THE INSPECTION SHALL BE KEPT IN WRITING BY THE STATE.

ALL NEW CONDUITS, INLETS, CATCH BASINS, AND MANHOLES CONSTRUCTED AS A PART OF THE PROJECT SHALL BE FREE OF ALL FOREIGN MATTER AND IN A CLEAN CONDITION BEFORE THE PROJECT WILL BE ACCEPTED BY THE STATE.

ALL EXISTING SEWERS INSPECTED INITIALLY BY THE ABOVE MENTIONED PARTIES SHALL BE MAINTAINED AND LEFT IN A CONDITION REASONABLY COMPARABLE TO THAT DETERMINED BY THE ORIGINAL INSPECTION. ANY CHANGE IN THE CONDITION RESULTING FROM THE CONTRACTOR'S OPERATIONS SHALL BE CORRECTED BY THE CONTRACTOR TO THE SATISFACTION OF THE ENGINEER.

PAYMENT FOR ALL OPERATIONS DESCRIBED ABOVE SHALL BE INCLUDED IN THE CONTRACT PRICE FOR THE PERTINENT 611 CONDUIT ITEMS.

CROSSINGS AND CONNECTIONS TO EXISTING PIPES AND UTILITIES

WHERE PLANS PROVIDE FOR A PROPOSED CONDUIT TO BE CONNECTED TO, OR CROSS OVER OR UNDER AN EXISTING SEWER OR UNDERGROUND UTILITY, THE CONTRACTOR SHALL LOCATE THE EXISTING PIPES OR UTILITIES BOTH AS TO LINE AND GRADE BEFORE STARTING TO LAY THE PROPOSED CONDUIT.

IF IT IS DETERMINED THAT THE ELEVATION OF THE EXISTING CONDUIT, OR EXISTING APPURTENANCE TO BE CONNECTED, DIFFERS FROM THE PLAN ELEVATION OR RESULTS IN A CHANGE IN THE PLAN CONDUIT SLOPE, THE ENGINEER SHALL BE NOTIFIED BEFORE STARTING CONSTRUCTION OF ANY PORTION OF THE PROPOSED CONDUIT WHICH WILL BE AFFECTED BY THE VARIANCE IN THE EXISTING ELEVATIONS.

IF IT IS DETERMINED THAT THE PROPOSED CONDUIT WILL INTERSECT AN EXISTING SEWER OR UNDERGROUND UTILITY IF CONSTRUCTED AS SHOWN ON THE PLAN, THE ENGINEER SHALL BE NOTIFIED BEFORE STARTING CONSTRUCTION OF ANY PORTION OF THE PROPOSED CONDUIT WHICH WOULD BE AFFECTED BY THE INTERFERENCE WITH AN EXISTING FACILITY.

PAYMENT FOR ALL THE OPERATIONS DESCRIBED ABOVE SHALL BE INCLUDED IN THE CONTRACT PRICE FOR THE PERTINENT 611 CONDUIT ITEM.

MANHOLES, CATCH BASINS AND INLETS REMOVED OR ABANDONED

ALL CASTINGS SHALL BE CAREFULLY REMOVED AND STORED WITHIN THE RIGHT OF WAY FOR SALVAGE BY STATE OF OHIO FORCES.

PAYMENT FOR ALL OF THE ABOVE SHALL BE INCLUDED IN THE CONTRACT PRICE FOR THE PERTINENT 202 ITEM.

ITEM SPECIAL - PIPE CLEANOUT

THIS WORK SHALL CONSIST OF REMOVING SEDIMENT AND DEBRIS FROM THE EXISTING DRAINAGE CONDUITS SPECIFIED IN THE PLANS. ALL MATERIAL REMOVED SHALL BE DISPOSED OF AS PER 105.16 AND 105.17. ALL SEWERS SHALL BE CLEANED OUT TO THE SATISFACTION OF THE ENGINEER.

CLEANOUT OF THE PIPE SHALL BE PAID FOR AT THE UNIT PRICE BID FOR ITEM SPECIAL - PIPE CLEANOUT. THIS PRICE SHALL INCLUDE THE COST FOR MATERIAL, EQUIPMENT, LABOR, AND ALL INCIDENTALS REQUIRED TO COMPLETE THE CLEANOUT.

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY FOR THE ABOVE NOTED WORK:

SPECIAL, PIPE CLEANOUT, 24" AND UNDER 397 FT.

POST CONSTRUCTION STORM WATER TREATMENT

THIS PLAN UTILIZES STRUCTURAL BEST MANAGEMENT PRACTICES (BMP'S) FOR POST CONSTRUCTION STORM WATER TREATMENT.

MANUFACTURED WATER QUALITY STRUCTURE

THIS PLAN UTILIZES MANUFACTURED WATER QUALITY STRUCTURES FOR WATER QUALITY TREATMENT. AREAS HAVE BEEN SHOWN IN THE PLANS FOR PLACEMENT OF AN OFF-LINE SYSTEM. PAYMENT FOR THESE DEVICES SHALL BE MADE AT THE CONTRACT UNIT PRICE FOR ITEM 895, MANUFACTURED WATER QUALITY STRUCTURE, TYPE 4.

THE WESTBOUND WQ UNIT WILL BE INSTALLED ADJACENT TO A 108" BASE I.D. NO-3 MH WITH A 12" DIVERSION WEIR. THIS MANHOLE SHALL BE PAID FOR AT THE UNIT BID PRICE FOR MANHOLE, NO.3.

ENDANGERED SPECIES HABITAT - INDIANA BAT/NORTHERN LONG-EARED BAT

THE PROJECT IS LOCATED WITHIN THE KNOWN HABITAT RANGES OF THE FEDERALLY LISTED AND PROTECTED INDIANA BAT AND NORTHERN LONG-EARED BAT. NO TREES SHALL BE REMOVED TO CONSTRUCT THE PROJECT FROM APRIL 1 THROUGH SEPTEMBER 30 ALL NECESSARY TREE REMOVAL SHALL OCCUR FROM OCTOBER 1 THROUGH MARCH 31. THIS REQUIREMENT IS NECESSARY TO AVOID AND MINIMIZE IMPACTS TO THESE SPECIES AS REQUIRED BY THE ENDANGERED SPECIES ACT. FOR THE PURPOSES OF THIS NOTE, A TREE IS DEFINED AS A LIVE, DYING, OR DEAD WOODY PLANT, WITH A TRUNK THREE INCHES OR GREATER IN DIAMETER AT A HEIGHT OF 4.5 FEET ABOVE THE GROUND SURFACE, AND WITH A MINIMUM HEIGHT OF 13 FEET.

STREAM 1 AVOIDANCE

UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR IMPACT STREAM 1 AS INDICATED IN THE PLAN. NO EXCAVATION, GRADING OR FILLING OPERATIONS SHALL BE PERFORMED IN STREAM 1. A QUANTITY OF ITEM 832 CONSTRUCTION FENCE AND A QUANTITY OF ITEM 832 PERIMETER FILTER FABRIC FENCE HAVE BEEN INCLUDED IN THE GENERAL SUMMARY. THE CONSTRUCTION FENCE AND PERIMETER FILTER FABRIC FENCE SHALL BE INSTALLED ALONG THE PROPOSED CONSTRUCTION LIMITS AT STREAM 1 LOCATIONS BY THE CONTRACTOR PRIOR TO THE START OF ANY CONSTRUCTION ACTIVITIES WITHIN THE LIMITS AND ADJACENT AREA, INCLUDING ANY NECESSARY CLEARING AND GRUBBING ACTIVITIES. THE CONSTRUCTION FENCE AND PERIMETER FILTER FABRIC FENCE SHALL BE MAINTAINED BY THE CONTRACTOR THROUGHOUT PROJECT CONSTRUCTION AND SHALL BE REMOVED BY THE CONTRACTOR UPON PROJECT COMPLETION. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR STORE EQUIPMENT AND/OR MATERIALS IN ANY STREAMS.

PAYMENT FOR ITEM 832 CONSTRUCTION FENCE AND ITEM 832 PERIMETER FILTER FABRIC FENCE WILL BE MADE UNDER ITEM 832, EROSION CONTROL.

STREAM 2 IMPACT (EASTBOUND REST AREA) AND AVOIDANCE (WESTBOUND REST AREA)

UNDER THE DIRECTION OF THE PROJECT ENGINEER, THE CONTRACTOR MAY IMPACT/PLACE TEMPORARY AND PERMANENT FILLS IN STREAM 2 AT THE EASTBOUND REST AREA AS INDICATED IN THE PLAN. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR IMPACT STREAM 2 AT THE WESTBOUND REST AREA AS INDICATED IN THE PLAN. THE CONTRACTOR SHALL CAREFULLY REVIEW AND COMPLY WITH ALL WATERWAY PERMIT CONDITIONS PROVIDED AS SPECIAL PROVISIONS.

PAYMENT FOR ITEM 832 CONSTRUCTION FENCE AND ITEM 832 PERIMETER FILTER FABRIC FENCE WILL BE MADE UNDER ITEM 832, EROSION CONTROL. THE CONSTRUCTION FENCE AND PERIMETER FILTER FABRIC FENCE SHALL BE INSTALLED ALONG THE PROPOSED CONSTRUCTION LIMITS AT THE STREAM 2 LOCATIONS BY THE CONTRACTOR PRIOR TO THE START OF ANY CONSTRUCTION ACTIVITIES WITHIN THE LIMITS AND ADJACENT AREA, INCLUDING ANY NECESSARY CLEARING AND GRUBBING ACTIVITIES. THE CONSTRUCTION FENCE AND PERIMETER FILTER FABRIC FENCE SHALL BE MAINTAINED BY THE CONTRACTOR THROUGHOUT PROJECT CONSTRUCTION AND SHALL BE REMOVED BY THE CONTRACTOR UPON PROJECT COMPLETION. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR STORE EQUIPMENT AND/OR MATERIALS IN ANY STREAMS.

TEMPORARILY IMPACTED AREAS OF STREAM 2 SHALL BE RESTORED TO NEAR NATURAL PRE-CONSTRUCTION STREAM BOTTOM AND BANK CONDITIONS. ALL TEMPORARY FILL MATERIALS SHALL BE DISPOSED OF IN ACCORDANCE WITH 105.16 AND 105.17 OF THE CMS WITH APPROVAL OF THE ENGINEER. TEMPORARILY IMPACTED STREAM 2 CHANNEL AREAS SHALL BE RESTORED TO THE SATISFACTION OF THE ENGINEER.

WETLANDS AVOIDANCE

WETLANDS ARE PRESENT IN PROXIMITY OF THE OF THE PROJECT CONSTRUCTION LIMITS. BEST MANAGEMENT PRACTICES SHALL BE EMPLOYED TO AVOID IMPACT TO WETLANDS AS INDICATED IN THE PLAN. A QUANTITY OF ITEM 832 CONSTRUCTION FENCE AND A QUANTITY OF ITEM 832 PERIMETER FILTER FABRIC FENCE HAVE BEEN INCLUDED IN THE GENERAL SUMMARY. THE CONSTRUCTION FENCE AND PERIMETER FILTER FABRIC FENCE SHALL BE INSTALLED ALONG THE PROPOSED CONSTRUCTION LIMITS AT THE WETLAND B LOCATION BY THE CONTRACTOR PRIOR TO THE START OF ANY CONSTRUCTION ACTIVITIES WITHIN THE LIMITS AND ADJACENT AREA, INCLUDING ANY NECESSARY CLEARING AND GRUBBING ACTIVITIES. THE CONSTRUCTION FENCE AND PERIMETER FILTER FABRIC FENCE SHALL BE MAINTAINED BY THE CONTRACTOR THROUGHOUT PROJECT CONSTRUCTION AND SHALL BE REMOVED BY THE CONTRACTOR UPON PROJECT COMPLETION.

THE CONTRACTOR SHALL TAKE PRECAUTIONS NECESSARY TO PROTECT WETLAND A WHICH IS LOCATED WELL SOUTH AND DOWN GRADIENT OF THE PROJECT CONSTRUCTION LIMITS. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR IMPACT WETLAND AREAS BEYOND THE CONSTRUCTION LIMITS AS SHOWN IN THE PLAN AND APPROVED BY THE PROJECT ENGINEER. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR STORE EQUIPMENT AND/OR MATERIALS WITHIN WETLAND AREAS.

PAYMENT FOR ITEM 832 CONSTRUCTION FENCE AND ITEM 832 PERIMETER FILTER FABRIC FENCE WILL BE MADE UNDER ITEM 832, EROSION CONTROL.

J:\20190025\000T\04-10_POR-76_Rest Area (PID 112697)\POR\112697_POR-76_RESTAREA\Design\Roadway\Sheets\112697_GND01.dwg 05-Jan-21 2:00 PM

CALCULATED
BS
CHECKED
JJC

GENERAL NOTES

POR-76-15.27