SHEET NUMBER 3	4		9			12		15	16		PARTICIPATION 01/MPO/ 05/MOGA	02/MPO/ 05/POCE	ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
																	ROADWAY	
			2575								2575		202	30000	2575	SF	WALK REMOVED	3
			201								201		202	32000	201	FT	CURB REOVED	
			1953								1953		608	10000	1953	SF	4" CONCRETE WALK	
			622								622		608	52000	622	FT	CURB RAMP	
			80								80		608	53020	80	SF	DETECTABLE WARNING	
			201								201		609	26000	201	FT	CURB, TYPE 6	
600											600		609	98000	600	FT	CURB MISC.: CURB REMOVED AND REPLACED	3
	LS										LS	LS	SPECIAL	690E98400	LS		PRECONSTRUCTION VIDEO TAPING	
																	EROSION CONTROL	
5000											4575	425	832	30001	5000	EACH	EROSION CONTROL, AS PER PLAN	3
																	DRAINAGE	
15											14	1	611	98630	15	EACH	CATCH BASIN ADJUSTED TO GRADE	3
26											24	2	611	99655	26	EACH	MANHOLE ADJUSTED TO GRADE, AS PER PLAN	3
7500											6863	637	611	99820	7500	LB	SPECIAL - MISCELLANEOUS METAL	
2											1	1	623	39501	2	EACH	MONUMENT ASSEMBLY BOX ADJUSTED TO GRADE, AS PER PLAN	3
17											16	1	638	10801	17	EACH	VALVE BOX ADJUSTED TO GRADE, AS PER PLAN	3
																	PAVEMENT	
	12										11	1	202	23500	12	SY	WEARING COURSE REMOVED	
	148										135	13	203	10000	148	CY	EXCAVATION (FOR PAVEMENT REPAIR)	
	888										813	75	204	10000	888	SY	SUBGRADE COMPACTION (FOR PAVEMENT REPAIR)	
	444										406	38	251	01000	444	SY	PARTIAL DEPTH PAVEMENT REPAIR (449)	
	888										813	75	253	01000	888	SY	PAVEMENT REPAIR	
						14813					13351	1462	254	01000	14813	SY	PAVEMENT PLANNING, ASPHALT CONCRETE (T=3")	
	148										135	13	304	20000	148	CY	AGGREGATE BASE (FOR PAVEMENT REPAIR)	4
	20					2074					1889	205	407	20000	2094	GAL	NON-TRACKING TACK COAT	
	6					515					477	44	441	70101	521	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22, AS PER PLAN	4
						721					650	71	441	70300	721	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (449)	
																	TRAFFIC CONTROL	
								0.92			0.71	0.21	644	00104	0.92	MILE	EDGE LINE, 6"	
								0.11			0.11		644	00204	0.11	MILE	LANE LINE, 6"	
								0.89			0.78	0.11	644	00300	0.89	MILE	CENTER LINE	
								663			663		644	00400	663	FT	CHANNELIZING LANE, 8"	
								110			110		644	00500	110	FT	STOP LINE	
								547			547		644	00620	547	FT	CROSSWALK LINE, 12"	
									2		2		644	01000	2	EACH	RAILROAD SYMBOL MARKING	
									11		11		644	01300	11	EACH	LANE ARROW	
									3		3		644	01400	3	EACH	WORD ON PAVEMENT, 72"	
								587			587		644	01510	587	FT	DOTTED LINE, 6"	

CALCULATED

CHECKED MDG

GENERAL SUMMARY

MOGADORE ROAD RESURFACING

O:\2021\2021049\05 - Mogadore Road Resurfacing\400-Engineering\Roadway\Sheets\202104905_GG001.dwg 05-Apr-23 10:55 AM