

LOCATION 1 - ESTIMATED QUANTITIES (03/STR)									
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUT.	PIERS	SUPER.	GEN.	SEE SHEET
202	11203	LS		PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	LS				P.27
202	22900	224	SY	APPROACH SLAB REMOVED				224	
203	20000	10	CY	EMBANKMENT				10	
503	11100	LS		COFFERDAMS AND EXCAVATION BRACING				LS	
203	35110	10	CY	GRANULAR MATERIAL, TYPE B				10	
503	21100	66	CY	UNCLASSIFIED EXCAVATION	66				
509	10000	428	LB	EPOXY COATED STEEL REINFORCEMENT	428				
510	10000	64	EACH	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT	64				
511	45710	6	CY	CLASS QC1 CONCRETE, ABUTMENT	6				
512	10100	402	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	22	380			
512	33000	10	SY	TYPE 2 WATERPROOFING	10				
512	74000	380	SY	REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACES		380			
516	13900	11	SF	2" PREFORMED EXPANSION JOINT FILLER	11				
516	14014	86	FT	INTEGRAL ABUTMENT EXPANSION JOINT SEAL	86				
518	21200	52	CY	POROUS BACKFILL WITH GEOTEXTILE FABRIC	52				
518	40000	117	FT	6" PERFORATED CORRUGATED PLASTIC PIPE	117				
518	40010	30	FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS	30				
519	11101	135	SF	PATCHING CONCRETE STRUCTURE, AS PER PLAN	135				P.27
526	25000	224	SY	REINFORCED CONCRETE APPROACH SLABS (T=15")				224	
526	90010	86	FT	TYPE A INSTALLATION				86	
SPECIAL	53000800	80	SY	STRUCTURES: CONCRETE SPALL REMOVAL WITH ZINC RICH PRIMER APPLIED			80		P.27

CALC:	SBD	DATE:	9/24/2026
CHECKED:	RC	DATE:	9/24/2026

STRUCTURE DETAILS - QUANTITIES
LOCATION 1 - POR-14-26.501
SR 14 OVER BERLIN LAKE

SFN

6701000

DESIGN AGENCY

DESIGNER

SBD

CHECKER

RC

REVIEWER

TJP 08/14/26

PROJECT ID

116747

SUBSET

4

TOTAL

11

SHEET

P.30

TOTAL

37