

SHEET NUMBER											PART.			ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
5			12	13	14		16	17	18	19	01/S5K/EAT	02/SAE/EAT	03/NFP		EXT	TOTAL			
								2,804			2,804			605	06000	2,804	FT	4" BASE PIPE UNDERDRAINS	
								270			270			611	00410	270	FT	4" CONDUIT, TYPE F FOR UNDERDRAIN OUTLET	
							17				17			611	00900	17	FT	6" CONDUIT, TYPE B	
							1,564				1,564			611	01400	1,564	FT	6" CONDUIT, TYPE E 707.45 (SDR-35)	
							595				595			611	04400	595	FT	12" CONDUIT, TYPE B	
							240				240			611	05900	240	FT	15" CONDUIT, TYPE B	
							348				348			611	97400	348	FT	18" CONDUIT, TYPE B	
							379				379			611	10400	379	FT	24" CONDUIT, TYPE B	
							348				343			611	16400	343	FT	36" CONDUIT, TYPE B	
20											20			611	97400	20	FT	CONDUIT, MISC.:TYPE B FOR DRAINAGE DISCHARGE CONTINUANCE	5
20											20			611	97400	20	FT	CONDUIT, MISC.:TYPE C FOR DRAINAGE DISCHARGE CONTINUANCE	5
											20			611	97400	20	FT	CONDUIT, MISC.:TYPE E FOR DRAINAGE DISCHARGE CONTINUANCE	5
20											20			611	97400	20	FT	CONDUIT, MISC.:TYPE F FOR DRAINAGE DISCHARGE CONTINUANCE	5
							18				18			611	98690	18	EACH	CATCH BASIN, MISC.: CB-1	67
							7				7			611	98690	7	EACH	CATCH BASIN, MISC.: CB-1A	67
							11				11			611	99574	11	EACH	MANHOLE, NO. 3	
							1				1			611	99575	1	EACH	MANHOLE, NO. 3, AS PER PLAN , (ORIFCE)	73
							1				1			611	99582	1	EACH	MANHOLE, NO. 3 WITH 90" BASE I.D. AND 8" WEIR	
1											1			611	99720	1	EACH	INSPECTION WELL	5
							12				12			611	99900	12	EACH	DRAINAGE STRUCTURE, MISC.:CLEAN OUT	68
							1				1			895	10020	1	EACH	MANUFACTURED WATER QUALITY STRUCTURE, TYPE 2	
					716						716			254	01001	716	SY	PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN, 1-1/4"	6
					602						602			301	56000	602	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
			2	5	1,853						1,853	7		304	20000	1,860	CY	AGGREGATE BASE	
			1		896						896	1		407	20000	897	GAL	NON-TRACKING TACK COAT	
			17	161								178		411	10000	178	CY	STABILIZED CRUSHED AGGREGATE	
					276						276			441	70000	276	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22	
					352						352			441	70300	352	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (449)	
			1	1								2		441	70500	2	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), (DRIVEWAYS)	
			1	2								3		441	70700	3	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (449), (DRIVEWAYS)	
			180									180		452	10011	180	SY	6" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P, AS PER PLAN	5
			13									13		452	12011	13	SY	8" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P, AS PER PLAN	5
					3,232						3,232			609	12001	3,232	FT	COMBINATION CURB AND GUTTER, TYPE 2, AS PER PLAN	5, 68
					167						167			609	26001	167	FT	CURB, TYPE 6, AS PER PLAN	5
									42		42			638	01130	42	FT	6" WATER MAIN POLYVINYL CHLORIDE PIPE AND FITTINGS, AWWA C900, DR18	
									825	50	875			638	05300	875	FT	3/4" POLYETHYLENE SERVICE BRANCH	
									1		1			638	07800	1	EACH	6" GATE VALVE AND VALVE BOX	
									3		3			638	09300	3	EACH	6" X 6" TAPPING SLEEVE, VALVE AND VALVE BOX6" WATER MAIN RECONNECTED	
									3		3			638	10200	3	EACH	6" FIRE HYDRANT	
										3	3			638	10480	3	EACH	FIRE HYDRANT REMOVED	
									11		11			638	10800	11	EACH	VALVE BOX ADJUSTED TO GRADE	
									2		2			638	10900	2	EACH	SERVICE BOX ADJUSTED TO GRADE	
									36	2	38			638	11100	38	EACH	METER AND CHAMBER REMOVED AND RESET	
									12		12			638	98000	12	EACH	WATER WORK, MISC.: 6" WATER MAIN RECONNECTED	6, 69
									195		195			638	98600	195	FT	WATER WORK, MISC.: 6" WATER MAIN RELOCATED	6, 69

GENERAL SUMMARY

DESIGN AGENCY



CHOICE ONE ENGINEERING

DESIGNER

BHB

REVIEWER

NNS 06-19-2025

PROJECT ID

118523

SHEET

P.10

TOTAL

79



34

275