


SAN-6-17.66 SLIDE REPAIR

MODEL: Sheet_SurvFI_PAPER SIZE: 34x22 (in.) DATE: 1/10/2025 TIME: 2:10:36 PM USER: GARRETT.BRENKE
 p:\vohodo-pw-bentley.com\shhodo-pw-02\Documents\01 Active Projects\District 02\Sandusky\120384\401-Engineering_TetraTech\Roadway\Sheets\120384_GS002.dgn

SHEET NO.	REF NO.	STATION TO STATION		SIDE	202	202	202	202	202	202	606	606	606	606	606	606	607	609	609	626	
					CURB REMOVED FT	GUARDRAIL REMOVED FOR REUSE FT	ANCHOR ASSEMBLY REMOVED FOR REUSE, TYPE T EACH	ANCHOR ASSEMBLY REMOVED FOR REUSE, TYPE E EACH	BRIDGE TERMINAL ASSEMBLY REMOVED FOR REUSE EACH	FENCE REMOVED FT	GUARDRAIL REBUILT, TYPE MGS FT	GUARDRAIL REBUILT, TYPE MGS, AS PER PLAN, WITH STEEL POSTS FT	ANCHOR ASSEMBLY REBUILT, MGS TYPE E EACH	ANCHOR ASSEMBLY REBUILT, MGS TYPE T EACH	MGS BRIDGE TERMINAL ASSEMBLY REBUILT, TYPE 1 EACH	MGS BRIDGE TERMINAL ASSEMBLY REBUILT, TYPE 2 EACH	FENCE, TYPE 47 FT	COMBINATION CURB AND GUTTER, TYPE 4 FT	COMBINATION CURB AND GUTTER, TYPE 4, AS PER PLAN FT	BARRIER REFLECTOR, TYPE 2, ONE-WAY EACH	
EB U.S. 6																					
21	R-1	32+40.26	TO	32+55.71	RT	16															
21	R-3	33+74.02	TO	34+60.21	RT																
21	F-1	33+74.02	TO	34+60.21	RT											87					
21-23	GR-1	32+23.27	TO	44+00.56	RT		1162.5	1		1			1162.5	1						12	
21, 22	C-1	32+40.26	TO	35+96.00	RT													357			
WB U.S. 6																					
21	R-4	132+40.26	TO	132+54.07	LT	14															
21	GR-2	132+22.98	TO	132+87.98	LT		37.5			1			37.5		1					1	
21-23	GR-3	132+87.98	TO	144+68.77	LT		1125		1			1125		1						12	
21, 22	C-2	132+40.26	TO	135+96.00	LT													356			
EB U.S. 6																					
22, 23	R-6	39+65.95	TO	40+35.15	RT																
22, 23	F-2	39+65.95	TO	40+35.15	RT											70					
22	C-3	35+96.00	TO	36+04.00	RT													392	8		
22	C-4	36+04.00	TO	39+96.00	RT														8		
22, 23	C-5	39+96.00	TO	40+04.00	RT														8		
WB U.S. 6																					
22	C-6	135+96.00	TO	136+04.00	LT													392	8		
22	C-7	136+04.00	TO	139+96.00	LT														8		
22, 23	C-8	139+96.00	TO	140+04.00	LT														8		
EB U.S. 6																					
23	C-9	40+04.00	TO	43+66.00	RT													362	6.5		
23	C-10	43+66.00	TO	43+72.50	RT																
WB U.S. 6																					
23	C-11	140+04.00	TO	144+01.00	LT													397	6.5		
23	C-12	144+01.00	TO	144+07.50	LT																
TOTALS CARRIED TO GENERAL SUMMARY						30	2325	1	1	2	156	1125	1200	1	1	1	1	157	2256	45	25

ROADWAY SUBSUMMARY

DESIGN AGENCY

 DESIGNER
GCB
 REVIEWER
DTC 10/02/24
 PROJECT ID
120384
 SHEET TOTAL
 P.17 | 72