SCI-52-13.33
MODEL: Sheet_SurvFt PAPERSIZE: 34x22 (in.) DATE: 10/6/2026 TIME: 12:24:36 PM PLTDRV: OHDOT_PDF.pltcfg PENTBL: OHDOT_Pen.tbl USER: Bradley.Mercer@dot.ohio.gov
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 09\Scioto\120321\400-Engineering\MOT\Sheets\120321_MN001.dgn
WORKSPACE: OHDOTCEv02 WORKSET: 120321 PRODUCT: OpenRoadsDesigner 24.00.00.205

ITEM 614, MAINTAINING TRAFFIC

A MINIMUM OF ONE LANE OF TRAFFIC IN EACH DIRECTION SHALL BE MAINTAINED AT ALL TIMES BY USE OF THE EXISTING PAVEMENT, THE COMPLETED PAVEMENT, AND TEMPORARY SURFACES USING ITEMS 614 AND 615.

ALL SIDE ROADS, COMMERCIAL AND RESIDENTIAL DRIVES SHALL HAVE ACCESS AT ALL TIMES WITH THE EXCEPTION OF DRIVE 4 WHERE THE CONTRACTOR SHALL COORDINATE WITH THE PROPERTY OWNER A TIME TO REPLACE THE DRIVE PIPE.

BEFORE THE WORK BEGINS, THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER THE NAME(S) AND TELEPHONE NUMBER(S) OF A PERSON OR PERSONS WHO CAN BE CONTACTED TWENTY-FOUR (24) HOURS PER DAY BY THE OHIO DEPARTMENT OF TRANSPORTATION AND ALL INTERESTED POLICE AGENCIES. THIS PERSON OR PERSONS SHALL BE RESPONSIBLE FOR PLACING OR REPLACING NECESSARY TRAFFIC CONTROL DEVICES IN ACCORDANCE WITH THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.

THE CONTRACTOR WILL ADVISE THE DISTRICT PUBLIC INFORMATION OFFICER AT (740) 774-8834, OR FAX (740) 773-2710 FOURTEEN (14) DAYS PRIOR TO THE START OF CONSTRUCTION ACTIVITIES. THE PROJECT ENGINEER WILL PROVIDE ASSISTANCE/CLARIFICATION FOR ANY QUESTIONS.

THE CONTRACTOR SHALL ARRANGE FOR ALL MAINTENANCE OF TRAFFIC OPERATIONS SUCH THAT THERE WILL BE NO OBSTRUCTIONS TO THE CONTINUOUS FLOW OF TRAFFIC. ALL INTERSECTIONS AND DRIVEWAYS SHALL BE OPEN TO TRAFFIC AT ALL TIMES UNLESS OTHERWISE SHOWN IN THE PLAN.

LENGTH AND DURATION OF LANE CLOSURES AND RESTRICTIONS SHALL BE AT THE APPROVAL OF THE ENGINEER. IT IS THE INTENT TO MINIMIZE THE IMPACT TO THE TRAVELING PUBLIC. LANE CLOSURES OR RESTRICTIONS OVER SEGMENTS OF THE PROJECT IN WHICH NO WORK IS ANTICIPATED WITHIN A REASONABLE TIME FRAME, AS DETERMINED BY THE ENGINEER, SHALL NOT BE PERMITTED. THE LEVEL OF UTILIZATION OF MAINTENANCE OF TRAFFIC DEVICES SHALL BE COMMENSURATE WITH THE WORK IN PROGRESS.

NOTIFICATION OF THE TRAFFIC RESTRICTIONS TIME TABLE:

ITEM	*DURATION OF CLOSURE*	*NOTICE DUE TO PERMITS & PIO*
RAMP & ROAD CLOSURES	*>= 2 WEEKS*	*21 CALENDAR DAYS PRIOR TO CLOSURE*
	> 12 HOURS & < 2 WEEKS	*14 CALENDAR DAYS PRIOR TO CLOSURE*
	<= 12 HOURS	*4 CALENDAR DAYS PRIOR TO CLOSURE*
LANE CLOSURES & RESTRICTIONS	*>= 2 WEEKS*	*14 CALENDAR DAYS PRIOR TO CLOSURE*
	< 2 WEEKS	*5 CALENDAR DAYS PRIOR TO CLOSURE*
START OF CONST. & TRAFFIC PATTERN CHANGES	*N/A*	*14 CALENDAR DAYS PRIOR TO CLOSURE*

ANY UNFORSEEN CONDITIONS NOT SPECIFIED IN THE PLANS REQUIRING TRAFFIC RESTRICTIONS SHALL ALSO BE REPORTED TO THE PROJECT ENGINEER USING THE NOTIFICATION TIME TABLE.

ITEM 614, WORK ZONE IMPACT ATTENUATOR FOR 24" WIDE HAZARDS (BIDIRECTIONAL)

THIS ITEM SHALL CONSIST OF FURNISHING AND INSTALLING 8 NON-GATING IMPACT ATTENUATORS. FURNISH AN IMPACT ATTENUATOR FROM THE OFFICE OF ROADWAY ENGINEERING'S APPROVED LIST FOR WORK ZONE IMPACT ATTENUATORS, FROM THE ROADWAY STANDARDS APPROVED PRODUCTS WEB PAGE.

INSTALLATION SHALL BE AT THE LOCATIONS SPECIFIED IN THE PLANS IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS.

THE CONTRACTOR SHALL REPAIR OR REPLACE A DAMAGED UNIT WITHIN 24 HOURS OF A DAMAGING IMPACT.

WHEN BIDIRECTIONAL DESIGNS ARE SPECIFIED, THE CONTRACTOR SHALL SUPPLY APPROPRIATE TRANSITIONS.

WHEN GATING IMPACT ATTENUATORS ARE DESIRED, THE CONTRACTOR SHALL SUBMIT DOCUMENTATION TO THE ENGINEER FOR ACCEPTANCE.

THE COST FOR THE ADDITIONAL BARRIER REQUIRED FOR A GATING IMPACT ATTENUATOR SHALL BE INCLUDED IN THE COST OF THE GATING IMPACT ATTENUATOR.

PAYMENT FOR THE ABOVE WORK SHALL BE MADE AT THE UNIT PRICE BID AND SHALL INCLUDE ALL LABOR, TOOLS, EQUIPMENT AND MATERIALS NECESSARY TO CONSTRUCT AND MAINTAIN A COMPLETE AND FUNCTIONAL IMPACT ATTENUATOR SYSTEM, INCLUDING ALL RELATED BACKUPS, TRANSITIONS, LEVELING PADS, HARDWARE AND GRADING, NOT SEPARATELY SPECIFIED, AS REQUIRED BY THE MANUFACTURER.

PROVIDE TIMING APPROPRIATE FOR THE SIGNAL LOCATION UNDER CONSIDERATION. TYPICAL FLOW RATES ARE DISPLAYED IN TABLE 697-2 IN THE ODOT TRAFFIC ENGINEERING MANUAL (TEM).

THE CONTRACTOR SHALL ALSO DESIGN, FURNISH, INSTALL AND MAINTAIN A TRAFFIC DETECTOR ON EACH TRAFFIC APPROACH WHICH WILL RELIABLY DETECT ALL LEGAL TRAFFIC APPROACHING (BUT NOT LEAVING) THE SIGNAL AS IT PASSES OR WAITS IN THE DESIGNATED DETECTOR ZONE SHOWN IN THE PLANS. DETECTOR DESIGNS WHICH DO NOT PROVIDE RELIABLE DETECTION, FREE FROM FALSE CALLS, SHALL BE IMMEDIATELY REPLACED BY THE CONTRACTOR.

THE TRAFFIC SIGNAL SHALL BE FULLY ACTUATED AND REST IN ALL RED.

TRENCH FOR WIDENING

TRENCH EXCAVATION FOR BASE WIDENING SHALL BE ONLY ON ONE SIDE OF THE PAVEMENT AT A TIME. THE OPEN TRENCH SHALL BE ADEQUATELY MAINTAINED AND PROTECTED WITH DRUMS OR BARRICADES AT ALL TIMES. PLACEMENT OF PROPOSED SUBBASE AND BASE MATERIAL SHALL FOLLOW AS CLOSELY AS POSSIBLE BEHIND EXCAVATION OPERATIONS. THE LENGTH OF WIDENING TRENCH WHICH IS OPEN AT ANY ONE TIME SHALL BE HELD TO A MINIMUM AND SHALL AT ALL TIMES BE SUBJECT TO APPROVAL OF THE ENGINEER.

OVERNIGHT TRENCH CLOSING

THE BASE WIDENING SHALL BE COMPLETED TO A DEPTH OF NO MORE THAN 17 INCHES BELOW THE EXISTING PAVEMENT BY THE END OF EACH WORK DAY. NO TRENCH SHALL BE LEFT OPEN OVERNIGHT EXCEPT FOR A SHORT LENGTH (25 FEET OR LESS) OF A WORK SECTION AT THE END OF THE TRENCH. IN CASE WORK MUST BE SUSPENDED BECAUSE OF INCLEMENT WEATHER OR OTHER REASONS, THE TRENCH FOR THE UNCOMPLETED BASE WIDENING SHALL BE BACKFILLED AT THE DIRECTION OF THE ENGINEER.

FULLY-ACTUATED OPERATION OF WORK ZONE TRAFFIC SIGNAL

THE WORK ZONE SIGNAL CONTROL REQUIRED FOR THIS PROJECT AND SHOWN ON SHEETS P.07 AND P.08, AND TRAFFIC SCDS MT-96.11, 96.20 AND 96.26 SHALL BE FULLY TRAFFIC-ACTUATED AND OPERATE IN A MANNER SIMILAR TO THAT DESCRIBED IN SECTION 733.02 OF THE CONSTRUCTION AND MATERIAL SPECIFICATIONS.

THE INITIAL CONTROLLER TIMING SHALL BE AS FOLLOWS:

	PHASE				
	1	*2*	*3*	*4*	*5*
	NB	*SB*	*SHAWNEE SF*	*DRIVE 2*	*DRIVE 4*
MIN. GREEN	*10*	*10*	*4*	*4*	*4*
EXTENSION	*4*	*4*	*3*	*3*	*3*
MAX. GREEN	*30*	*30*	*12*	*12*	*12*
YELLOW	*3.5*	*3.5*	*3.5*	*3.5*	*3.5*
ALL RED (INTERVAL CLERANCE)	*25*	*25*	*20*	*20*	*20*
RECALL	*OFF*	*OFF*	*OFF*	*OFF*	*OFF*

ALL SIGNALS SHALL REST ON RED.

SUGGESTED CONSTRUCTION PHASING:

PHASE 1:
SET UP TRAFIC CONTROL IN ACCORDANCE WITH SCD MT-97.10 TO CLOSE THE EASTBOUND LANE. SAW CUT THE EXISTING PAVEMENT AND INSTALL ITEM 615 - PAVEMENT FOR MAINTAINING TRAFFIC, CLASS A. SCD MT-101.90 SHALL APPLY.

PHASE 2:
SET UP TRAFFIC CONTROL IN ACCORDANCE WITH SCD'S MT-96.11, MT-96.20, AND SHEET 7 TO CLOSE THE WESTBOUND LANE. COMPLETE ALL PROPOSED WORK TO THE CULVERT AND ROADWAY WITH THE EXCEPTION OF PLACING THE 2ND LIFT OF THE SURFACE COURSE.

PHASE 3:
SET UP TRAFFIC CONTROL IN ACCORDANCE WITH SCD'S MT-96.11, MT-96.20, AND SHEET 8 TO CLOSE THE EASTBOUND LANE. COMPLETE THE REMAINING WORK TO THE CULVERT WITH THE EXCEPTION OF PLACING THE 2ND LIFT OF SURFACE COURSE.

PHASE 4:
SET UP TRAFFIC CONTROL IN ACCORDANCE WITH SCD MT-97.10 TO PLACE THE FINAL LIFT OF ASPHALY CONCRETE SURFACE COURSE

ITEM 614, MAINTAINING TRAFFIC (ESTIMATED QUANTITIES)

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY FOR USE AS DETERMINED BY THE ENGINEER FOR THE MAINTENANCE OF TRAFFIC.

ITEM 614,	*WORK ZONE EDGE LINE, CLASS I, 6"*	*0.28 MILE*
ITEM 615,	*PAVEMENT FOR MAINTAINING TRAFFIC CLASS A*	*22 SQ. YD.*
ITEM 615,	*ROADS FOR MAINTAINING, TRAFFIC*	*LS*
ITEM 622,	*PORTABLE BARRIER, UNANCHORED*	*410 FT.*

DELINEATION OF PORTABLE AND PERMANENT BARRIER

BARRIER REFLECTORS AND OBJECT MARKERS SHALL BE INSTALLED ON ALL PORTABLE BARRIER (PB) USED FOR TRAFFIC CONTROL; AND, ON PERMANENT CONCRETE BARRIER (INCLUDING BRIDGE PARAPETS) LOCATED WITHIN 5 FEET OF THE EDGE OF THE ADJACENT TRAVEL LANE.

BARRIER REFLECTORS SHALL CONFORM TO C&MS 626, EXCEPT THAT THE SPACING SHALL BE AS PER TRAFFIC SCD MT-101.70. OBJECT MARKERS AND THEIR INSTALLATION SHALL CONFORM TO C&MS 614.03 AND SCD MT-101.70. WHEN THE PB OR PERMANENT BARRIER (INCLUDING BRIDGE PARAPETS) CONTAINS GLARE SCREEN, ONE SET OF THREE VERTICAL STRIPES OF SHEETING SHALL BE CONSIDERED EQUIVALENT TO AN OBJECT MARKER, ONE-WAY.

INCREASED BARRIER DELINEATION, AS SPECIFIED HEREIN, SHALL BE INSTALLED ON ALL PB AND PERMANENT CONCRETE BARRIER LOCATED WITHIN 5 FEET OF THE EDGE OF THE TRAVELED LANE UNDER EITHER OF THE FOLLOWING CONDITIONS: ALONG TAPERS AND TRANSITION AREAS; OR ALONG CURVES (OUTSIDE ONLY) WITH DEGREE OF CURVATURE GREATER THAN OR EQUAL TO 3 DEGREES.

THE INCREASED BARRIER DELINEATION SHALL CONSIST OF EITHER DELINEATION PANELS OR THE TRIPLE STACKING OF WORK ZONE BARRIER REFLECTORS.

DELINEATION PANELS SHALL CONSIST OF PANELS OF DELINEATION, APPROXIMATELY 34 INCHES LONG AND 6 INCHES WIDE AND SHALL BE "CRIMPED." PANELS SHALL BE INSTALLED AND SPACED PER TRAFFIC SCD MT-101.70.

TRIPLE-STACKED BARRIER REFLECTORS SHALL CONSIST OF ALIGNING THREE BARRIER REFLECTORS VERTICALLY, AT LOCATIONS WHERE A SINGLE BARRIER REFLECTOR WOULD BE OTHERWISE ATTACHED. THERE SHALL BE NO OPEN SPACE BETWEEN THE ADJACENT BARRIER REFLECTORS. THE TRIPLE-STACKED BARRIER REFLECTORS SHALL CONFORM TO C&MS 626, EXCEPT THAT THEY SHALL BE SPACED AND ALIGNED PER TRAFFIC SCD MT-101.70.

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE PLANS AND CARRIED TO THE GENERAL SUMMARY:

ITEM 614, INCREASED BARRIER BELINEATION	*320 FEET*
ITEM 614, BARRIER REFLECTOR, TYPE 1 (BI-DIRECTIONAL)	*4 EACH*
ITEM 614, BARRIER REFLECTOR, TYPE 3 (BI-DIRECTIONAL)	*8 EACH*
ITEM 614, OBJECT MARKER, TWO-WAY	*12 EACH*

PAYMENT SHALL BE FULL COMPENSATION FOR ALL MATERIAL, LABOR, INCIDENTALS AND EQUIPMENT NECESSARY FOR FURNISHING, INSTALLING, MAINTAINING AND REMOVING EACH OF THE ABOVE ITEMS.

ALONG RUNS OF INCREASED BARRIER DELINEATION WHERE THIS ITEM IS PROVIDED, THE QUANTITY SHALL BE MEASURED AS THE ENTIRE LENGTH OF THE RUN OF INCREASED BARRIER DELINEATION, INCLUDING THE SPACES BETWEEN THE INDIVIDUAL DELINEATION PANELS OR STACKS OF BARRIER REFLECTORS.

DUST CONTROL

THE CONTRACTOR SHALL FURNISH AND APPLY WATER FOR DUST CONTROL AS DIRECTED BY THE ENGINEER. THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED FOR DUST CONTROL PURPOSES:

ITEM 616, WATER 1 M. GAL.

MAINTENANCE OF TRAFFIC GENERAL NOTES

DESIGN AGENCY

DESIGNER BRVM
REVIEWER JAZ 06/09/26
PROJECT ID 120321
SHEET P.06 TOTAL 35

SHEET NUMBER													PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
					P.05	P.06	P.13	P.14	P.28	P.31			01/NHS		EXT	TOTAL			
																		PAVEMENT	
								237					237	252	01500	237	FT	FULL DEPTH PAVEMENT SAWING	
								79					79	301	56000	79	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
								69					69	304	20000	69	CY	AGGREGATE BASE	
								91					91	407	10000	91	GAL	TACK COAT	
					6			3					9	411	10000	9	CY	STABILIZED CRUSHED AGGREGATE	
								61					61	441	70000	61	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22	
								3					3	441	70500	3	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), (DRIVEWAYS)	
																		TRAFFIC CONTROL	
							4						4	621	00100	4	EACH	RPM	
							4						4	621	54000	4	EACH	RAISED PAVEMENT MARKER REMOVED	
							0.08						0.08	642	00104	0.08	MILE	EDGE LINE, 6", TYPE 1	
							0.05						0.05	642	00300	0.05	MILE	CENTER LINE, TYPE 1	
																		MAINTENANCE OF TRAFFIC	
						320							320	614	11630	320	FT	INCREASED BARRIER DELINEATION	
						8							8	614	12384	8	EACH	WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (BIDIRECTIONAL)	
						4							4	614	13310	4	EACH	BARRIER REFLECTOR, TYPE 1, BI-DIRECTIONAL	
						8							8	614	13314	8	EACH	BARRIER REFLECTOR, TYPE 3, BI-DIRECTIONAL	
						12							12	614	13360	12	EACH	OBJECT MARKER, TWO WAY	
						0.28							0.28	614	22010	0.28	MILE	WORK ZONE EDGE LINE, CLASS I, 6"	
						LS							LS	615	10000	LS		ROADS FOR MAINTAINING TRAFFIC	
						22							22	615	20000	22	SY	PAVEMENT FOR MAINTAINING TRAFFIC, CLASS A	
						1							1	616	10000	1	MGAL	WATER	
						410							410	622	41100	410	FT	PORTABLE BARRIER, UNANCHORED	
																		INCIDENTALS	
													LS	614	11000	LS		MAINTAINING TRAFFIC	
													LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
													LS	623	50000	LS		PRECONSTRUCTION SURVEY MONUMENT VERIFICATION AND REPORT	
													LS	623	51000	LS		POST CONSTRUCTION SURVEY MONUMENT VERIFICATION AND REPORT	
													LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY

DESIGNER BRVM

REVIEWER JAZ 06/09/26

PROJECT ID 120321

SHEET P.12 TOTAL 35

SCI-52-13.33

MODEL: Sheet_SurvFt PAPERSIZE: 34x22 (in.) DATE: 10/6/2026 TIME: 12:26:16 PM PLTDRV: OHDOT_PDF.pltcfg PENTBL: OHDOT_Pen.tbl USER: Bradley.Mercer@dot.ohio.gov WORKSPACE: OHDOTCEv02 WORKSET: 120321 PRODUCT: OpenRoadsDesigner 24.00.00.205
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 09\Scioto\120321\400-Engineering\Roadway\Sheets\120321_GG002.dgn