



**ESTIMATED QUANTITIES (01/STR/BR)**

ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUT.	SUPER.	GEN.	SEE SHEET
202	11201	LS		PORTIONS OF STRUCTURE REMOVED, AS PER PLAN			LUMP	2
202	22900	178	SY	APPROACH SLAB REMOVED			178	
202	23500	316	SY	WEARING COURSE REMOVED		138	178	
503	21101	36	CY	UNCLASSIFIED EXCAVATION, AS PER PLAN	36			2
509	10000	7708	LB	EPOXY COATED REINFORCING STEEL	1977	5731		
510	10000	144	EACH	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT	144			
511	31610	28	CY	CLASS QC2 CONCRETE, SUPERSTRUCTURE	28			
511	45710	12	CY	CLASS QC1 CONCRETE, ABUTMENT	12			
512	10050	52	SY	SEALING OF CONCRETE SURFACES (NON-EPOXY)	30	22		
515	12030	8	EACH	PRESTRESSED CONCRETE COMPOSITE BOX BEAM BRIDGE MEMBERS, LEVEL 1, CB17-48, (38'-6" LONG)		8		
516	13600	20	SF	1" PREFORMED EXPANSION JOINT FILLER		20		
516	14020	78	FT	SEM-INTEGRAL ABUTMENT EXPANSION JOINT SEAL	78			
516	31000	64	FT	JOINT SEALER, 705.04			64	
516	43100	32	EACH	ELASTOMERIC BEARING WITH INTERNAL LAMINATES ONLY (NEOPRENE) (7"x11"x3/4")		32		
517	70000	84.83	FT	RAILING (TWIN STEEL TUBE)		84.83		
518	21200	22	CY	POROUS BACKFILL WITH GEOTEXTILE FABRIC	22			
SPECIAL	51822300	97	FT	STEEL DRIP STRIP		97		
518	40000	100	FT	6" PERFORATED CORRUGATED PLASTIC PIPE		100		
518	40012	20	FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE		20		
519	11100	28	SF	PATCHING CONCRETE STRUCTURE	28			
526	15000	142	SY	REINFORCED CONCRETE APPROACH SLABS (T=13")			142	
526	90010	64	FT	TYPE A INSTALLATION			64	
601	20000	8	SY	CRUSHED AGGREGATE SLOPE PROTECTION			8	

ESTIMATED QUANTITIES  
 BRIDGE NO. SEN-19-0197  
 OVER SILVER CREEK

SFN 7400969	
DESIGN AGENCY	
DESIGNER	CHECKER
GLH	DJG
REVIEWER	
DJG 02-28-20	
PROJECT ID	
102934	
SUBSET	TOTAL
3	11
SHEET	TOTAL
P.09	17