

I:\ProjectData\STA\102870_225-0.59\Design\Roadway\Sheets\102870_GG001.dgn_Sheet 10/15/2021 6:51:40 AM rbaughma

SHEET NUM.												PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
2	4	5	9	10	11	12	03/S>2/O T	EXT	TOTAL									
ROADWAY																		
LS							LS	201	11000	LS		CLEARING AND GRUBBING						
		12					12	202	30600	12	SY	CONCRETE MEDIAN REMOVED						
			325				325	202	38000	325	FT	GUARDRAIL REMOVED						
				2	9		11	203	10000	11	CY	EXCAVATION						
				10	19		29	203	20000	29	CY	EMBANKMENT						
			325				325	606	15100	325	FT	GUARDRAIL, TYPE MGS WITH LONG POSTS						
EROSION CONTROL																		
2							2	601	21050	2	SY	TIED CONCRETE BLOCK MAT WITH TYPE 1 UNDERLAYMENT						
63							63	659	00300	63	CY	TOPSOIL						
571							571	659	10000	571	SY	SEEDING AND MULCHING						
0.08							0.08	659	20000	0.08	TON	COMMERCIAL FERTILIZER						
0.12							0.12	659	31000	0.12	ACRE	LIME						
3							3	659	35000	3	MGAL	WATER						
							10,000	832	30000	10,000	EACH	EROSION CONTROL						
DRAINAGE																		
20							20	605	13300	20	FT	6" UNCLASSIFIED PIPE UNDERDRAINS						
20							20	605	31100	20	FT	AGGREGATE DRAINS						
20							20	611	00510	20	FT	6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS						
1							1	611	99710	1	EACH	PRECAST REINFORCED CONCRETE OUTLET						
PAVEMENT																		
			29				29	408	10001	29	GAL	PRIME COAT, AS PER PLAN	2					
			4				4	617	10101	4	CY	COMPACTED AGGREGATE, AS PER PLAN	2					
TRAFFIC CONTROL																		
			4				4	626	00110	4	EACH	BARRIER REFLECTOR, TYPE 2, ONE-WAY						
	140						140	642	30000	140	FT	REMOVAL OF PAVEMENT MARKING						
RETAINING WALLS																		
1							1	SPECIAL	20307502	1	EACH	INCLINOMETER	2,9					
						2,065	2,065	507	00400	2,065	FT	STEEL PILES, MISC.: HP12X53 STEEL BEAM, FURNISHED	2					
						2,100	2,100	524	94501	2,100	FT	DRILLED SHAFTS, 24" DIAMETER, AS PER PLAN	2,9					
MAINTENANCE OF TRAFFIC																		
	100						100	614	11110	100	hour	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE						
	10						10	614	12460	10	EACH	WORK ZONE MARKING SIGN						
	30						30	614	13000	30	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC						
	10						10	614	13310	10	EACH	BARRIER REFLECTOR, TYPE 1, ONE-WAY						
	10						10	614	13350	10	EACH	OBJECT MARKER, ONE WAY						
	0.78						0.78	614	22010	0.78	MILE	WORK ZONE EDGE LINE, CLASS I, 6"						
	3						3	616	10000	3	MGAL	WATER						
	500						500	622	41100	500	FT	PORTABLE BARRIER, UNANCHORED						
INCIDENTALS																		
							LS	614	11000	LS		MAINTAINING TRAFFIC, AS PER PLAN	4					
							LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING						
							LS	624	10000	LS		MOBILIZATION						

GENERAL SUMMARY

STA -62T -4.62

CALCULATED
RCB
CHECKED
TJP