

STATION RANGE			TYPICAL SECTION	SIDE	DISTANCE (D)	AVERAGE WIDTH (W)	SURFACE AREA (A) A=DxW/9	CADD GENERATED AREA	202	204	301	304	407	408	441	617
									PAVEMENT REMOVED	SUBGRADE COMPACTION	ASPHALT CONCRETE BASE, PG64-22, (449)	AGGREGATE BASE 6"	NON-TRACKING TACK COAT (0.06 GAL/SY)	PRIME COAT, AS PER PLAN	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG70-22M	COMPACTED AGGREGATE, AS PER PLAN
					FT	FT	SY	SY	SY	SY	CY	CY	GAL	GAL	CY	CY
591+50.00	TO	592+55.14		LT/RT	105.14	33.50		360.04								
593+33.58	TO	594+50.00		LT/RT	116.42	32.05		386.03								
591+50.00	TO	592+55.14		LT/RT	105.14	40.00	467.29						56.07		38.94	
593+33.58	TO	594+50.00		LT/RT	116.42	40.00	517.42						62.09		43.12	
591+50.00	TO	592+55.14		LT/RT	105.14	40.67	475.08				59.38		28.50			
593+33.58	TO	594+50.00		LT/RT	116.42	40.67	526.05				65.76		31.56			
591+50.00	TO	592+55.14		LT/RT	105.14	41.67	486.76				60.84					
593+33.58	TO	594+50.00		LT/RT	116.42	41.67	538.98				67.37					
591+50.00	TO	592+55.14		LT/RT	105.14	42.67	498.44					83.07				
593+33.58	TO	594+50.00		LT/RT	116.42	42.67	551.92					91.99				
591+50.00	TO	592+55.14		LT/RT	105.14	43.00	502.34									
593+33.58	TO	594+50.00		LT/RT	116.42	43.00	556.23				502.34					
591+50.00	TO	592+55.14		LT/RT	105.14	4.00	46.73						18.69			1.30
593+33.58	TO	594+50.00		LT/RT	116.42	4.00	51.74						20.70			1.44
592+55.14	TO	592+80.14		LT/RT	25.00	41.00	113.89					18.98				
593+08.58	TO	593+33.58		LT/RT	25.00	41.00	113.89					18.98				
592+55.14	TO	592+80.14		LT/RT	25.00	43.00	119.44				119.44					
593+08.58	TO	593+33.58		LT/RT	25.00	43.00	119.44				119.44					
TOTALS CARRIED TO SHEET GENERAL SUMMARY									746.07	1297.45	253.36	213.02	178.23	39.39	82.06	2.74
									746	1297	253	213	178	39	82	3

PAVEMENT CALCS

DESIGN AGENCY  
  
**ENGINEERING ASSOCIATES**  
 INC.  
 1935 EAGLE PASS  
 WOODBURN, OHIO 44691  
 PHONE : (330) 345-6556  
 www.eaohtl.com

DESIGNER  
**JGL**

REVIEWER  
**SDS 07-12-24**

PROJECT ID  
**118713**

SHEET TOTAL  
**P.1 1**