SHEET NUM. 3	4	5	6	8	9	10	PART. 01/STR/05	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
												ROADWAY	
		REDUCED		180			180	202	REDUCED 25500	180	REDUCED SY	WEARING COURSE REMOVED FOR DRIVEWAYS	
	2						2	202	98100	2	EACH	REMOVAL MISC.: BARRIER REFLECTOR	4
84							84	203	10000	84	CY	EXCAVATION	4
274							274	209	60200	274	STA	LINEAR GRADING	
				274			274	209	72000	274	STA	PREPARING SUBGRADE FOR SHOULDER PAVING (SAFETY EDGE)	
	LS						LS	SPECIAL	69091000	LS		AS-BUILT CONSTRUCTION PLANS	4
												EROSION CONTROL	
1.03							1.03	654	11000	1.03	TON	COMMERCIAL FERTILIZER	
7,612							7,612	659	10000	7,612	SY	SEEDING AND MULCHING	
1.57							1.57	659	31000	1.57	ACRE	LIME	
41.1							41.1	659	35000	41.1	MGAL	WATER	
							3,000	832	30000	3,000	EACH	EROSION CONTROL	
												PAVEMENT	
500							500	251	01000	500	SY	PARTIAL DEPTH PAVEMENT REPAIR (441)	
3,000							3,000	252	01500	3,000	FT	FULL DEPTH PAVEMENT SAWING	
500							500	253	01000	500	SY	PAVEMENT REPAIR	
				47,354			47,354	254	01000	47,354	SY	PAVEMENT PLANING, ASPHALT CONCRETE (T = 3")	
84							84	304	20000	84	CY	AGGREGATE BASE	
				7,157			7,157	407	20000	7,157	GAL	NON-TRACKING TACK COAT	
				2,432			2,432	408	10001	2,432	GAL	PRIME COAT, AS PER PLAN	3
				1,689			1,689	441	50100	1,689	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG70-22M PG70-22M (1.25")	
				2,302			2,302	441	50300	2,302	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448)(1.75")	
				338			338	617	10101	338	CY	COMPACTED AGGREGATE, AS PER PLAN	3
				3			3	618	43000	3	MILE	RUMBLE STRIPES, CENTER LINE (ASPHALT CONCRETE)	
				13,676			13,676	874	20000	13,676	FT	LONGITUDINAL JOINT PREPARATION	
												TRAFFIC CONTROL	
					171		171	621	00100	171	EACH	RPM	
					137		137	621	54000	137	EACH	RAISED PAVEMENT MARKER REMOVED	
	6						6	626	00110	6	EACH	BARRIER REFLECTOR, TYPE 2 (BIDIRECTIONAL)	
						5.18	5.18	646	10010	5.18	MILE	EDGE LINE, 6"	
						2.59	2.59	646	10200	2.59	MILE	CENTER LINE	
												MAINTENANCE OF TRAFFIC	
		100					100	614	11110	100	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
			18				18	614	12460	18	EACH	WORK ZONE MARKING SIGN	
		20					20	614	13000	20	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	
		4					4	614	18601	4	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	6
		5.18					5.18	614	21100	5.18	MILE	WORK ZONE CENTER LINE, CLASS I, 642 PAINT	
		2.59					2.59	614	21550	2.59	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
		5.18					5.18	614	22360	5.18	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT	
												INCIDENTALS	
							LS	614	11000	LS		MAINTAINING TRAFFIC	
							6	619	16010	6	MNTH	FIELD OFFICE, TYPE B	
							LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
							LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY

DESIGNER KMK

REVIEWER RMM 11-13-23

PROJECT ID 118985

SHEET P.7 TOTAL 10

TRU-45-23.76

MODEL: Sheet_SurvFt PAPERSIZE: 34x22 (in.) DATE: 12/10/2024 TIME: 4:20:53 PM USER: rbisesi
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 04\Trumbull\118985\400-Engineering\Roadway\Sheets\118985_GG001.dgn