

SHEET NUM.													PART.	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
4	5	10	11	12	13	58	67	79	83	89	109		01/ENH/28						
LS													LS	201	11000	LS		ROADWAY	
			1,096										1,096	202	23000	1,096	SY	CLEARING AND GRUBBING	
		8,399											8,399	202	30000	8,399	SF	PAVEMENT REMOVED	
		69											69	202	35100	69	FT	WALK REMOVED	
		3											3	202	58100	3	EACH	PIPE REMOVED, 24" DIAMETER AND UNDER	
	1												1	202	98100	1	EACH	CATCH BASIN REMOVED	5
																		REMOVAL MISC.:EXISTING METAL POLE AND FOUNDATION	
						192	50	93	10	24	223		592	203	10000	592	CY	EXCAVATION	
						17							17	203	20000	17	CY	EMBANKMENT	
			1,291										1,291	204	10000	1,291	SY	SUBGRADE COMPACTION	
		26,928											26,928	608	10000	26,928	SF	4" CONCRETE WALK	
		2,282											2,282	608	13000	2,282	SF	6" CONCRETE WALK	
		1,839											1,839	608	52000	1,839	SF	CURB RAMP	
		2											2	638	10500	2	EACH	FIRE HYDRANT REMOVED AND RESET	
		7											7	638	10800	7	EACH	VALVE BOX ADJUSTED TO GRADE	
	10	4											14	638	10900	14	EACH	SERVICE BOX ADJUSTED TO GRADE	5
		1											1	638	98000	1	EACH	WATER WORK, MISC.:WATER MANHOLE ADJUTED TO GRADE	19
		16											16	SPECIAL	69050350	16	EACH	MAILBOX REMOVED AND RESET, AS PER PLAN	4
																		EROSION CONTROL	
109													109	659	00300	109	CY	TOPSOIL	
973													973	659	00500	973	SY	SEEDING AND MULCHING, CLASS 1	
49													49	659	14000	49	SY	REPAIR SEEDING AND MULCHING	
49													49	659	15000	49	SY	INTER-SEEDING	
0.14													0.14	659	20000	0.14	TON	COMMERCIAL FERTILIZER	
0.21													0.21	659	31000	0.21	ACRE	LIME	
6													6	659	35000	6	MGAL	WATER	
													15,000	832	30000	15,000	EACH	EROSION CONTROL	
																		DRAINAGE	
		5											5	611	00200	5	FT	4" CONDUIT, TYPE C	
		36											36	611	04600	36	FT	12" CONDUIT, TYPE C	
		20											20	611	06100	20	FT	15" CONDUIT, TYPE C	
		10											10	611	07600	10	FT	18" CONDUIT, TYPE C	
		3											3	611	98470	3	EACH	CATCH BASIN, NO. 2-2B	
		3											3	611	99574	3	EACH	MANHOLE, NO. 3	
																		PAVEMENT	
			1,191										1,191	452	10050	1,191	SY	6" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC MS	
			100										100	452	12050	100	SY	8" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC MS	
		3											3	625	10481	3	EACH	LIGHT POLE, AESTHETIC, AS PER PLAN	5
																		LIGHTING	
																		TRAFFIC CONTROL	
				2									2	625	32000	2	EACH	GROUND ROD	
				38									38	630	02100	38	FT	GROUND MOUNTED SUPPORT, NO. 2 POST	
				3									3	630	85100	3	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
				3									3	630	86002	3	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
				2									2	630	97700	2	EACH	SIGNING, MISC.:SOLAR POWERED RECTANGULAR RAPID FLASHING BEACON (RRFB) SIGN ASSEMBLY	5
				2									2	632	64020	2	EACH	PEDESTAL FOUNDATION	
				1,062									1,062	644	00620	1,062	FT	CROSSWALK LINE, 12"	
				25		1,062							25	644	20800	25	FT	YIELD LINE	
													LS	614	11000	LS		INCIDENTALS	
													LS	619	16010	5	MNTH	MAINTAINING TRAFFIC	
													5	619	16010	5		FIELD OFFICE, TYPE B	
													LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
													LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY

THE THRASHER GROUP

DESIGNER

NCT

REVIEWER

CJD 12/16/24

PROJECT ID

117393

SHEET

P.06

TOTAL

140

TUS-HERITAGE DRIVE SIDEWALKS

MODEL: Sheet_SunFL_PAPER/SIZE: 34x22 (in.) DATE: 3/24/2025 TIME: 1:36:54 PM USER: nhtompson
R:\080T80-11038.00 - Village of Tuscarawas - TUS-Heritage Sidewalks\117393\400-Engineering\Traffic\Sheets\117393 TS001.dgn

[illegible]

MODEL: CLP_6 - Plan 5 PAPER SIZE: 34x22 (in.) DATE: 3/24/2025 TIME: 1:37:24 PM USER: nthompson
R:\0801780-11038.00 - Village of Tuscarawas - TUS-Heritage Sidewalks\117393\400-Engineering\Roadway\Sheets\117393_GP005.dgn



PLAN AND PROFILE - EAST CHERRY STREET STA. 209+00.00 TO STA. 214+00.00		
DESIGN AGENCY THE THRASHER GROUP		
DESIGNER NCT		
REVIEWER CJD 12/16/24		
PROJECT ID 117393		
SHEET	TOTAL	
P.18	140	