

# Estimated Quantities

## Instructions

The requested information on this form is necessary the creation of the official Engineer's Estimate. If any of the following items are listed as "Lump Sum" in the construction plans, specific quantities must be provided. This form is for Consultant use only. Districts shall input this information into the ODOT Plan Package Submittal SharePoint site.

|              |        |
|--------------|--------|
| CRS          | PID    |
| WAR-350-8.30 | 116664 |

Item 201 - Tree and Stump Removals (*List by Size*):

NA

Item 202 - Structure(s)/Portions of Structure(s) Removed (*List Structures & Associated Quantities*):

NA

Item 502 - Structure(s) for Maintaining Traffic (*List Structures & Associated Quantities*):

NA

Item 503 - Unclassified Excavation (*Cubic Yards*):

UNCLASSIFIED EXCAVATION - LS (581 CY)

Item 509 - Reinforcing Steel (List Structure(s), Item (*i.e., Wall, Deck, Parapet*), & Pounds of Steel):

NA

Item 513 - Structural Steel (List Structure(s), Item (*i.e., Wall, Deck, Parapet*), & Pounds of Steel):

NA

Item 514 - Steel Surfaces to be Painted (*List Structures & Square Footage of Steel*):

NA

Item 518 - Porous Backfill (*Cubic Yards*):

NA

Item 615 - Roads and Pavement for Maintaining Traffic (*Earthwork & Pavement Cubic Yards*):

NA

Miscellaneous Items:

ROADWAY MISC.: GABION WALL CONSTRUCTION ACCESS DRIVE - LS (288 CY EXCAVATION, 140 CY EMBANKMENT, 82 CY AGGREGATE BASE, 476 SY SEEDING AND MULCHING)